

PROJECT NO.	SHEET NO.	TOTAL NO.
5CR.10921.57	8	

### SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW CY	SHOULDER GRADING SMI	INCIDENTAL STONE BASE TONS	2" MILLING SY	SURFACE COURSE, S9.5C TONS	ASPHALT BINDER FOR PLANT MIX TON	PATCHING EXISTING PAVEMENT TONS	SEALING EXISTING PAVEMENT CRACKS & JOINTS LB	ADJUST MANHOLES EA	PORTABLE LIGHTING LS	TEMP. SILT FENCE LF	WATTLE LF	SEED & MULCHING AC	INDUCTIVE LOOP LF
5CR.10921.57	Wake	1	US 70 BUS	JOINT AT I 40 TO JOHNSTON CO	2	4	MD	NO	NO	3.75	60-146	1,500	15.00	375	180,274	22,255	1,313	750		3		1,090	2,730	10.90	2,692
	Wake	2	US 70	LIMIT OF BRG PROJ TO SR 2026 - HAMMOND RD	2	4	MD	NO	NO	0.69	67-146	142	1.42	70	45,733	5,643	333	170			0.17	103	260	1.03	3,235
	Wake	3	US 401	NC 55 TO ENNIS ST	3	5	MU	NO	YES	1.97	60-73				79,397	9,360	552	493	14,563		0.47				5,755
	Wake	4	US 401	ENNIS ST TO HARNETT CO	1	2	2WU	NO	NO	3.23	28-50	304	3.04	152	70,943	8,779	518	323			0.36	220	550	2.20	4,632
<b>TOTAL FOR PROJ NO. 5CR.10921.57</b>										<b>9.64</b>		<b>1,946</b>	<b>19.46</b>	<b>597</b>	<b>376,347</b>	<b>46,037</b>	<b>2,716</b>	<b>1,736</b>	<b>14,563</b>	<b>3</b>	<b>1.00</b>	<b>1,413</b>	<b>3,540</b>	<b>14.13</b>	<b>16,314</b>
<b>GRAND TOTAL</b>										<b>9.64</b>		<b>1,946</b>	<b>19.46</b>	<b>597</b>	<b>376,347</b>	<b>46,037</b>	<b>2,716</b>	<b>1,736</b>	<b>14,563</b>	<b>3</b>	<b>1.00</b>	<b>1,413</b>	<b>3,540</b>	<b>14.13</b>	<b>16,314</b>