



NOTES:

1. CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE PLANS. IF DISCREPANCIES EXIST CONTACT THE ENGINEER. TO DETERMINE HOW TO PROCEED WITH RESPLICING.
2. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
3. INSTALL FIBER THROUGH 2" COUPLING LOCATED AT THE TOP OF THE POLE. SEAL WITH HEAT SHRINK TUBING.
4. NOTIFY THE CITY OF FAYETTEVILLE TRANSPORTATION ENGINEER, MR. LEE JERNIGAN, AT (910) 433-1153 24 HOURS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEMS COMMUNICATION CABLE. NOTIFY THE CITY TRANSPORTATION ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY.

	COMMUNICATION CABLE AND CONDUIT ROUTING PLANS DIVISION 6 CUMBERLAND COUNTY FAYETTEVILLE		SEAL GREGORY A. FULLER 4/13/2015
	PLAN DATE: APRIL 2015 PREPARED BY: A.J. SKUCE	REVIEWED BY: <i>Neil Avery</i> REVIEWED BY: G. A. FULLER	
750 N. Greenfield Pkwy., Garner, NC 27529 SCALE 0 30	CADD Filename:		