Approximate quantities only. Shoulder borrow, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

PROJ. REFERENCE NO.	SHEET NO.
R-5206	X-1A

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station Dr4	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+34.38	0	0	41+50.00	35	194	67+50.00	21	5	10+32.61	0	9
15+50.00	0	0	42+00.00	0	259	68+00.00	8	7	10+50.00	2	8
16+00.00	367	0	42+50.00	0	487	68+50.00	9	8	10+62.50	1	0
16+50.00	447	0	43+00.00	44	444	69+00.00	12	9			
17+00.00	380	1	43+50.00	82	115	69+50.00	6	83			
17+50.00	367	5	44+00.00	129	3	70+00.00	3	236			
18+00.00	446	25	44+23.00	128	0	70+50.00	0	393			
18+50.00	446	66	44+50.00	244	0	71+00.00	23	446			
19+00.00	286	94	45+00.00	849	0	71+50.00	34	212			
19+50.00	123	79	45+50.00	1287	0	72+00.00	53	2			
20+00.00	134	32	46+00.00	1276	5	72+50.00	95	1			
20+50.00	171	3	46+50.00	746	16	73+00.00	59	0			
21+00.00	127	57	47+00.00	206	29	73+50.00	11	1			
21+50.00	42	326	47+50.00	55	28	74+00.00	8	1			
22+00.00	3	844	48+00.00	51	16	74+50.00	9	0			
22+50.00	6	678	48+50.00	34	10	75+00.00	13	0			
23+00.00	3	119	49+00.00	7	16	75+08.00	1	0			
23+50.00	8	17	49+50.00	16	38						
24+00.00	102	4	50+00.00	52	50	**Station Y**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**			
24+50.00	181	4	50+50.00	66	58						
25+00.00	177	7	51+00.00	64	71	10+25.00	0	0			
25+50.00	172	14	51+50.00	82	64	10+50.00	11	0			
26+00.00	169	9	52+00.00	91	68	10+75.00	12	0			
26+50.00	171	1	52+50.00	77	67						
27+00.00	191	1	53+00.00	37	32	**Station Dr1**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**			
27+50.00	107	2	53+50.00	8	6	10+25.00	0	0			
28+00.00	3	32	54+00.00	12	1	10+50.00	0	113			
28+50.00	45	66	54+50.00	20	0	10+69.00	0	194			
29+00.00	200	36	55+00.00	29	0						
29+50.00	363	0	55+50.00	35	1	**Station Dr2**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**			
30+00.00	675	0	56+00.00	32	5	10+25.00	0	0			
30+50.00	939	0	56+50.00	21	5	10+50.00	0	383			
31+00.00	788	30	57+00.00	10	6	10+75.00	0	450			
31+50.00	529	55	57+50.00	7	11	11+00.00	0	399			
32+00.00	440	26	58+00.00	12	9	11+25.00	0	225			
32+50.00	579	1	58+50.00	24	2	11+45.00	1	47			
33+00.00	530	0	59+00.00	22	1						
33+50.00	250	6	59+50.00	15	3	**Station Dr3**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**			
34+00.00	193	16	60+00.00	15	2	10+25.00	0	0			
34+50.00	316	18	60+50.00	28	3	10+50.00	6	5			
35+00.00	331	15	61+00.00	38	7						
35+50.00	232	16	61+50.00	44	7	**Station Dr4**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**			
36+00.00	243	33	62+00.00	37	7	10+11.00	0	0			
36+50.00	387	37	62+50.00	13	22	10+25.00	0	10			
37+00.00	547	55	63+00.00	4	26						
37+50.00	675	59	63+50.00	2	18						
38+00.00	445	26	64+00.00	1	16						
38+50.00	88	117	64+50.00	22	6						
39+00.00	16	275	65+00.00	66	2						
39+50.00	7	305	65+50.00	100	4						
40+00.00	7	247	66+00.00	119	5						
40+50.00	9	204	66+50.00	94	3						
41+00.00	40	187	67+00.00	43	2						