PROJ. REFERENCE NO.	SHEET NO.
B-5136	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L (DET)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+50.00	0	0
14+00.00	5	37
14+50.00	10	72
15+00.00	10	80
15+50.00	9	98
16+00.00	6	133
16+50.00	5	217
17+00.00	6	296
17+50.00	5	331
18+00.00	3	336
18+50.00	2	473
19+00.00	1	821
19+50.00	0	1323
20+00.00	0	1816
20+50.00	0	2176
21+00.00	0	2322
21+39.75	0	1830

Station L (DET)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
23+06.15	0	0
23+50.00	0	867
24+00.00	0	962
24+50.00	0	886
25+00.00	0	663
25+50.00	0	381
26+00.00	1	194
26+50.00	2	137
27+00.00	2	136
27+50.00	1	67

Station L(L2)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
17+00.00	0	0
17+50.00	0	17
18+00.00	0	30
18+50.00	3	18
19+00.00	5	9
19+50.00	2	17
20+00.00	0	13
20+50.00	4	2

Station L(L2)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
23+50.00	0	0
24+00.00	2	3
24+50.00	1	9
25+00.00	0	34
25+50.00	0	95
26+00.00	0	157

Station L(L2)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
26+50.00	0	143
27+00.00	3	80
27+50.00	0	26

Station L (RT.)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+75.00	0	0
13+00.00	6	5
13+50.00	15	31
14+00.00	26	20
14+50.00	43	0
15+00.00	24	21
15+50.00	7	53
16+00.00	5	99
16+50.00	7	171
17+00.00	8	208

Station L (RT.)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
27+00.00	0	0
27+50.00	0	410
28+00.00	0	264
28+50.00	1	130
29+00.00	3	110
29+50.00	4	92
30+00.00	6	55
30+50.00	5	16

Station L RT PHASE 3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
17+00.00	0	0
17+50.00	6	111
18+00.00	2	270
18+50.00	0	589
19+00.00	0	717
19+50.00	0	848
20+00.00	0	941
20+26.04	0	503

Station L RT PHASE 3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
23+00.00	0	0
23+50.00	0	707
24+00.00	0	731
24+50.00	0	753
25+00.00	0	743
25+50.00	0	685
26+00.00	3	612
26+50.00	5	576

Station L RT PHASE 3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
27+00.00	2	505
27+50.00	0	410
28+00.00	0	265
28+50.00	1	130
29+00.00	3	109
29+50.00	4	92
30+00.00	6	55
30+50.00	5	16

Station L PHASE 4	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
18+00.00	0	8
18+50.00	0	51
19+00.00	0	160
19+50.00	0	264
20+00.00	0	356
20+50.00	0	353

Station L PHASE 4	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
23+00.00	0	0
23+50.00	0	365
24+00.00	0	573
24+50.00	0	508
25+00.00	0	357
25+50.00	0	191
26+00.00	6	75
26+50.00	16	24
27+00.00	17	14
27+50.00	7	27
28+00.00	1	25
28+50.00	3	6
29+00.00	4	0
29+50.00	4	0
30+00.00	3	0

Station L LT(PHASE 5)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+75.00	0	0
13+00.00	0	20
13+50.00	4	83
14+00.00	3	85
14+50.00	0	90
15+00.00	0	108
15+50.00	0	135
16+00.00	0	168
16+50.00	2	133
17+00.00	3	79
17+50.00	1	81
18+00.00	0	114

Station L LT(PHASE 5)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
18+50.00	0	183
19+00.00	32	182
19+50.00	288	147
20+00.00	733	169
20+50.00	1037	205
21+00.00	1150	283

Station L LT(PHASE 5)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
23+50.00	0	0
24+00.00	844	235
24+50.00	751	188
25+00.00	511	212
25+50.00	244	225
26+00.00	71	197
26+50.00	6	146
27+00.00	0	96
27+50.00	0	44
28+00.00	0	7
28+50.00	1	31
29+00.00	3	53
29+50.00	5	39
30+00.00	6	31
30+50.00	6	30
31+00.00	4	15

Station Ey4	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+60.00	0	0
10+80.00	3	16

Station Drv2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+70.00	0	0
10+80.00	0	18
10+90.00	0	8