



• DOWELS SHALL BE PLACED IN THE SAME HORIZONTAL PLANE AS THE TOP AND BOTTOM SLAB REINFORCING STEEL.

THE QUANTITY OF #4 JI BARS ON THE BILL OF MATERIAL IS BASED ON 1'-0" CENTERS. JI BARS SHALL BE PLACED AT EACH VERTICAL STUD ANCHOR, IN THE EVENT THAT THE NUMBER OF VERTICAL STUD ANCHORS EXCEEDS THE NUMBER OF JI BARS SPECIFIED, ADDITIONAL JI BARS WILL NOT BE REQUIRED.

PROJECT NO. B-5136  
CABARRUS COUNTY  
 STATION: 12+74.92 -L-

SHEET 1 OF 9

STATE OF NORTH CAROLINA  
 DEPARTMENT OF TRANSPORTATION  
 RALEIGH

**SUPERSTRUCTURE  
 PLAN OF SPANS  
 STAGE I**

SPAN A



Designed by:  
 V. A. Patel  
 10/15/2015

REVISIONS						SHEET NO. S-15
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 75
2			4			

DRAWN BY : P.S. ADKINS DATE : 7/14/14  
 CHECKED BY : K.D. LAYNE DATE : 11/14/14  
 DESIGN ENGINEER OF RECORD: V.A. PATEL DATE : 1/5/15

18-FEB-2015 14:03  
 R:\Structures\Plans\B5136.SD.S\*\_01.dgn  
 thcarroll

**SPAN A**