| PROJ. REFERENCE NO. | SHEET NO. |
|---|---|
| B-5105 | X-1A |

# STATE OF NORTH CAROLINA
# DIVISION OF HIGHWAYS

**Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing and removal of existing pavement will be paid for at the lump sum price for "Grading".**

**NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT**

## *CROSS-SECTION SUMMARY*

| Station L | Uncl. Exc. (cu. yd.) | Embt (cu. yd.) |
|---|---|---|
| 12+00.00 | 0 | 0 |
| 12+50.00 | 10 | 19 |
| 13+00.00 | 17 | 62 |
| 13+50.00 | 9 | 125 |
| 14+00.00 | 3 | 188 |
| 14+50.00 | 2 | 324 |
| 15+00.00 | 0 | 321 |
| 15+50.00 | 2 | 192 |
| 16+00.00 | 38 | 228 |
| 16+50.00 | 71 | 267 |
| 17+00.00 | 62 | 266 |
| 17+50.00 | 35 | 449 |
| 18+00.00 | 26 | 681 |
| 18+50.00 | 27 | 793 |
| 19+00.00 | 12 | 883 |
| 19+18.00 | 2 | 330 |

| Station L | Uncl. Exc. (cu. yd.) | Embt (cu. yd.) |
|---|---|---|
| 20+98.00 | 0 | 0 |
| 21+00.00 | 0 | 41 |
| 21+50.00 | 0 | 765 |
| 22+00.00 | 0 | 322 |
| 22+50.00 | 0 | 119 |
| 23+00.00 | 1 | 54 |
| 23+50.00 | 6 | 30 |
| 24+00.00 | 42 | 36 |
| 24+50.00 | 104 | 25 |
| 25+00.00 | 140 | 20 |
| 25+25.00 | 37 | 5 |

| Station Y | Uncl. Exc. (cu. yd.) | Embt (cu. yd.) |
|---|---|---|
| 11+25.00 | 0 | 0 |
| 11+50.00 | 7 | 2 |
| 11+75.00 | 10 | 10 |

| Station EY1 | Uncl. Exc. (cu. yd.) | Embt (cu. yd.) |
|---|---|---|
| 11+00.00 | 0 | 0 |
| 11+25.00 | 4 | 4 |