Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the contract lump sum price for "Grading".

PROJ. REFERENCE NO.	SHEET NO.
U-5008	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMET COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	undercut
10+64.82	0	0	
11+00.00	55	0	
11+50.00	131	0	
12+00.00	129	0	
12+50.00	148	0	
13+00.00	123	2	
13+50.00	96	4	
14+00.00	120	8	
14+50.00	95	25	
15+00.00	24	162	
15+50.00	0	462	
16+00.00	0	758	
16+50.00	0	1107	
17+00.00	0	1693	
17+50.00	0	2611	
18+00.00	0	3565	
18+50.00	0	4368	
19+00.00	0	5084	
19+50.00	0	5520	
20+00.00	0	5668	
20+05.51	0	541	
20+50.00		BRIDGE	
21+00.00		BRIDGE	
21+50.00		BRIDGE	
22+00.00		BRIDGE	
22+50.00		BRIDGE	
23+00.00		BRIDGE	
23+50.00		BRIDGE	
24+00.00		BRIDGE	
24+50.00		BRIDGE	
25+00.00		BRIDGE	
25+50.00		BRIDGE	
26+00.00		BRIDGE	
26+50.00		BRIDGE	
27+00.00		BRIDGE	
27+50.00		BRIDGE	
28+00.00		BRIDGE	
28+50.00		BRIDGE	
28+51.64	0	6894	
29+00.00	0	2721	
29+50.00	0	2493	
30+00.00	0	2231	
30+50.00	0	1889	
31+00.00	0	1507	
31+50.00	0	1118	
32+00.00	0	783	
32+50.00	0	509	
33+00.00	3	286	
33+50.00	24	143	
34+00.00	54	99	
34+50.00	72	80	
35+00.00	75	75	
35+50.00	79	78	

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	undercut
36+00.00	84	74	
36+50.00	88	75	
37+00.00	90	109	
37+50.00	85	122	
38+00.00	75	91	
38+50.00	60	83	
39+00.00	49	73	
39+00.43	0	0	

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	undercut
10+54.32	0	0	
10+75.00	1	0	
11+00.00	10	21	
11+25.00	17	38	
11+50.00	24	27	
11+61.97	2	12	

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+31.50	0	0
10+50.00	0	260
11+00.00	0	405
11+50.00	18	134
11+81.18	0	0

Station Y3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	undercut
8+68.60	0	0	
9+00.00	0	0	
9+50.00	2	0	
10+00.00	45	0	
10+50.00	71	7	228
11+00.00	75	7	215
11+50.00	115	0	263
12+00.00	154	0	311
12+50.00	152	7	321
13+00.00	138	7	342
13+50.00	191	1	353
14+00.00	225	1	342
14+50.00	214	4	309
14+89.87	158	3	

Station Y3Rev	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	undercut
12+08.12	0	0	
12+50.00	33	6	
13+00.00	70	25	
13+50.00	62	33	
14+00.00	106	29	
14+50.00	139	22	
15+00.00	95	32	
15+50.00	60	41	
16+00.00	120	23	
16+50.00	206	17	
17+00.00	195	18	
17+50.00	140	26	
18+00.00	110	42	
18+50.00	50	210	
19+00.00	0	538	
19+21.11	0	149	

Station Y4	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	undercut
10+17.00	0	0	
10+50.00	42	12	
11+00.00	94	19	
11+50.00	128	10	
12+00.00	63	22	
12+50.00	50	17	
13+00.00	51	16	
13+50.00	42	28	
14+00.00	18	89	
14+50.00	0	245	
15+00.00	0	322	
15+50.00	0	195	
16+00.00	12	61	

Station Y5	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	undercut
12+56.01	0	0	
13+00.00	20	4	
13+50.00	42	23	
14+00.00	40	37	
14+50.00	74	23	
15+00.00	104	7	
15+50.00	76	14	
15+99.86	25	18	

Station Y6	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	undercut
10+63.13	0	0	
10+75.00	5	11	
11+00.00	21	46	
11+25.00	31	40	
11+50.00	20	22	
11+74.00	0	0	

Station Y7	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	undercut
10+33.97	0	0	
10+50.00	26	13	
11+00.00	86	41	
11+50.00	106	37	
12+00.00	133	38	
12+50.00	100	49	
13+00.00	38	126	
13+50.00	4	339	
13+58.89	0	85	
14+00.00	0	370	
14+50.00	0	410	
15+00.00	0	356	
15+50.00	1	250	
16+00.00	4	159	
16+27.90	4	73	
16+50.00	4	57	
17+00.00	6	144	
17+50.00	1	178	
18+00.00	0	167	
18+50.00	92	64	
19+00.00	149	1	
19+50.00	151	1	
19+75.98	97	0	

Station Y8	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	undercut
11+19.18	0	0	
11+50.00	2	6	
12+00.00	8	13	
12+50.00	20	5	
13+00.00	43	2	
13+50.00	46	1	
14+00.00	29	1	
14+49.18	18	1	

Station DR2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	undercut
10+00.00	0	0	
10+25.00	0	144	
10+50.00	0	92	
10+75.00	2	41	
11+00.00	12	7	