PROJ. REFERENCE NO.	SHEET NO.
U-3338B	X-1C

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station L (RT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
38+50.00	31	13
38+70.97	13	10
39+00.00	17	14
39+50.00	20	20
39+70.97	4	25
40+00.00	6	28
40+10.00	4	1

Station Y1 (LT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+80.62	0	0
13+00.00	5	12
13+50.00	7	34
14+00.00	4	50
14+24.00	2	29

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
18+80.50	0	0
19+00.00	0	58
19+50.00	126	140
19+63.68	49	35
20+00.00	69	89
20+50.00	69	123
21+00.00	54	107
21+50.00	52	75
22+00.00	50	56
22+50.00	51	49
23+00.00	56	46
23+50.00	54	39
24+00.00	29	32
24+50.00	11	32
25+00.00	11	44
25+50.00	11	49
26+00.00	11	42
26+50.00	11	39
27+00.00	11	44
27+50.00	11	52
28+00.00	11	50
28+50.00	11	44
29+00.00	11	32
29+27.40	3	6

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+40.39	0	0
10+84.24	26	19
11+00.00	8	8
11+07.47	4	4
11+50.00	26	16

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+00.00	17	13
12+50.00	6	6
12+57.47	0	0

Station L (RT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
40+10.00	0	0
40+37.98	0	14
40+50.00	1	4
41+00.00	10	6
41+50.00	11	8
42+00.00	20	7
42+40.03	23	8
42+50.00	6	3
43+00.00	25	38
43+40.03	20	87
43+50.00	7	15
44+00.00	45	8
44+35.53	24	12
44+50.00	7	3
44+80.04	13	1
45+00.00	9	1
45+18.94	10	5
45+50.00	14	18
45+75.46	6	20
46+00.00	7	18
46+36.05	21	16
46+50.00	11	4
47+00.00	58	8
47+36.05	42	7
47+50.00	11	5
48+00.00	41	14
48+36.05	38	4
48+50.00	17	1
49+00.00	52	10
49+50.00	39	14
50+00.00	24	17
50+50.00	15	39
51+00.00	8	63
51+50.00	5	78
52+00.00	7	94
52+50.00	4	98
53+00.00	4	62
53+50.00	5	32
54+00.00	7	21
54+50.00	15	3
55+00.00	19	2
55+37.90	15	2
55+48.30	4	1
55+50.00	0	0
56+00.00	22	4
57+50.00	53	28

Station L (RT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
58+00.00	25	10
58+50.00	49	1
58+62.01	12	0
59+00.00	33	0
59+50.00	23	11
60+00.00	5	24
60+50.00	6	25
61+00.00	6	26
61+50.00	2	42
62+00.00	8	51
62+50.00	8	55
63+00.00	1	63
63+50.00	1	77
64+00.00	4	67
64+50.00	15	39
65+00.00	22	28
65+50.00	25	18
66+00.00	32	10
66+11.00	7	2

Station Y4	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+48.00	0	0
10+89.49	26	9
11+00.00	6	2
11+01.51	1	0
11+10.00	2	1

Station Y6 (RT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
9+31.00	0	0
9+50.00	1	9
9+68.59	4	8
10+00.00	13	9
10+32.91	28	12
10+50.00	20	6
11+00.00	51	9
11+50.00	34	7
12+00.00	20	8
12+50.00	20	7
13+00.00	25	2
13+32.91	18	1
13+50.00	9	1
14+00.00	23	7
14+25.00	10	5
14+50.00	13	3
14+75.00	16	1
15+00.00	17	1
15+25.00	18	2
15+50.00	18	3
15+75.00	18	2

Station Y6 (RT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+00.00	18	2
16+25.00	17	1
16+50.00	17	1
17+00.00	17	1
17+50.00	4	10
18+00.00	4	35
18+50.00	0	62
19+00.00	0	107
19+50.00	0	125
20+00.00	2	65
20+50.00	3	10
21+00.00	1	0
21+50.00	7	3
21+88.16	12	2
22+00.00	4	1
22+50.00	17	3
23+00.00	15	4
23+50.00	8	9
24+00.00	3	15
24+50.00	1	21
25+00.00	1	22
25+50.00	3	16
26+00.00	3	15
26+50.00	1	23
27+00.00	0	27
27+29.60	0	16
27+50.00	0	11
28+00.00	1	27
28+50.00	0	28
29+00.00	0	30
29+30.00	0	17
29+50.00	0	12
30+00.00	0	33
30+50.00	0	35
31+00.00	0	35
31+50.00	1	25
32+00.00	4	16
32+50.00	5	14
33+00.00	6	10
33+50.00	3	3
34+70.00	0	0

Station L (RT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
68+00.00	0	0
68+17.95	0	15
68+37.13	1	14
68+50.00	2	10
68+67.95	2	23
69+00.00	1	41
69+17.95	1	15
69+37.12	0	18

Station L (RT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
69+50.00	0	13
70+00.00	2	37
70+12.11	1	9
70+50.00	8	23
70+77.14	8	2
71+00.00	5	0
71+50.00	27	10
72+00.00	33	17
72+50.00	23	23
73+00.00	9	45
73+50.00	0	70
74+00.00	0	73
74+50.00	0	63
75+00.00	1	54
75+50.00	6	40
75+65.34	6	8
76+00.00	26	13
76+50.00	38	16
76+65.34	9	7
77+00.00	23	16
77+15.34	12	7
77+50.00	29	15
77+80.29	25	9
78+00.00	14	7
78+17.15	15	9
78+50.00	25	17
78+72.19	10	11
79+00.00	19	12
79+22.55	14	8
79+37.16	6	5
79+50.00	5	5
80+00.00	36	16
80+22.55	20	5
80+50.00	29	4
81+00.00	61	9
81+50.00	62	10
82+00.00	57	15
82+22.55	15	7
82+50.00	15	13
83+00.00	17	46
83+22.55	14	19
83+50.00	42	12
83+88.97	70	14
84+00.00	12	5
84+50.00	15	14
84+62.55	1	0
84+71.16	0	0
85+00.00	4	3
85+26.34	3	18
85+39.07	0	14
85+50.00	2	9
86+00.00	19	30
86+25.00	4	24

Station L (RT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
86+50.00	6	22
87+00.00	11	35
87+50.00	1	35
87+75.00	1	14
88+00.00	5	10
88+50.00	11	15
89+00.00	1	31
89+50.00	1	41
90+00.00	1	43
90+25.00	2	17
90+50.00	3	11
91+00.00	7	19
91+20.00	4	4
91+50.00	3	3
93+00.00	3	0
93+50.00	6	1
94+00.00	6	2
94+50.00	3	0
96+97.55	0	0

Station Y8	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+02.29	0	0
15+50.00	5	25
15+62.33	2	6
16+00.00	9	13
16+50.00	15	8
17+00.00	22	2
17+02.29	1	0

Station Y9	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+39.50	0	0
10+89.54	24	24
11+00.00	5	5
11+50.00	18	18
11+70.83	6	4

Station Y12	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+39.50	0	0
10+84.80	27	15
11+00.00	8	4
11+35.76	8	3