HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554

DATE: JANUARY 19, 2015

PROJECT REFERENCE NO.	SHEET NO.
P-4900A	EC-3
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	L	9+25	17+00	LT	2420
4	L	15+50	19+00	RT	1095
5	L	17+00	18+00	LT	315
5	L	19+00	20+73	RT	540
5	L	24+50	34+50	RT	2315
5	L	28+00	34+00	LT	1455
6	L	39+11	40+69	LT	160
6	L	40+00	49+00	RT	2805
7	L	46+50	51+00	LT	1405
7	L	53+00	58+00	LT	1410
7	L	49+00	54+90	RT	1840
8	L	58+00	70+50	RT	3865
8	L	63+50	73+00	LT	2305
9	L	70+50	87+00	RT	4275
9	L	77+00	81+02	LT	975
9	L	82+50	88+00	LT	1330
10	L	87+00	100+00	RT	3385
10	L	88+00	100+00	LT	3090
11	L	100+00	102+00	LT	625
11	L	100+00	109+18	RT	2865
11	L	105+50	112+00	LT	1575
12	L	109+18	128+00	RT	5060
12	L	112+00	120+00	LT	2245
12	L	12550	128+00	LT	780
13	L	128+00	132+00	LT	1250
				SUBTOTAL	49,385
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					5,411
				TOTAL	54,796
				SAY	55,500

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
				SUBTOTAL	0
	ADDITIONAL PSRM TO BE INSTALLED				13925
				TOTAL	13925
				SAY	13925