D3CA0274448

COMPUTED BY: JL MOORE DATE: 6/1/2015

CHECKED BY: PA JORDAN DATE: 6/1/15

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS

PROJECT NO.	SHEET NO.
W-5103	3D-3

Note: Invert Elevations indicated are for Bid Purposes only and shall not be used for project construction stakeout.
See "Standard Specifications For Roads and Structures, Section 300-5".

SUB-REGIONAL & REGIONAL
LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48 INCHES & UNDER)

STATION	LOCATION (LT, RT, OR CL)	STRUCTURE NO. FROM	STRUCTURE NO. TO	TOP ELEVATION	INVERT ELEVATION	INVERT ELEVATION	SLOPE CRITICAL	DRAINAGE PIPE (RCP, CSP, CAAP, HDPE, or PVC) SIZE 12"	15"	18"	24"	30"	36"	42"	48"
								THICKNESS OR GAUGE							
-L-															
200+00	LT	1592		41.6	36.8										
198+00	CL	1581		42.9	39.9										
201+90	LT	1593		40.9	36.4										
		1581	1592		39.9	37.3									
		1592	1593		36.8	36.2									
205+40	LT	1613		42.4	39.2										
205+40	RT	1614		41.9	38.7										
204+50	CL	1615		42.2	38.5										
204+00	LT	1616		42.1	38.3										
203+50	LT	1617		41.9	38.2										
		1613	1614		39.2	38.7									
		1614	1615		38.7	38.5	X								
		1615	1616		38.5	38.3	X								
		1616	1617		38.3	38.2	X								
		1617	1503		38.2	36.9	X								
		1503	1505		36.4	36.0	X								
206+50	RT	1612		41.7	39.5										
207+00	RT	1611		41.9	39.3										
208+00	CL	1610		41.9	39.0										
208+50	RT	1609		43.0	38.9										
209+35	CL	1607		43.2	38.1										
213+00	CL	1601		47.9	45.2										
211+80	RT	1602		46.5	43.3										
211+35	LT	1603		46.0	42.8										
210+90	LT	1604		44.8	41.6										
209+35	LT	1606		42.6	38.1										
		1612	1611		39.5	39.3	X								
		1611	1610		39.3	39.0	X								
		1610	1609		39.0	38.9	X								
		1609	1607		38.9	38.6	X								
		1601	1602		45.2	43.3	X								
		1602	1603		43.3	42.8	X								
		1603	1604		42.8	41.6	X								
		1604	1607		41.6	40.2	X								
		1605	1606		38.2	38.1	X								
		1606	1607		38.1	38.1	X								
		1607	1608		38.1	37.9	X								
205+00	RT	1618											288		
		804	807		41.6	40.2	X								
		805	806		38.2	38.1	X								
		806	807		38.1	38.1	X								
		807	808		38.1	37.9	X								
205+00	RT	899											288		
SHEET TOTALS													576		

DO NOT USE RCP	DO NOT USE CSP	DO NOT USE CAAP	DO NOT USE HDPE	C.S.PIPE 12"	15"	18"	24"	30"	36"	42"	48"	R.C.PIPE CLASS III 12"	15"	18"	24"	30"	36"	42"	48"	R.C.PIPE CLASS IV 12"	15"	18"	24"	30"	36"	42"
				.064	.064	.064	.064	.079	.079	.109	.109																
																						200				
																							190			
																						20				
																						29				
																						48				
																						48				
																						48				
																						160				
																									84	