


**This electronic collection of documents is provided
for the convenience of the user
and is Not a Certified Document –**

**The documents contained herein were originally issued
and sealed by the individuals whose names and license
numbers appear on each page, on the dates appearing
with their signature on that page.**

**This file or an individual page
shall not be considered a certified document.**

TIP PROJECT: W-5516




STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PLAN FOR PROPOSED
HIGHWAY EROSION CONTROL

ROWAN COUNTY

**LOCATION: OLD BEATTY FORD ROAD FROM WEST
OF BOSTIAN ROAD INTERSECTION TO
LENTZ ROAD**

**TYPE OF WORK: GRADING, PAVING, DRAINAGE, TRAFFIC
CONTROL, SIGNING, PAVEMENT MARKINGS
AND STRUCTURES**



STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	W-5516	EC-1	
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
44105.1.FD	HSIP-1221(18)	PE	

EROSION AND SEDIMENT CONTROL MEASURES

Std. #	Description	Symbol
1630.03	Temporary Silt Ditch	---
1630.05	Temporary Diversion	--- TD ---
1605.01	Temporary Silt Fence	
1606.01	Special Sediment Control Fence	--- Z ---
1622.01	Temporary Berms and Slope Drains	--- B ---
1630.02	Silt Basin Type B	--- S ---
1633.01	Temporary Rock Silt Check Type-A	--- R ---
	Temporary Rock Silt Check Type-A with Matting and Polyacrylamide (PAM)	--- R/P ---
1633.02	Temporary Rock Silt Check Type-B	--- R/B ---
	Wattle / Coir Fiber Wattle	--- W ---
	Wattle / Coir Fiber Wattle with Polyacrylamide (PAM)	--- W/P ---
1634.01	Temporary Rock Sediment Dam Type-A	--- RSDA ---
1634.02	Temporary Rock Sediment Dam Type-B	--- RSDA ---
1635.01	Rock Pipe Inlet Sediment Trap Type-A	--- RPIST ---
1635.02	Rock Pipe Inlet Sediment Trap Type-B	--- RPIST ---
1630.04	Stilling Basin	--- SB ---
1630.06	Special Stilling Basin	--- SSB ---
	Rock Inlet Sediment Trap:	
1632.01	Type A	A
1632.02	Type B	B
1632.03	Type C	C
	Skimmer Basin	--- SB ---
	Tiered Skimmer Basin	--- TSB ---
	Infiltration Basin	--- IB ---

**THIS PROJECT CONTAINS
EROSION CONTROL PLANS
FOR CLEARING AND
GRUBBING PHASE OF
CONSTRUCTION.**

**THIS PROJECT HAS
BEEN DESIGNED TO
SENSITIVE WATERSHED
STANDARDS.**

**HIGH QUALITY WATER(S) EXIST
ON THIS PROJECT**


*High Quality Water Zone(s) Exist
From Sta. 135+00 -L- @ Sta. 11+15 -Y3-
to Sta. 141+70 -L- @ Sta. 16+75 -Y3-
Refer To E. C. Special Provisions
for Special Considerations.*

ALEXANDER SNIDER, P.E.
ROADSIDE ENVIRONMENTAL ENGINEER

3064
LEVEL III CERTIFICATION NUMBER

STACEY H. BAILEY, P.E.
ROADSIDE ENVIRONMENTAL PROJECT ENGINEER

3074
LEVEL III CERTIFICATION NUMBER



ROADSIDE ENVIRONMENTAL UNIT
DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

LEVEL III CERTIFIED BY:
STACEY H. BAILEY, PE
CERTIFICATION NUMBER: 3074
ISSUED: MAY 26, 2015

**THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY
WITH THE REGULATIONS SET FORTH BY THE
NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE AUGUST 3, 2011
ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND
NATURAL RESOURCES DIVISION OF WATER QUALITY.**

Prepared In the Office of:

ICA ENGINEERING

5121 KINGDOM WAY
SUITE 100
RALEIGH, NC 27607
919-851-6066
NC LIC. NO. F-0258

2012 STANDARD SPECIFICATIONS


Roadway Standard Drawings

The following roadway english standards as appear in "Roadway Standard Drawings"- Roadway Design Unit - N. C. Department of Transportation - Raleigh, N. C., dated January 2012 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

1604.01 Railroad Erosion Control Detail	1632.01 Rock Inlet Sediment Trap Type A
1605.01 Temporary Silt Fence	1632.02 Rock Inlet Sediment Trap Type B
1606.01 Special Sediment Control Fence	1632.03 Rock Inlet Sediment Trap Type C
1607.01 Gravel Construction Entrance	1633.01 Temporary Rock Silt Check Type A
1622.01 Temporary Berms and Slope Drains	1633.02 Temporary Rock Silt Check Type B
1630.01 Riser Basin	1634.01 Temporary Rock Sediment Dam Type A
1630.02 Silt Basin Type B	1634.02 Temporary Rock Sediment Dam Type B
1630.03 Temporary Silt Ditch	1635.01 Rock Pipe Inlet Sediment Trap Type A
1630.04 Stilling Basin	1635.02 Rock Pipe Inlet Sediment Trap Type B
1630.05 Temporary Diversion	1640.01 Coir Fiber Baffle
1630.06 Special Stilling Basin	1645.01 Temporary Stream Crossing
1631.01 Matting Installation	

6/1/2015 5:17:20 PM \\s:\ncad\w5516_hyd_esc_tsh.dgn

TEMPORARY ROCK SILT CHECK TYPE 'A' WITH EXCELSIOR MATTING AND POLYACRYLAMIDE (PAM)




PLAN

NOTES


USE EXCELSIOR FOR MATTING MATERIAL AND ANCHOR MATTING SECTION AT TOP AND BOTTOM WITH CLASS B STONE.

PRIOR TO POLYACRYLAMIDE (PAM) APPLICATION, OBTAIN A SOIL SAMPLE FROM PROJECT LOCATION, AND FROM OFFSITE MATERIAL, AND ANALYZE FOR APPROPRIATE PAM FLOCCULANT TO BE APPLIED TO EACH ROCK SILT CHECK.


INITIALLY APPLY 3.5 OUNCES OF POLYACRYLAMIDE (PAM) TO TOP OF MATTING SECTION AND AFTER EVERY RAINFALL EVENT THAT EQUALS OR EXCEEDS 0.50 INCHES.



INSET A



SECTION A-A






SECTION B-B

*T = 12" MIN., 18" MAX.

NOT TO SCALE

WATTLE WITH POLYACRYLAMIDE (PAM) DETAIL



NOTES:

USE MINIMUM 12 IN. DIAMETER EXCELSIOR WATTLE.

USE 2 FT. WOODEN STAKES WITH A 2 IN. BY 2 IN. NOMINAL CROSS SECTION.

ONLY INSTALL WATTLE(S) TO A HEIGHT IN DITCH SO FLOW WILL NOT WASH AROUND WATTLE AND SCOUR DITCH SLOPES AND AS DIRECTED.

INSTALL A MINIMUM OF 2 UPSLOPE STAKES AND 4 DOWNSLOPE STAKES AT AN ANGLE TO WEDGE WATTLE TO BOTTOM OF DITCH.


PROVIDE STAPLES MADE OF 0.125 IN. DIAMETER STEEL WIRE FORMED INTO A U SHAPE NOT LESS THAN 12" IN LENGTH.

INSTALL STAPLES APPROXIMATELY EVERY 1 LINEAR FOOT ON BOTH SIDES OF WATTLE AND AT EACH END TO SECURE IT TO THE SOIL.





INSTALL MATTING IN ACCORDANCE WITH SECTION 1631 OF THE STANDARD SPECIFICATIONS.

PRIOR TO POLYACRYLAMIDE (PAM) APPLICATION, OBTAIN A SOIL SAMPLE FROM PROJECT LOCATION, AND FROM OFFSITE MATERIAL, AND ANALYZE FOR APPROPRIATE PAM FLOCCULANT TO BE APPLIED TO EACH WATTLE.

INITIALLY APPLY 2 OUNCES OF ANIONIC OR NEUTRALLY CHARGED PAM OVER WATTLE WHERE WATER WILL FLOW AND 1 OUNCE OF PAM ON EACH SIDE OF WATTLE. REAPPLY PAM AFTER EVERY RAINFALL EVENT THAT IS EQUAL TO OR EXCEEDS 0.50 IN.



SKIMMER BASIN WITH BAFFLES DETAIL




COIR FIBER MAT ANCHOR OPTIONS

NOTES

1. SEED AND PLACE MATTING FOR EROSION CONTROL ON INTERIOR AND EXTERIOR SIDESLOPES.
2. LIMIT EARTH DIKE HEIGHT TO 5 FT.
3. FOR BASIN DEPTH OF 3 FT., THE MINIMUM BASIN WIDTH SHALL BE 9 FT.
4. DETERMINE PRIMARY SPILLWAY WEIR LENGTH (FT.) USING $Q/0.4$, WHERE Q IS FLOW RATE (CFS) INTO BASIN.
5. PLASTIC SLOPE DRAIN PIPE AT INLET OF BASIN MAY BE REPLACED BY FILTRATION GEOTEXTILE OR TARP AS DIRECTED.
6. SOIL STABILIZATION GEOTEXTILE FOR PRIMARY SPILLWAY SHALL BE ONE CONTINUOUS PIECE OF MATERIAL OR OVERLAPPED 18 IN. (MIN.).

NOT TO SCALE

TIERED SKIMMER BASIN DETAIL



2" x 2" (nominal) WOODEN STAKE

#10 STEEL REINFORCEMENT BAR

1" (nominal) STAPLE

COIR FIBER MAT ANCHOR OPTIONS

NOTES

1. SEED AND PLACE MATTING FOR EROSION CONTROL ON INTERIOR AND EXTERIOR SIDESLOPES OF BASINS.
2. LIMIT HEIGHT OF EARTH DIKES TO 5 FT.
3. ADDITIONAL MODIFIED SILT BASINS TYPE 'B' MAY BE NEEDED DEPENDING ON SLOPE.
4. FOR BASIN DEPTHS OF 3FT., THE MINIMUM BASIN WIDTHS SHALL BE 9 FT.
5. DETERMINE PRIMARY SPILLWAY LENGTHS (FT.) USING $Q/0.4$, WHERE Q IS FLOW RATE (CFS) INTO UPPER BASIN.
6. SOIL STABILIZATION GEOTEXTILE FOR PRIMARY SPILLWAYS SHALL BE ONE CONTINUOUS PIECE OF MATERIAL OR OVERLAPPED 18 IN. (MIN.).

NOT TO SCALE

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA



SOIL STABILIZATION TIMEFRAMES

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

LEVEL III CERTIFIED BY:
STACEY H. BAILEY, PE
CERTIFICATION NUMBER: 3074
ISSUED: MAY 26, 2015

- NOTE:
PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE:
PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE:
CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE:
ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING RW OR EASEMENT.
- NOTE:
ESTABLISH SUFFICIENT BUFFER FOR WATER COURSE.

CLEARING AND GRUBBING
EROSION CONTROL FOR
CONSTRUCTION SHEET 4



10-22-14 REVISED STATION/OFFSET CALLOUTS ON PARCELS 1 & 2


5/28/2015 cadd\w5516_hyd_erosion_c&g_psh_04.dgn ICA ENGINEERING, INC

MATCHLINE -L- STA. 25+00.00 SEE SHEET NO. 5

PAVEMENT REMOVAL

5/14/99



LEVEL III CERTIFIED BY:
 STACEY H. BAILEY, PE
 CERTIFICATION NUMBER: 3074
 ISSUED: SEPTEMBER 15, 2014



-MATCHLINE- L- STA. 25 + 00.00 SEE SHEET NO. 4

-MATCHLINE- L- STA. 38 + 00.00 SEE SHEET NO. 6

CLEAN WATER DIVERSION



- NOTE: PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE: PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE: CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE: ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING R/W OR EASEMENT.
- NOTE: ESTABLISH SUFFICIENT BUFFER FOR WATER COURSE.

CLEARING AND GRUBBING EROSION CONTROL FOR CONSTRUCTION SHEET 5



9/10/2014 9:08:10 AM \\cadd\w5516_hyd_erosion_c&g_psh_05.dgn
 ICA ENGINEERING, INC.

5/14/99

NAD 83/NSRS 2007

ICA Engineering
 5121 Kingdom Way,
 Suite 100
 Raleigh, NC 27607
 NC License No: F-0258

PROJECT REFERENCE NO.	SHEET NO.
W-5516	EC-5A/CONST.5
RW SHEET NO.	
ROADSIDE ENVIRONMENTAL PROJECT ENGINEER	
LEVEL III CERTIFIED BY: STACEY H. BAILEY, PE CERTIFICATION NUMBER: 3074 ISSUED: SEPTEMBER 15, 2014	



NOTES

- CULVERT CONSTRUCTION SHALL BE PERFORMED IN ONLY DRY OR ISOLATED SECTIONS OF CHANNEL.
- IMPERVIOUS DIKES ARE TO BE USED TO ISOLATE WORK FROM STREAM FLOW AS NECESSARY.
- ALL GRADED AREAS SHALL BE STABILIZED WITHIN 24 HOURS.
- MAINTENANCE OF STREAM FLOW OPERATIONS SHALL BE INCIDENTAL TO THE WORK. THIS INCLUDES POLYETHYLENE SHEETING, DIVERSION PIPES, PUMPS AND HOSES.
- PUMPS AND HOSES SHALL BE SUFFICIENT SIZE TO DEWATER THE WORK AREA.
- THE CONTRACTOR SHALL NOT PUMP SEDIMENT-LADEN WATER DIRECTLY INTO STREAM. FOR DEWATERING OF CULVERT SITES, THE CONTRACTOR SHALL FILTER SEDIMENT-LADEN WATER THROUGH STILLING BASIN AND/OR SPECIAL STILLING BASIN.


CONSTRUCTION SEQUENCE

- EXCAVATE TEMPORARY DIVERSION CHANNEL (~160 LF), INSTALL 24" TEMPORARY PIPE (130 LF) AND IMPERVIOUS DIKES (54 LF) AS SHOWN. DIVERT CHANNEL FLOW THROUGH TEMPORARY DIVERSION DITCHES AND TEMPORARY PIPE.
- CONSTRUCT STILLING BASIN TO SIZE SPECIFIED AT LOCATION SHOWN.
- CONSTRUCT 2 @ 11' x 8' RCBC w/SILLS AND BEVELED INLET.
- CONSTRUCT UPSTREAM AND DOWNSTREAM CHANNEL IMPROVEMENTS AND PLACE REQUIRED RIP RAP.
- REMOVE IMPERVIOUS DIKES, STILLING BASIN, TEMPORARY PIPE, AND TEMPORARY DITCHES.
- CONSTRUCT PROPOSED ROADWAY.

9/10/2014 10:41:00 AM C:\Users\icaadmin\Documents\Projects\5516\hyd_const_seq.dgn

5/14/99


LEVEL III CERTIFIED BY:
 STACEY H. BAILEY, PE
 CERTIFICATION NUMBER: 3074
 ISSUED: SEPTEMBER 15, 2014



-MATCHLINE- L- STA. 38+00.00 SEE SHEET NO. 5

-MATCHLINE- L- STA. 51+00.00 SEE SHEET NO. 7

54 x 27 x 3
 1.5 inch Skimmer
 with 1.125 inch
 Orifice Diameter
 11 ft. weir
 ID 6.1




- NOTE: PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE: PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE: CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE: ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING RW OR EASEMENT.
- NOTE: ESTABLISH SUFFICIENT BUFFER FOR WATER COURSE.

CLEARING AND GRUBBING
 EROSION CONTROL FOR
 CONSTRUCTION SHEET 6

9/10/2014 9:08:16 AM cadd\w5516_hyd_erosion_c&g_psh_06.dgn ICA ENGINEERING, INC.

LEVEL III CERTIFIED BY:
 STACEY H. BAILEY, PE
 CERTIFICATION NUMBER: 3074
 ISSUED: SEPTEMBER 15, 2014


ICA
 Engineering
 5121 Kingdom Way,
 Suite 100
 Raleigh, NC 27607
 NC License No. F0258



-Y-
 PI Sta 44+63.14
 $\Delta = 12' 28" 03.6" (LT)$
 $D = 0' 29" 15.8"$
 $L = 2556.26'$
 $T = 1283.20'$
 $R = 11,747.41'$

- NOTE: PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE: PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE: CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE: ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING RW OR EASEMENT.
- NOTE: ESTABLISH SUFFICIENT BUFFER FOR WATER COURSE.

CLEAN WATER DIVERSION
 (Not to Scale)



CLEARING AND GRUBBING EROSION CONTROL FOR CONSTRUCTION SHEET 7


9/10/2014 \\cadd\w5516_hyd_erosion_c&g_pesh_07.dgn
 5/14/99
 ICA ENGINEERING, INC.

5/14/99

9/10/2014
C:\Users\jacobd\w5516_hyd_erosion_c&g_psh_08.dgn
JACOBS ENGINEERING, INC.

ICA Engineering
 5121 Kingdom Way,
 Suite 100
 Raleigh, NC 27607
 NC License No: F-0258

PROJECT REFERENCE NO.	SHEET NO.
W-5516	EC-8/CONST.8
RW SHEET NO.	
ROADSIDE ENVIRONMENTAL PROJECT ENGINEER	
LEVEL III CERTIFIED BY: STACEY H. BAILEY, PE CERTIFICATION NUMBER: 3074 ISSUED: SEPTEMBER 15, 2014	



78 x 39 x 3
 2 inch Skimmer
 with 1.625 inch
 Orifice Diameter
 23 ft. weir
 ID 8.1

- NOTE: PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE: PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE: CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE: ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING RW OR EASEMENT.
- NOTE: ESTABLISH SUFFICIENT BUFFER FOR WATER COURSE.


CLEARING AND GRUBBING
 EROSION CONTROL FOR
 CONSTRUCTION SHEET 8

5/14/99



5121 Kingdom Way,
Suite 100
Raleigh, NC 27607
NC License No: F-0258

PROJECT REFERENCE NO.	SHEET NO.
W-5516	EC-9/CONST.9
RW SHEET NO.	
ROADSIDE ENVIRONMENTAL PROJECT ENGINEER	
LEVEL III CERTIFIED BY: STACEY H. BAILEY, PE CERTIFICATION NUMBER: 3074 ISSUED: SEPTEMBER 15, 2014	



81 x 40 x 3
2 inch Skimmer
with 1.625 inch
Orifice Diameter
25 ft. weir
ID 9.1

47 x 23 x 3
1.5 inch Skimmer
with 0.875 inch
Orifice Diameter
8 ft. weir
ID 9.2


36 x 18 x 3
4 ft. weir
ID 9.3

42 x 20 x 3
4 ft. weir
ID 9.4

32 x 16 x 3
4 ft. weir
ID 9.5

-MATCHLINE- L- STA. 77+00.00 SEE SHEET NO. 8

-MATCHLINE- L- STA. 90+00.00 SEE SHEET NO. 10





- NOTE: PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE: PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE: CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE: ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING RW OR EASEMENT.
- NOTE: ESTABLISH SUFFICIENT BUFFER FOR WATER COURSE.

CLEARING AND GRUBBING
EROSION CONTROL FOR
CONSTRUCTION SHEET 9

9/10/2014
C:\Users\jbailes\Documents\5516_hyd_erosion_c&g_psh_09.dgn
ICA ENGINEERING, INC.

REVISIONS
 10-22-14 REVISED STATION/OFFSET CALLOUTS ON PARCEL 9





- NOTE:
PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE:
PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE:
CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE:
ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING RW OR EASEMENT.
- NOTE:
ESTABLISH SUFFICIENT BUFFER FOR WATER COURSE.

CLEARING AND GRUBBING EROSION CONTROL FOR CONSTRUCTION SHEET 10

10/24/2014
 C:\projects\5516\hyd_erosion_c&g_psh_10.dgn
 ICA ENGINEERING, INC.

5/14/99

PROJECT REFERENCE NO.	SHEET NO.
W-5516	EC-II/CONST.II
RW SHEET NO.	
ROADSIDE ENVIRONMENTAL PROJECT ENGINEER	
LEVEL III CERTIFIED BY: STACEY H. BAILEY, PE CERTIFICATION NUMBER: 3074 ISSUED: MAY 26, 2015	



- NOTE: PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE: PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE: CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE: ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING RW OR EASEMENT.
- NOTE: ESTABLISH SUFFICIENT BUFFER FOR WATER COURSE.


CLEARING AND GRUBBING
 EROSION CONTROL FOR
 CONSTRUCTION SHEET 11

6/1/2015 10:51:13 AM C:\Users\psh\OneDrive\Engineering\5516\hyd_erosion_c&g_psh.11.dgn

5/14/99
9/10/2014
I:\projects\5516\add\w5516-hyd-erosion_c&g_psh_12.dgn
P&E ENGINEERING, INC.


ICA Engineering
5121 Kingdom Way,
Suite 100
Raleigh, NC 27607
NC License No: P-0258

PROJECT REFERENCE NO.	SHEET NO.
W-5516	EC-12/CONST.12
RW SHEET NO.	
ROADSIDE ENVIRONMENTAL PROJECT ENGINEER	
LEVEL III CERTIFIED BY: STACEY H. BAILEY, PE CERTIFICATION NUMBER: 3074 ISSUED: SEPTEMBER 15, 2014	



-L-
PI Sta. 133+40.55
$\Delta = 80^{\circ} 04' 24.5''$ (RT)
D = 6' 21" 58.3"
L = 1,257.79'
T = 756.17'
R = 900.00'
SE = .06
DS = 50 MPPH

- NOTE: PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
 - NOTE: PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
 - NOTE: CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
 - NOTE: ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING RW OR EASEMENT.
 - NOTE: ESTABLISH SUFFICIENT BUFFER FOR WATER COURSE.
- CLEARING AND GRUBBING EROSION CONTROL FOR CONSTRUCTION SHEET 12




5121 Kingdom Way,
Suite 100
Raleigh, NC 27607
NC License No: F-0258

PROJECT REFERENCE NO.	SHEET NO.
W-5516	EC-13/CONST.13

RW SHEET NO.
ROADSIDE ENVIRONMENTAL PROJECT ENGINEER

LEVEL III CERTIFIED BY:
STACEY H. BAILEY, PE
CERTIFICATION NUMBER: 3074
ISSUED: SEPTEMBER 15, 2014



- NOTE:
PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE:
PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE:
CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE:
ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING RW OR EASEMENT.
- NOTE:
ESTABLISH SUFFICIENT BUFFER FOR WATER COURSE.


CLEARING AND GRUBBING
EROSION CONTROL FOR
CONSTRUCTION SHEET 13

72 x 26 x 3
1.5 inch Skimmer
with 1.25 inch
Orifice Diameter
14 ft. weir
ID 13.1

PAVEMENT REMOVAL

FOR -L- PROFILE, SEE SHEET 19


9/10/2014 1:55:11 PM C:\Users\jbailey\Documents\Projects\W-5516-hyd-erosion.cad\g_psh_13.dgn



5121 Kingdom Way,
Suite 100
Raleigh, NC 27607
NC License No: F-0258

PROJECT REFERENCE NO.	SHEET NO.
W-5516	EC-14/CONST.14
RW SHEET NO.	
ROADSIDE ENVIRONMENTAL PROJECT ENGINEER	
LEVEL III CERTIFIED BY: STACEY H. BAILEY, PE CERTIFICATION NUMBER: 3074 ISSUED: SEPTEMBER 15, 2014	

NAD 83/NSRS 2007



73 x 36 x 3
1.5 inch Skimmer
with 1.375 inch
Orifice Diameter
20 ft. weir
ID 14.1

END TIP PROJECT W-5516
END CONSTRUCTION
-L- POC 141+70.00

PI Sta 133+40.55	PI Sta 141+27.9	PI Sta 142+93.87
$\Delta = 80^{\circ} 04' 24.5" (RT)$	$\Delta = 13^{\circ} 29' 54.2" (LT)$	$\Delta = 4^{\circ} 41' 00.0" (LT)$
D = 6' 21" 58.3"	D = 6' 52" 41.7"	D = 2' 48" 31.0"
L = 1,257.79'	L = 196.25'	L = 166.75'
T = 756.17'	T = 98.58'	T = 83.42'
R = 900.00'	R = 833.00'	R _s = 2,040.00'
SE = .08	SE = .06	
DS = 50 MPH	DS = 50 MPH	

- NOTE:
PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE:
PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE:
CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE:
ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING RW OR EASEMENT.
- NOTE:
ESTABLISH SUFFICIENT BUFFER FOR WATER COURSE.

CLEARING AND GRUBBING
EROSION CONTROL FOR
CONSTRUCTION SHEET 14




9/10/2014 1:54:14 PM C:\projects\w5516-hyd-erosion\c&g\psh_14.dgn ICA ENGINEERING, INC

8/10/2014 9:10:20 AM cadd:\w5516_hyd_erosion_c&g_psh15_02B.dgn
 ICA ENGINEERING, INC.



PROJECT REFERENCE NO.	SHEET NO.
W-5516	EC-15/CONST.2B
RW SHEET NO.	
ROADSIDE ENVIRONMENTAL PROJECT ENGINEER	
LEVEL III CERTIFIED BY: STACEY H. BAILEY, PE CERTIFICATION NUMBER: 3074 ISSUED: SEPTEMBER 15, 2014	

- NOTE:
 PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE:
 PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE:
 CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE:
 ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING RW OR EASEMENT.
- NOTE:
 ESTABLISH SUFFICIENT BUFFER FOR WATER COURSE.
- CLEARING AND GRUBBING EROSION CONTROL FOR CONSTRUCTION SHEET 2B



-SAC_ALN-			
PI Sta 10+74.34	PI Sta 11+92.06	PI Sta 14+98.77	PI Sta 15+97.87
$\Delta = 26^{\circ}09'21.6"$ (RT)	$\Delta = 8^{\circ}45'47.1"$ (RT)	$\Delta = 8^{\circ}27'48.8"$ (LT)	$\Delta = 5^{\circ}43'07.5"$ (LT)
$D = 17^{\circ}54'17.8"$	$D = 9^{\circ}32'57.5"$	$D = 5^{\circ}08'19.1"$	$D = 11^{\circ}27'33.0"$
$L = 146.08'$	$L = 91.77'$	$L = 164.54'$	$L = 49.91'$
$T = 74.34'$	$T = 45.97'$	$T = 82.42'$	$T = 24.97'$
$R = 320.00'$	$R = 600.00'$	$R = 1,115.00'$	$R = 500.00'$
PI Sta 17+06.78	PI Sta 18+46.73		
$\Delta = 12^{\circ}46'38.3"$ (LT)	$\Delta = 4^{\circ}03'27.3"$ (LT)		
$D = 7^{\circ}38'22.0"$	$D = 3^{\circ}34'51.5"$		
$L = 167.25'$	$L = 113.31'$		
$T = 83.98'$	$T = 56.68'$		
$R = 750.00'$	$R = 1,600.00'$		


-MATCHLINE- -SAC_ALN- STA. 21 + 50.00 SEE SHEET NO. 2-C

5/14/99



5121 Kingdom Way,
Suite 100
Raleigh, NC 27607
NC License No: F-0258

PROJECT REFERENCE NO.	SHEET NO.
W-5516	EC-16/CONST.2C
RW SHEET NO.	
ROADSIDE ENVIRONMENTAL PROJECT ENGINEER	
LEVEL III CERTIFIED BY: STACEY H. BAILEY, PE CERTIFICATION NUMBER: 3074 ISSUED: SEPTEMBER 15, 2014	



-MATCHLINE- -SAC ALN- STA. 21+50.00 SEE SHEET NO. 2-B



S 70° 30' 23.5" E
-SAC ALN-

-SAC ALN-
 PI Sta 29+08.04
 $\Delta = 15^{\circ} 55' 10.3"$ (LT)
 $D = 5^{\circ} 22' 47.6"$
 $L = 295.9'$
 $T = 148.9'$
 $R = 1,065.00'$

- NOTE:
PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE:
PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE:
CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE:
ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING RW OR EASEMENT.
- NOTE:
ESTABLISH SUFFICIENT BUFFER FOR WATER COURSE.

CLEARING AND GRUBBING
EROSION CONTROL FOR
CONSTRUCTION SHEET 2C

8/10/2014 8:10:20 AM C:\Users\psh16\OneDrive\Documents\Projects\5516\hyd_erosion_c&g_psh16_02C.dgn



-Y-
 $PI\ Sta\ 44+63.14$
 $\Delta = 12' 28'' 03.6" (LT)$
 $D = 0' 29'' 15.8"$
 $L = 2556.26'$
 $T = 1283.20'$
 $R = 11,747.41'$







DECK DRAINS REQUIRED
 6" DIAMETER SCUPPERS ON 12' CENTERS
 FROM STA. 57+20 TO STA. 58+16 RT. & LT.
 FROM STA. 59+61 TO STA. 60+57 RT. & LT.
 FROM STA. 60+67 TO STA. 60+79 RT. & LT.

65 x 29 x 3
 1.5 inch Skimmer
 with 1.25 inch
 Orifice Diameter
 14 ft. weir
 ID 7.1


68 x 34 x 3
 1.5 inch Skimmer
 with 1.375 inch
 Orifice Diameter
 17 ft. weir
 ID 7.2

-MATCHLINE- -L- STA. 51+00.00 SEE SHEET NO. 6

-MATCHLINE- -L- STA. 64+00.00 SEE SHEET NO. 8



- NOTE:
 CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE:
 CONTRACTOR SHALL PROVIDE INLET PROTECTION FOR PARTIALLY INSTALLED STORM DRAINS. THIS MEASURE SHOULD BE INSTALLED AT THE END OF EACH WORKING DAY.
- NOTE:
 CONTRACTOR SHALL MAINTAIN ALL DEVICES AS PROJECT IS BROUGHT UP TO GRADE.
- NOTE:
 ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN RW OR EASEMENT.
- NOTE:
 INSTALL MATTING FOR EROSION CONTROL IN ALL PROPOSED DITCH LINES EXCEPT WHERE PERMANENT LINERS ARE SPECIFIED ON THE PLANS OR DIRECTED OTHERWISE BY THE ENGINEER.
- NOTE:
 PLACE MATTING ON ALL CUT AND FILL SLOPES THAT ARE GREATER THAN 3:1.
- FINAL EROSION CONTROL FOR CONSTRUCTION SHEET 7



9/10/2014 9:04:56 AM C:\pds\w5516_hyd_erosion_f.mxd psh_07.dgn
 ICA ENGINEERING, INC.

5/14/99
 9/10/2014
 C:\Users\psh\Documents\5516_hyd_erosion_final_psh_08.dgn
 PSH ENGINEERING, INC.




NAD 83/NSRS 2007

HIGH BRIDGE, LLC




5121 Kingdom Way,
 Suite 100
 Raleigh, NC 27607
 NC License No: F-0258

PROJECT REFERENCE NO.	SHEET NO.
W-5516	EC-21/CONST.8
RW SHEET NO.	
ROADSIDE ENVIRONMENTAL PROJECT ENGINEER	
LEVEL III CERTIFIED BY: STACEY H. BAILEY, PE CERTIFICATION NUMBER: 3074 ISSUED: SEPTEMBER 15, 2014	










- NOTE:
CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE:
CONTRACTOR SHALL PROVIDE INLET PROTECTION FOR PARTIALLY INSTALLED STORM DRAINS. THIS MEASURE SHOULD BE INSTALLED AT THE END OF EACH WORKING DAY.
- NOTE:
CONTRACTOR SHALL MAINTAIN ALL DEVICES AS PROJECT IS BROUGHT UP TO GRADE.
- NOTE:
ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN RW OR EASEMENT.
- NOTE:
INSTALL MATTING FOR EROSION CONTROL IN ALL PROPOSED DITCH LINES EXCEPT WHERE PERMANENT LINERS ARE SPECIFIED ON THE PLANS OR DIRECTED OTHERWISE BY THE ENGINEER.
- NOTE:
PLACE MATTING ON ALL CUT AND FILL SLOPES THAT ARE GREATER THAN 3:1.

FINAL EROSION CONTROL FOR CONSTRUCTION SHEET 8



-MATCHLINE- -L- STA. 77+00.00 SEE SHEET NO. 8


-MATCHLINE- -L- STA. 90+00.00 SEE SHEET NO. 10



- NOTE:
CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE:
CONTRACTOR SHALL PROVIDE INLET PROTECTION FOR PARTIALLY INSTALLED STORM DRAINS. THIS MEASURE SHOULD BE INSTALLED AT THE END OF EACH WORKING DAY.
- NOTE:
CONTRACTOR SHALL MAINTAIN ALL DEVICES AS PROJECT IS BROUGHT UP TO GRADE.
- NOTE:
ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN RW OR EASEMENT.
- NOTE:
INSTALL MATTING FOR EROSION CONTROL IN ALL PROPOSED DITCH LINES EXCEPT WHERE PERMANENT LINERS ARE SPECIFIED ON THE PLANS OR DIRECTED OTHERWISE BY THE ENGINEER.
- NOTE:
PLACE MATTING ON ALL CUT AND FILL SLOPES THAT ARE GREATER THAN 3:1.



FINAL EROSION CONTROL FOR CONSTRUCTION SHEET 9

5/14/99
 9/10/2014
 C:\Users\psh_09\Documents\Projects\W-5516\hyd_erosion_fina\psh_09.dgn
 ICA ENGINEERING, INC.




NAD 83/NSRS 2007


95 9 100
HIGH BRIDGE, LLC



FROM STA. 92+00 TO STA. 94+50 -L- LT
 FROM STA. 92+00 TO STA. 94+00 -L- RT
 FROM STA. 95+00 TO STA. 96+12 -L- LT
 FROM STA. 95+50 TO STA. 96+65 -L- RT
 FROM STA. 96+12 TO STA. 98+00 -L- LT
 FROM STA. 96+65 TO STA. 98+00 -L- RT
 FROM STA. 98+00 TO STA. 99+23 -L- LT
 FROM STA. 98+00 TO STA. 99+23 -L- RT
 FROM STA. 99+23 TO STA. 102+50 -L- LT
 FROM STA. 99+23 TO STA. 102+50 -L- RT



FROM STA. 90+00 TO STA. 92+00 -L- RT
 FROM STA. 90+25 TO STA. 92+00 -L- LT



STA. 96+65 -L- RT
 STA. 99+23 -L- RT

- NOTE: CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE: CONTRACTOR SHALL PROVIDE INLET PROTECTION FOR PARTIALLY INSTALLED STORM DRAINS. THIS MEASURE SHOULD BE INSTALLED AT THE END OF EACH WORKING DAY.
- NOTE: CONTRACTOR SHALL MAINTAIN ALL DEVICES AS PROJECT IS BROUGHT UP TO GRADE.
- NOTE: ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN RW OR EASEMENT.
- NOTE: INSTALL MATTING FOR EROSION CONTROL IN ALL PROPOSED DITCH LINES EXCEPT WHERE PERMANENT LINERS ARE SPECIFIED ON THE PLANS OR DIRECTED OTHERWISE BY THE ENGINEER.
- NOTE: PLACE MATTING ON ALL CUT AND FILL SLOPES THAT ARE GREATER THAN 3:1.

FINAL EROSION CONTROL FOR CONSTRUCTION SHEET 10

REVISIONS
 10-22-14 REVISED STATION/OFFSET CALLOUTS ON PARCEL 9

5/14/99
 10/24/2014
 I:\Projects\2014\10-22-14\10-22-14.dwg
 I:\Projects\2014\10-22-14\10-22-14.dwg
 I:\Projects\2014\10-22-14\10-22-14.dwg







6/1/2015 10:54:56 AM C:\Users\jca\Documents\Projects\51616_hyd_erosion_final_psh_11.dgn

NAD 83/NSRS 2007



5121 Kingdom Way,
Suite 100
Raleigh, NC 27607
NC License No: P-0258

PROJECT REFERENCE NO.	SHEET NO.
W-5516	EC-24/CONST II
RW SHEET NO.	
ROADSIDE ENVIRONMENTAL PROJECT ENGINEER	
LEVEL III CERTIFIED BY: STACEY H. BAILEY, PE CERTIFICATION NUMBER: 3074 ISSUED: MAY 26, 2015	




- NOTE: CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE: CONTRACTOR SHALL PROVIDE INLET PROTECTION FOR PARTIALLY INSTALLED STORM DRAINS. THIS MEASURE SHOULD BE INSTALLED AT THE END OF EACH WORKING DAY.
- NOTE: CONTRACTOR SHALL MAINTAIN ALL DEVICES AS PROJECT IS BROUGHT UP TO GRADE.
- NOTE: ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN RW OR EASEMENT.
- NOTE: INSTALL MATTING FOR EROSION CONTROL IN ALL PROPOSED DITCH LINES EXCEPT WHERE PERMANENT LINERS ARE SPECIFIED ON THE PLANS OR DIRECTED OTHERWISE BY THE ENGINEER.
- NOTE: PLACE MATTING ON ALL CUT AND FILL SLOPES THAT ARE GREATER THAN 3:1.

FINAL EROSION CONTROL FOR CONSTRUCTION SHEET 11


5/14/99
9/10/2014
C:\Users\pca\Documents\Road\5516_hyd_erosion_final_psh_12.dgn
PCA ENGINEERING, INC.

PROJECT REFERENCE NO.	SHEET NO.
W-5516	EC-25/CONST.12
RW SHEET NO.	
ROADSIDE ENVIRONMENTAL PROJECT ENGINEER	
LEVEL III CERTIFIED BY: STACEY H. BAILEY, PE CERTIFICATION NUMBER: 3074 ISSUED: SEPTEMBER 15, 2014	



-MATCHLINE- -L- STA. 116+00.00 SEE SHEET NO. 11

-MATCHLINE- -L- STA. 129+00.00 SEE SHEET NO. 13






FROM STA. 122+50 TO STA. 124+10 -L- RT
FROM STA. 124+10 TO STA. 126+50 -L- RT
FROM STA. 128+00 TO STA. 129+00 -L- LT

17
NORMAN R. BASINGER

-L-
PI Sta 133+40.55
 $\Delta = 80^{\circ} 04' 24.5'' (RT)$
 $D = 6' 21'' 58.3''$
 $L = 1,257.79'$
 $T = 756.17'$
 $R = 900.00'$
 $SE = .06$
 $DS = 50 MPH$

- NOTE:
CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE:
CONTRACTOR SHALL PROVIDE INLET PROTECTION FOR PARTIALLY INSTALLED STORM DRAINS. THIS MEASURE SHOULD BE INSTALLED AT THE END OF EACH WORKING DAY.
- NOTE:
CONTRACTOR SHALL MAINTAIN ALL DEVICES AS PROJECT IS BROUGHT UP TO GRADE.
- NOTE:
ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN RW OR EASEMENT.
- NOTE:
INSTALL MATTING FOR EROSION CONTROL IN ALL PROPOSED DITCH LINES EXCEPT WHERE PERMANENT LINERS ARE SPECIFIED ON THE PLANS OR DIRECTED OTHERWISE BY THE ENGINEER.
- NOTE:
PLACE MATTING ON ALL CUT AND FILL SLOPES THAT ARE GREATER THAN 3:1.

FINAL EROSION CONTROL FOR CONSTRUCTION SHEET 12



73 x 36 x 3
 1.5 inch Skimmer
 with 1.375 inch
 Orifice Diameter
 20 ft. weir
 ID 14.1

2' BASE TAIL DITCH
 118 LF @ 0.68%
 SEE DETAIL M
 DDE = 30 CY

END TIP PROJECT W-5516
 END CONSTRUCTION
 -L- POC 141+70.00

-L-		
PI Sta 133+40.55	PI Sta 141+12.79	PI Sta 142+93.87
$\Delta = 80^{\circ} 04' 24.5''$ (RT)	$\Delta = 13^{\circ} 29' 54.2''$ (LT)	$\Delta = 4^{\circ} 41' 00.0''$ (LT)
D = 6' 21' 58.3"	D = 6' 52' 41.7"	D = 2' 48' 31.0"
L = 1,257.79'	L = 196.25'	L = 166.75'
T = 756.17'	T = 98.58'	T = 83.42'
R = 900.00'	R = 833.00'	R = 2,040.00'
SE = .08	SE = .06	
DS = 50 MPH	DS = 50 MPH	

- NOTE:
CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE:
CONTRACTOR SHALL PROVIDE INLET PROTECTION FOR PARTIALLY INSTALLED STORM DRAINS. THIS MEASURE SHOULD BE INSTALLED AT THE END OF EACH WORKING DAY.
- NOTE:
CONTRACTOR SHALL MAINTAIN ALL DEVICES AS PROJECT IS BROUGHT UP TO GRADE.
- NOTE:
ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN R/W OR EASEMENT.
- NOTE:
INSTALL MATTING FOR EROSION CONTROL IN ALL PROPOSED DITCH LINES EXCEPT WHERE PERMANENT LINERS ARE SPECIFIED ON THE PLANS OR DIRECTED OTHERWISE BY THE ENGINEER.
- NOTE:
PLACE MATTING ON ALL CUT AND FILL SLOPES THAT ARE GREATER THAN 3:1.

FINAL EROSION CONTROL
 FOR CONSTRUCTION SHEET 14




5/14/09
 9/10/2014
 C:\Users\jca\Documents\Projects\W5516\hyd_erosion_final_psh_14.dgn
 JCA ENGINEERING, INC

5/14/99

- NOTE:
CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES WITHIN 14 CALENDAR DAYS, AFTER ANY PHASE OF GRADING.
- NOTE:
CONTRACTOR SHALL PROVIDE INLET PROTECTION FOR PARTIALLY INSTALLED STORM DRAINS. THIS MEASURE SHOULD BE INSTALLED AT THE END OF EACH WORKING DAY.
- NOTE:
CONTRACTOR SHALL MAINTAIN ALL DEVICES AS PROJECT IS BROUGHT UP TO GRADE.
- NOTE:
ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN R/W OR EASEMENT.
- NOTE:
INSTALL MATTING FOR EROSION CONTROL IN ALL PROPOSED DITCH LINES EXCEPT WHERE PERMANENT LINERS ARE SPECIFIED ON THE PLANS OR DIRECTED OTHERWISE BY THE ENGINEER.
- NOTE:
PLACE MATTING ON ALL CUT AND FILL SLOPES THAT ARE GREATER THAN 3:1.

FINAL EROSION CONTROL FOR CONSTRUCTION SHEET 2B



NAD 83 NRS 2007

-MATCHLINE- -SAC_ALN- STA. 21 + 50.00 SEE SHEET NO. 2-C

-SAC_ALN-

PI Sta 10+74.34 Δ = 26° 09' 21.6" (RT) D = 17° 54' 17.8" L = 146.08' T = 74.34' R = 320.00'	PI Sta 11+92.06 Δ = 8° 45' 47.1" (RT) D = 9° 32' 57.5" L = 91.77' T = 45.97' R = 600.00'	PI Sta 14+90.77 Δ = 8° 27' 18.8" (LT) D = 5° 08' 19.1" L = 164.54' T = 82.42' R = 1,115.00'	PI Sta 15+97.87 Δ = 5° 43' 07.5" (LT) D = 11° 27' 33.0" L = 49.91' T = 24.97' R = 500.00'
	PI Sta 17+06.78 Δ = 12° 46' 38.3" (LT) D = 7° 38' 22.0" L = 167.25' T = 83.98' R = 750.00'	PI Sta 18+46.73 Δ = 4° 03' 27.3" (LT) D = 3° 34' 51.5" L = 113.31' T = 56.68' R = 1,600.00'	

9/10/2016 9:00 AM C:\add\w5516_hyd_erosion_final_psh28_02B.dgn
 ICA ENGINEERING, INC.

