PROJECT REFERENCE NO.	SHEET NO.
B-3159	U0-05

UTILITIES BY OTHERS

NOTE:
ALL PROPOSED UTILITY WORK SHOWN ON THIS SHEET WILL BE DONE BY OTHERS. NO PAYMENT WILL BE MADE TO THE CONTRACTOR FOR PROPOSED UTILITY WORK SHOWN ON THIS SHEET.

SCALE:
0 50 100

NAD 83/NSRS 2007

–RPA–
PIs Sta 11+97.82
Θs = 8° 58' 47.7"
Ls = 184.00'
LT = 122.82'
ST = 61.48'

PI Sta 13+24.10
Δ = 12° 39' 25.3" (RT)
D = 9° 45' 38.8"
L = 129.67'
T = 65.10'
R = 587.00'
SE = .08

PIs Sta 14+50.15
Θs = 8° 58' 47.7"
Ls = 184.00'
LT = 122.82'
ST = 61.48'

PI Sta 18+86.35
Δ = 48° 51' 21.7" (LT)
D = 12° 54' 16.5"
L = 378.61'
T = 201.68'
R = 444.00'
SE = .08

–Y7–
PI Sta 16+37.49
Δ = 77° 12' 46.1" (RT)
D = 19° 05' 54.9"
L = 404.29'
T = 239.54'
R = 300.00'
SE = .06

–Y–
PI Sta 25+58.78
Δ = 30° 35' 22.0" (RT)
D = 1° 00' 18.7"
L = 3,043.15'
T = 1,558.78'
R = 5,700.00'
SE = EXIST

CITY OF LEXINGTON TO INSTALL 8" SANITARY SEWER OUTFALL TO DIVERT 8" SANITARY SEWER ALONG I-85 BUS TO BE ABANDONED

PROPOSED LEXINGTON UNDERGROUND GAS LINE

EXISTING GAS LINE TO BE ABANDONED

EXISTING GAS LINE TO BE ABANDONED

PROPOSED LEXINGTON UNDERGROUND GAS LINE

CITY OF LEXINGTON TO INSTALL 8" SANITARY SEWER OUTFALL TO DIVERT 8" SANITARY SEWER ALONG I-85 BUS TO BE ABANDONED

MATCHLINE SHEET U0-02 –RPA– STA. 11+00.00

MATCHLINE SHEET U0-02 –Y– STA. 29+50.00

BEGIN CONSTRUCTION –Y7– POT Sta. 10+00.00

TIE TO EXISTING GUARDRAIL –Y– STA 39+00.00

END CONSTRUCTION –Y– POC Sta. 39+00.00

TIE TO EXISTING MEDIAN GUARDRAIL –Y– STA 39+00.00 LT & RT

END CONSTRUCTION –Y7– POT Sta. 18+53.57

–Y7– PT Sta. 18+02.23

–RPA– SC Sta. 12+59.00

–Y7– PC Sta. 13+97.95

–RPA– TS Sta. 10+75.00

–Y– POC Sta. 36+00.00

–RPA– POT Sta. 10+00.00, 36.00' LT

–RPA– PC Sta. 16+84.67

–RPA– CS Sta. 13+88.67

–Y– PT Sta. 40+43.15

BM#2
N=761288
E=1630122
ELEV=781.59'

PAVEMENT REMOVAL
PAVED SHOULDER

NOTES:
SEE SHEET 9 FOR –RPA– PROFILE.
SEE SHEET 11 FOR –Y7– PROFILE.

CITY OF LEXINGTON TO INSTALL 8" SANITARY SEWER OUTFALL TO DIVERT 8" SANITARY SEWER ALONG I-85 BUS TO BE ABANDONED

GREGORY NORMAN JONES
DB 2037 PG 1639
PB 5 PG 34

DAVID TODD HUNT
DB 1983 PG 455
PB 5 PG 34

JUAN A. MONTOYA HAGGITH A. MONYOYA
DB 1448 PG 874
PB 5 PG 34

H. CLAY KOONTS
DB 1148 PG 764
PB 5 PG 34

ROY BACEL HOLMAN, JR.
HOMER ROGER HOLMAN
JANET FAYE HOLMAN STEWART
DB 923 PG 138
PB 5 PG 34

HILDA W. FLYNT
DB 840 PG 1150
PB 5 PG 34

GRUBB HOLDINGS COMPANY, LLC
DB 1110 PG 421

THOMAS LEROY LEE
DB 1758 PG 318
PB 5 PG 25

JOHN MILTON FRITTS
BETTY E. FRITTS
DB 507 PG 744
PB 5 PG 25

VIVIAN E. BROADWAY
DB 514 PG 359
PB 5 PG 25

LAKETA S. PETERSON
DB 1393 PG 1195
PB 5 PG 34

TODD. J. SURRATT
DB 2012 PG 2079
PB 5 PG 34

JAMES EARL LANIER
DEBRA LANIER
DB 1805 PG 1273
PB 5 PG 34

HEIH. TAM
YIM CHAU WU TAM
DB 1235 PG 948
PB 5 PG 34

ROBERT L. EVERHART, III

JOHNNY LEE BARKER AND WIFE PHYLLIS J. BARKER
DB 449 PG 323
PB 11PG 89

SANDRA DAVIS
DB 1126 PG 958
PB 11PG 89

JEFFERY VON CAUDLE
DB 1522 PG 1855
PB 11PG 89

LARRY HICKS
DB 1341PG 43
PB 11PG 89

GARY S. COOPER
PB 11PG 89

RAJKUMAR DYAL SEENANAN ET UX NADIA SEENANAN
DB 1144 PG 819
PB 11PG 89

RONALD TERRY
ROSA R. TERRY
DB 787 PG 963
PB 11PG 89

DAVID E. INABINETT
ELIZABETH H. INABINETT
DB 1358 PG 1212

CAROL E. McCANDIES
DB 754 PG 1050

HINDE ENGINEERING
License No. C-2639
401 Harrison Oaks Blvd., Suite 145 Cary, NC 27513

06-JUL-2015 09:34
C:\PROJECTS\2012\2012801.00 B-3159\Design\Utilities\Engineering\UBGVP-roJ\B3159_ut_rdy7_U005_psh.dgn
$$$$USERNAME$$$$