

PHASING DIAGRAM




TABLE OF OPERATION

SIGNAL FACE	PHASE			
	Ø 2 + 5	Ø 2 + 6	Ø 4 + 8	F L
21, 22	G	G	R	Y
41, 42	R	R	G	R
51	←	←	←	←
61, 62	R	G	R	Y
63	←	←	←	←
81, 82, 83	R	R	G	R
P21, P22	W	W	DW	DRK
P41, P42	DW	DW	W	DRK
P61, P62	DW	W	DW	DRK

W - Walk  
DW - Don't Walk  
DRK - Dark


OASIS 2070 LOOP & DETECTOR INSTALLATION CHART												
INDUCTIVE LOOPS				DETECTOR PROGRAMMING								
LOOP	SIZE (FT)	DISTANCE FROM STOPBAR (FT)	TURNS	NEW LOOP	PHASE	CALLING	EXTENSION	FULL TIME DELAY	STRETCH TIME	DELAY TIME	SYSTEM LOOP NEW CARD	
2A, 2B	6X6	300	EXIST	-	2	Y	Y	-	-	-	-	
2C, 2D	6X6	90	EXIST	-	DISCONNECT						-	-
4A	6X40	0	2-4-2	-	4	Y	Y	-	-	3	-	
4B	6X40	0	2-4-2	-	4	Y	Y	-	-	-	-	
5A	6X40	0	2-4-2	-	5	Y	Y	-	-	15	-	
					2	Y	Y	-	-	3	-	
6A, 6B	6X6	300	EXIST	-	6	Y	Y	-	-	-	-	
6C, 6D	6X6	90	EXIST	-	DISCONNECT						-	-
6E	6X40	0	2-4-2	-	6	Y	Y	-	-	-	-	
8A	6X40	0	2-4-2	-	8	Y	Y	-	-	3	-	
8B	6X40	0	2-4-2	-	8	Y	Y	-	-	10	-	
S1	6X6	+175	EXIST	-	-	-	-	-	-	-	Y	
S2	6X6	+175	EXIST	-	-	-	-	-	-	-	Y	

3 Phase Fully Actuated (High Point Signal System)



NOTES

1. Refer to "Roadway Standard Drawings NCDOT" dated January 2012 and "Standard Specifications for Roads and Structures" dated January 2012.
2. Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
3. Phase 5 may be lagged.
4. Reposition existing signal heads numbered 22, 61 and 62.
5. Disconnect existing loops 2C, 2D, 6C, and 6D.
6. Set all detector units to presence mode.
7. Locate new cabinet so as not to obstruct sight distance of vehicles turning right on red.
8. Omit "WALK" and flashing "DON'T WALK" with no pedestrian calls.
9. Program pedestrian heads to countdown the flashing "Don't Walk" time only.
10. Pavement markings are existing.
11. Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.

PHASING DIAGRAM DETECTION LEGEND



SIGNAL FACE I.D.




OASIS 2070 TIMING CHART

FEATURE	PHASE				
	2	4	5	6	8
Min Green 1 *	12	7	7	12	7
Extension 1 *	6.0	2.0	2.0	6.0	2.0
Max Green 1 *	50	25	15	50	25
Yellow Clearance	4.6	3.7	3.0	4.6	3.8
Red Clearance	1.7	2.3	3.2	1.7	2.3
Red Revert	2.0	2.0	2.0	2.0	2.0
Walk 1 *	7	7	-	7	-
Don't Walk 1	11	23	-	16	-
Seconds Per Actuation *	1.5	-	-	1.5	-
Max Variable Initial *	34	-	-	34	-
Time Before Reduction *	15	-	-	15	-
Time To Reduce *	30	-	-	30	-
Minimum Gap	3.0	-	-	3.0	-
Recall Mode **	SOFT RECALL	-	-	SOFT RECALL	-
Vehicle Call Memory	YELLOW	-	-	YELLOW	-
Dual Entry	-	ON	-	-	ON
Simultaneous Gap	ON	ON	ON	ON	ON

\* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.  
\*\* May be changed to Min Recall by Time of Day at discretion of City Traffic Engineer.

LEGEND



Signal Upgrade

SR 1113 (E. Kivett Drive) at Hoskins St. and Oneka Ave.

Division 7 Guilford County High Point

PLAN DATE: March 2014 REVIEWED BY: T. L. Averette

PREPARED BY: T. L. Averette REVIEWED BY:

SEAL

ROBERT J. ZIEMBA

ENGINEER

026486

3/5/2015

SIG. INVENTORY NO. 07-0550

750 N. Greenfield Pkwy, Garner, NC 27529

SCALE 0 40 1"=40'

21-Apr-2015 15:53  
 S:\IT\5550\15\_Signal\Signal Design\_Section\Central\_Regional\iv\_7ac-5558\_High\_Point\Signal\_Plans\Ø170550\_Ø170550\_20150305.dgn  
 rz:terbo