


# 3 Phase Fully Actuated (High Point Signal System)

## **NOTES**

- 1. Refer to "Roadway Standard Drawings NCDOT" dated January 2012 and "Standard Specifications for Roads and Structures" dated January 2012.
- 2. Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- 3. Phase 5 may be lagged.
- 4. Set all detector units to presence mode.
- 5. In the event of loop replacement, refer to the current ITS and Signals Design Manual and submit a Plan of Record to the Signal Design Section.
- 6. Locate new cabinet so as not to obstruct sight distance of vehicles turning right on red.
- 7. Omit "WALK" and flashing "DON'T WALK" with no pedestrian calls.
- 8. Program pedestrian heads to countdown the flashing "Don't Walk" time only.
- 9. Existing lane control signs (R3-5L and/or R3-5R) may be removed at the direction of the Engineer.
- 10. Pavement markings are existing.
- 11. Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.



OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

TURNS

INDUCTIVE LOOPS

FROM STOPBAR

6X6 | 300 | EXIST |

0

6X6 300 EXIST

300 EXIST

0 2-4-2

0 2-4-2

0 2-4-2

300 EXIST

2-4-2

SIZE (FT)

6X6

6X60

6X60

6X60

6X60

6X6

LOOP

2A

2B

4 A

4B

5Α

5B

DETECTOR PROGRAMMING

	<u>SIGNS</u>	
<u>PROPOSED</u>		<u>EXISTING</u>
(A) (B) (C)	Left Arrow "ONLY" Sign (R3-5L) Right Arrow "ONLY" (R3-5R) U-Turn "MUST YIELD" (R3-27)	(A) (B) (C)
$\langle \mathbb{D} \rangle$	Street Name Sign (D3-1)	$\bigcirc$
E	"TURNING TRAFFIC MUST YIELD TO PEDESTRIANS" Sign (R10-15)	E

# <u>PROPOSED</u> **EXISTING** Traffic Signal Head $\bigcirc$ Modified Signal Head Pedestrian Signal Head With Push Button & Sign

$\bigcirc$	Signal Pole with Guy	
	Signal Pole with Sidewalk Guy	
	Inductive Loop Detector	$\subset = = =$
	Controller & Cabinet	K×7
	Junction Box	
— —	2-in Underground Conduit	
N/A	Right of Way	
$\longrightarrow$	Directional Arrow	$\longrightarrow$
	Metal Strain Pole	

**LEGEND** 

Signal	Upgrade
0 - 9	

ignai opgrade			
Prepared in the Offices of:	SR 1546 (Guilford Colle	ege F	Rd.)
Transpa.	SR 4241 (Guilford F	,	
	Division 7 Guilford County	Jam	ıestown
OF TRANSCION	PLAN DATE: May 2014 PREPARED BY:		
	PREPARED BY: T. L. Averette REVIEWED BY:		
SCALE	REVISIONS	INIT.	DATE

SEAL	
WILL CARO	
ROFES SION	
- • 026/186	• -
WGINE ER	A Chin
DocuSigned by	
1895 HG NY ALTA LUSTE	3/16/2015 DATE

SIG. INVENTORY NO.

#### PHASING DIAGRAM DETECTION LEGEND

PHASING DIAGRAM

DETECTED MOVEMENT


02+6


UNDETECTED MOVEMENT (OVERLAP) UNSIGNALIZED MOVEMENT

← − − > PEDESTRIAN MOVEMENT


## SIGNAL FACE I.D.


All Heads L.E.D.





YELLOW








TABLE OF OPERATION

SIGNAL

FACE

21, 22

PHASE

OASIS	2070	TIMING	CHAR	Γ
	PHASE			
FEATURE	2	4	5	6
Min Green 1 *	12	7	7	12
Extension 1 *	6.0	1.0	1.0	6.0
Max Green 1 *	100	25	15	100
Yellow Clearance	4.6	3.0	3.0	4.6
Red Clearance	1.9	3.3	2.4	1.9
Red Revert	2.0	2.0	2.0	2.0
Walk 1 *	-	-	=	7
Don't Walk 1	-	-	-	28
Seconds Per Actuation *	1.5	-	-	1.5
Max Variable Initial *	34	-	-	34
Time Before Reduction *	15	-	-	15
Time To Reduce *	45	-	-	45
Minimum Gap	3.0	-	_	3.0
Recall Mode**	SOFT RECALL	-	-	SOFT RECA
		·		

\* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not

ON

ON

YELLOW

Vehicle Call Memory

Simultaneous Gap

\*\* May be changed to Min Recall by Time of Day at discretion of City Traffic Engineer.