



NOTES:

- PERFORM ALL WORK IN ACCORDANCE WITH THE CURRENT EDITION OF THE NATIONAL ELECTRICAL CODE.
- PROVIDE LOCKABLE POWER INLET BOX WITH L14-30P THAT RETAINS NEMA 3R RAINPROOF RATING WITH GENERATOR CORD SET CONNECTED.
- A COMBINATION METER BASE, TRANSFER PANEL, AND POWER INLET MAY BE USED WITH APPROVAL OF THE ENGINEER.
- REFER TO NCDOT ROADWAY STANDARD DRAWINGS 1700.01 AND 1700.02 FOR GROUNDING ELECTRODE SYSTEM REQUIREMENTS.
- REFER TO SHEET ITS 5.17 (SHEET 2 OF 2) FOR BONDING REQUIREMENTS.

04-JUN-2015 16:49 T:\Product\ITSS\ITS\NCDOT\100037777 - High Point Sig Sys\Special Detail\ITS-5.16.dgn SLOC3653 AT LUS291201

ATKINS 1616 EAST MILLBROOK ROAD, SUITE 310
RALEIGH, NORTH CAROLINA 27609
(919) 876-6888 NCBEES #F-0326

	High Point Signal System Transfer Switch (Panel) New Construction Detail (1 of 2)		
	Division 7 Guilford County High Point	PLAN DATE: June 2015 REVIEWED BY: HA Badgett	
PREPARED BY: BJ Slocum	REVIEWED BY: SG Haynie		DocuSigned by: 6/5/2015 DATE
SCALE: NTS	REVISIONS	INIT. DATE	