


# SUMMARY OF WORK BY CABLE ROUTING PLANS

CABLE ROUTING SHEET NUMBER	MESSANGER CABLE (1/4")	BOND MESSANGER CABLE	TRACER WIRE	UNDERGROUND CONDUIT (1 CONDUIT, 1 INCH)	UNDERGROUND CONDUIT (1 CONDUIT, 2 INCH)	UNDERGROUND CONDUIT (2 CONDUIT, 2 INCH)	DIRECTIONAL DRILL (2 CONDUIT, 2 INCH)	JUNCTION BOX (OVER-SIZED)	JUNCTION BOX (SPECIAL -SIZED)	REMOVE EXISTING JUNCTION BOX	REPLACE EXISTING JUNCTION BOX COVER	DELINATEATOR MARKER	STANDARD GUY ASSEMBLY	AERIAL GUY ASSEMBLY	SIDEWALK GUY ASSEMBLY	1" RISER WTH WEATHERHEAD FOR CCTV ELEC SERVICE	1" RISER WITH WEATHERHEAD FOR CAT 5E OR COMPOSITE	2" RISER WITH WEATHERHEAD	1" RISER WITH HEAT SHRINK TUBING	2" RISER WITH HEAT SHRINK TUBING	HEAT SHRINK TUBING RETROFIT KIT	DRILL/ CORE DRILL EXIST FOUNDATION
	LF	EA	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	
CRP-6.211	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.212	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.213	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.214	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.215	140	2	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3	-	-	-	-	
CRP-6.216	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.217	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.218	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.219	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.220	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.221	195	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.222	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.223	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.224	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.225	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.226	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.227	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.228	235	2	700	-	-	605	95	6	-	-	-	1	2	-	-	-	-	-	2	-	-	
CRP-6.229	255	2	385	-	-	245	140	4	-	-	-	1	2	-	-	-	-	-	2	-	-	
CRP-6.230	105	1	585	-	-	355	225	2	1	-	-	-	1	-	-	-	-	-	1	-	-	
CRP-6.231	-	-	1,300	-	-	1,140	165	4	-	-	-	1	-	-	-	-	-	-	-	-	-	
CRP-6.232	1,185	4	235	-	-	235	-	1	-	-	-	-	5	-	-	-	3	-	2	-	2	
CRP-6.233	930	1	-	-	-	-	-	-	-	-	-	-	1	-	-	-	-	-	-	-	-	
CRP-6.234	-	1	-	-	-	-	-	-	-	-	-	-	1	-	-	-	-	-	-	1	-	
CRP-6.235	-	1	-	-	-	-	-	-	-	-	-	-	-	-	2	-	-	-	-	-	-	
CRP-6.236	-	1	430	-	40	-	-	-	1	1	-	-	-	-	-	-	-	-	1	-	-	
CRP-6.237	-	-	1,315	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.238	-	-	1,395	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.239	-	1	1,040	-	-	75	375	1	2	2	-	-	1	-	-	-	-	-	1	-	-	
CRP-6.240	-	1	1,005	-	-	-	-	1	-	-	-	-	1	-	-	-	-	-	1	-	-	
CRP-6.241	-	-	1,340	-	-	-	-	-	1	1	-	-	-	-	-	-	-	-	-	-	-	
CRP-6.242	-	2	1,450	-	-	-	-	-	1	1	-	-	-	-	-	-	-	-	1	1	1	
CRP-6.243	225	2	125	-	-	35	90	2	-	-	-	-	2	-	-	-	-	-	2	-	-	
CRP-6.244	115	1	735	-	-	370	365	3	1	-	-	1	2	1	-	-	1	-	1	-	-	
CRP-6.245	975	2	115	-	-	-	115	2	-	-	-	1	-	-	1	-	-	-	1	1	-	

- Work shown on this sheet is a summary of work for the installation of the fiber-optic cable and CCTV installations that are shown on the cable routing plans (i.e. CRP sheets). Work to be done for traffic signals is shown separately on the signal designs and the "Summary of Work by Intersection" sheets in Volume III of III.
- The items listed above are for informational purposes only and represent work that is necessary to complete the project and are not necessarily pay items. See Summary of Quantites and the Project Special Provisions for defined Pay Items for this contract.

**ATKINS** 1616 EAST MILLBROOK ROAD, SUITE 310  
RALEIGH, NORTH CAROLINA 27609  
(919) 876-6888 NCBEES #F-0326



High Point Signal System  
Summary of Work by  
Cable Routing Plans  
(sheet 1 of 2)

Atkins  
1616 East Millbrook Road, Suite 310  
Raleigh, NC 27609  
(919) 876-6888 NCBEES #F-0326

SEAL  
NORTH CAROLINA  
PROFESSIONAL  
ENGINEER  
SEAL 025892  
MELISSA B. TOTH  
DATE 6/5/2015  
CADD File name: CRP-1.012.dgn