



08-JUN-2015 09:21 T:\projects\100037777 - High Point Sig Sys\Comms and ITS\Fiber Splicing\SpliceDetail-171.dgn SLOC3653 AT LUS291201

LEGEND

COLOR CODE TABLE 598-B		X = FUSION SPlice INDIVIDUAL FIBER
(1) BLUE	(7) RED	C = CAP AND SEAL
(2) ORANGE	(8) BLACK	
(3) GREEN	(9) YELLOW	EXPRESS = EXPRESS ENTIRE BUFFER TUBE / FIBERS THROUGH WITHOUT CUTTING
(4) BROWN	(10) VIOLET	BUFFER SPlice = SPlice ALL FIBERS IN BUFFER TUBE COLOR TO COLOR
(5) SLATE	(11) ROSE	
(6) WHITE	(12) AQUA	

- #### NOTES
- UNUSED FIBERS LEFT COILED AND STORED IN SPLICE TRAY
 - UNUSED BUFFER TUBES LEFT COILED AND STORED IN SPLICE ENCLOSURE
 - EDGE SWITCH CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING THE PROPER TERMINATIONS.

Prepared for the Offices of:

750 Greenfield Parkway, Garner, NC 27529

ATKINS

1616 EAST MILLBROOK ROAD, SUITE 310
RALEIGH, NORTH CAROLINA 27609
(919) 876-6888 NCBEES #F-0326

SEAL

High Point Signal System Splicing Details

Division 7	Guilford County	High Point
PLAN DATE: June 2015	REVIEWED BY: HA Badgett	
PREPARED BY: BJ Slocum	REVIEWED BY: SG Haynie	

REVISIONS	INIT.	DATE

DocuSigned by:
Henry Alfred Badgett
DATE: 6/8/2015
CADD Filename: SpliceDetail-171.dgn