



SPLICE ENCLOSURE NO. S19-2				
DEVICE ID	CL SHEET	CABLE X		
		CABLE NUMBER	ALONG ROUTE	TO
07-0783	CRP-6.167	19B	E KIVETT DR	N HAMILTON ST
07-0772	CRP-6.165	19D	W ENGLISH RD	N ELM ST
HP0602	CRP-6.168	19E	N WRENN ST	FRED ALEXANDER PL

08-JUN-2015 09:21  
 T:\projects\104115\ANDOT\100037777 - High Point Sig Sys\Comms and ITS\Fiber Splicing\SpliceDetail1-80.dgn  
 S:\033653 AT LUS291201

COLOR CODE		LEGEND	
TABLE	598-B		
(1) BLUE	(7) RED	X = FUSION SPlice INDIVIDUAL FIBER	
(2) ORANGE	(8) BLACK	C = CAP AND SEAL	
(3) GREEN	(9) YELLOW	EXPRESS = EXPRESS ENTIRE BUFFER TUBE / FIBERS THROUGH WITHOUT CUTTING	
(4) BROWN	(10) VIOLET	BUFFER SPlice = SPlice ALL FIBERS IN BUFFER TUBE COLOR TO COLOR	
(5) SLATE	(11) ROSE		
(6) WHITE	(12) AQUA		

NOTES
1. UNUSED FIBERS LEFT COILED AND STORED IN SPLICE TRAY
2. UNUSED BUFFER TUBES LEFT COILED AND STORED IN SPLICE ENCLOSURE
3. EDGE SWITCH CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING THE PROPER TERMINATIONS.

**ATKINS** 1616 EAST MILLBROOK ROAD, SUITE 310  
 RALEIGH, NORTH CAROLINA 27609  
 (919) 876-6888 NCBEES #F-0326

<p>Prepared for the Offices of:                  Transportation Mobility and Safety Division                  STATE OF NORTH CAROLINA                  DEPARTMENT OF TRANSPORTATION                  Intelligent Transportation Systems</p>	<b>High Point Signal System                  Splicing Details</b>		SEAL
	Division 7      Guilford County      High Point PLAN DATE: June 2015      REVIEWED BY: HA Badgett PREPARED BY: BJ Slocum      REVIEWED BY: SG Haynie	REVISIONS      INIT.      DATE	
SCALE: NTS	DocuSigned by: Henry Fred Badgett DATE: 6/8/2015		CADD Filename: SpliceDetail1-80.dgn