PROJ. REFERENCE NO.	SHEET NO.
W-5206AM	X-1A

NOTE: EARTHWORK QUANTITIES ARE CALCULATED BY THE ROADWAY DESIGN UNIT. THESE EARTHWORK QUANTITIES ARE BASED IN PART ON SUBSURFACE DATA PROVIDED BY THE GEOTECHNICAL ENGINEERING UNIT.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
38+50.00	0	0
39+00.00	9	0
39+50.00	25	0
40+00.00	35	0
40+50.00	32	0
41+00.00	29	43
41+50.00	19	90

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
74+50.00	0	0
75+00.00	13	0
75+50.00	48	0
76+00.00	55	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
107+50.00	0	0
108+00.00	19	14

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
44+57.96	0	0
45+00.00	0	16
45+50.00	0	18
46+00.00	0	17
46+50.00	0	17
47+00.00	0	17
47+50.00	0	17
48+00.00	0	17
48+50.00	0	17
49+00.00	0	17
49+50.00	0	17
49+74.44	0	8

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
56+35.41	0	0
56+50.00	0	5
57+00.00	0	17
57+50.00	0	17
58+00.00	0	17
58+50.00	0	17
58+87.38	0	12

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
65+17.32	0	0
65+50.00	0	13
66+00.00	0	19
66+50.00	0	17
67+00.00	0	17
67+50.00	0	17
68+00.00	0	17
68+50.00	0	17
69+00.00	0	17
69+50.00	0	17
70+00.00	0	17
70+50.00	0	17
71+00.00	0	17
71+50.00	0	17
71+77.98	0	9

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
78+07.98	0	0
78+50.00	0	14
79+00.00	0	17
79+50.00	0	17
80+00.00	0	17
80+50.00	0	17
81+00.00	0	17
81+50.00	0	17
82+00.00	0	17
82+50.00	0	17
83+00.00	0	17
83+50.00	0	17
84+00.00	0	17
84+50.00	0	17
85+00.00	0	17
85+50.00	0	17
86+00.00	0	17
86+23.28	0	8

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
93+06.30	0	0
93+50.00	0	15
94+00.00	0	17
94+50.00	0	17
95+00.00	0	17
95+50.00	0	17
96+00.00	0	17
96+50.00	0	17
97+00.00	0	17
97+50.00	0	17
98+00.00	0	17
98+50.00	0	17

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
99+00.00	0	17
99+50.00	0	17
100+00.00	0	17
100+50.00	0	19
101+00.00	0	21
101+50.00	0	23
102+00.00	0	25
102+50.00	0	29
103+00.00	0	33
103+50.00	0	37
104+00.00	0	39
104+50.00	0	40
105+00.00	0	39
105+50.00	0	35
106+00.00	0	32
106+50.00	0	30
107+00.00	0	28
107+50.00	0	28
108+00.00	0	29
108+15.91	0	9

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
147+47.96	0	0
147+50.00	0	1
148+00.00	0	14
148+50.00	0	13
149+00.00	0	13
149+50.00	0	13
150+00.00	0	13
150+40.45	0	13