

CLEARING AND GRUBBING  
EROSION CONTROL FOR  
CONSTRUCTION SHEET 13

NOTE:  
PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B  
AND TEMPORARY ROCK SILT CHECKS TYPE - A AT  
DRAINAGE OUTLETS.

NOTE:  
PERIMETER EROSION CONTROL MEASURES SHALL BE  
INSTALLED DURING CLEARING AND GRUBBING PHASE.

-L-  
PI Sta 229+66.62  
 $\Delta = 1^\circ 04' 44.6'' LT$   
 $D = 1^\circ 02' 30.3''$   
 $L = 103.58'$   
 $T = 51.79'$   
 $R = 5,500.00'$

NOTE:  
SILT FENCE AND COIR FIBER WATTLE BREAKS  
SHALL BE INSTALLED AS DIRECTED BY ENGINEER.

