PROJ. REFERENCE NO.	SHEET NO.
W-5519	X-1C

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
423+50.00	19	11	0
423+72.00	9	2	0

Station SR1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
17+00.00	0	0	0
17+50.00	46	12	0
18+00.00	63	28	0
18+50.00	70	21	0
19+00.00	48	17	0
19+50.00	31	36	0
20+00.00	32	56	0
20+50.00	26	115	0
21+00.00	24	163	0