PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.05.04.20921.1	17	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/ GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4510000000-E LAW ENFORCE-MENT HR	4685000000-E 4" X 90 M WHITE THERMO LF	4685000000-E 4" X 90 M YELLOW THERMO LF	4686000000-E 4" X 120 M WHITE THERMO LF	4686000000-E 4" X 120 M YELLOW THERMO LF	4695000000-E 8" X 90 M YELLOW THERMO LF	4695000000-E 8" X 90 M WHITE THERMO LF	4697000000-E 8" X 120 M WHITE THERMO LF	4705000000-E 16" X 120 M WHITE THERMO LF	4710000000-E 24" X 120 M WHITE THERMO LF	4721000000-E THERMO MSG SCHOOL 120 M EA	4721000000-E THERMO MSG STOP 120 M EA	4721000000-E THERMO MSG AHEAD 120 M EA	4721000000-E THERMO MSG ONLY 120 M EA	4721000000-E THERMO RXR 120 M EA	4725000000-E THERMO LT ARROW 90 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E THERMO STR & RT ARROW 90 M EA	4725000000-E THERMO STR ARROW 90 M EA	4725000000-E THERMO STR & LT ARROW 90 M EA	4726110000-E HEATED-IN-PLACE THERMO SYMBOL 90 M (HELMETED BICYCLIST) EA	4726110000-E HEATED-IN-PLACE THERMO SYMBOL 90 MIL (BIKE STR ARROW) EA
2016CPT.05.04.20921.1	Wake	1	SR 1010 - TEN TEN RD	SR 2727 - CROWDER RD TO 485' EAST OF SR 2722 - OLD MCCULLERS RD	2	2	3.462	26-40	388	0.12		40,700		2,338	45,375	585				370	12					15						
		2	SR 1107 - EAST ACADEMY ST	US 401 TO SR 2768 - JUDD PKWY	2,3	2	0.998	36	112	0.04	20			158	10,057	65		400		225	12					9	3					
		3	SR 1112 - SPENCE FARM RD	SR 1111 - OLD POWELL RD TO SR 1101 PINEY GROVE-WILBON RD	1	2	1.159	20-21	130	0.03		12,471		100	12,240																	
		4	SR 1113 - WADE NASH RD	NC 55 TO SR 1101 - PINEY GROVE-WILBON RD SKIPPING NEW BRG PROJECT	1	2	1.636	20-28	192	0.04	20	18,378		125	18,037					30						1		1					
		5	SR 1115 - AVENT FERRY RD	JT .2 MI NORTH OF 55 BYP TO END OF MAINT.	1	2	0.46	22-48	163	0.03		4,125	578	27	8,804					300		16	10									
		6	SR 1126 - HONEYCUTT RD	SR 1101 - PINEY GROVE-WILBON RD TO SR 1116 - CASS-HOLT RD	2	2	0.871	20	98	0.02		9,198			9,198																	
		7	SR 1152 - HOLLY SPRINGS RD	850' S OF SR 1385 - LILLY ATKINS RD TO 75' N OF SR 1319 - JONES FRANKLIN RD SKIPPING FROM BAKERSFIELD TO CAMPBELL	1,4	2	1.524	24-52	185	0.06		15,022		1,605	17,843	180	110	338		230				4		12	5		4				
		8	SR 1152 - W HOLLY SPRINGS RD	JT 500 FT EAST OF NC 55 TO NC 55 - MAIN ST	1	2	0.713	22-37	80	0.02		6,410		830	8,086	140	30			47						7	2		8				
		9	SR 1152 - HOLLY SPRINGS-NEW HILL RD	GREEN OAKS PKWY TO PVMT CHG	1	2	0.927	21-35	104	0.03		9,450		407	10,544	72				36						4	3		8				
		10	SR 1153 - TINGEN RD	SR 1011- SALEM ST TO US1	2	2	1.693	24-42	190	0.05		14,290		1,040	17,885	290	90		100	510	12			4		15	4	1		2			
		11	SR 1154 - WOODS CREEK RD	SR 1153 - OLD HOLLY SPRINGS-APEX RD TO SR 1149 - FRIENDSHIP RD	2	2	2.298	21	258	0.05		24,585		30	22,560																	
		12	SR 1301 - SUNSET LAKE RD	.22 MI SOUTH OF SR 1152 - HOLLY SPRINGS RD TO US 401 - N MAIN ST	2	2	5.326	24-51	597	0.19		55,287		5,225	67,716	1,720		150	100	500	12		8	4		42	16	6	4	1	5	4
		13	SR 1303 - SMITH RD	SR 1010 - TEN TEN RD TO DEAD END	1	2	1.289	21-33	145	0.03		13,870			13,380																	
		14	SR 1305 - ARTHUR PIERCE RD	SR 1152 - HOLLY SPRINGS RD TO .24 MI E OF SR 1300 - KILDAIRE FARM RD	1	2	0.764	20	86	0.02		8,221		63	8,221																	
		15	SR 1375 - LAKE WHEELER RD	SR 1010 - TEN TEN RD TO US 401	1	2	3.927	24-50	440	0.11	20	42,255		408	38,375	157				100						1							
		16	SR 1503 - DONNY BROOK RD	US 401 TO SR 1375 - LAKE WHEELER RD	2	2	0.7	20-21	79	0.02	20	7,532		97	7,216					37						1				1			
		17	SR 1601 - JENKS RD	NC 55 TO 540 PROJECT LIMIT	2	2	0.758	20-32	85	0.03		4,695		679	9,375	41				35						20		2					
		18	SR 1614 - SALEM CH RD	SR 1613 - DAVIS DR TO SR 1011- N SALEM ST	1	2	0.96	20-43	108	0.03		10,030		295	10,706	90	215		100	126				4		2	2		1				
		19	SR 1371 - LAKE WHEELER RD	SR 1370 - TRYON RD TO SR 1379 - PENNY RD SKIPPING NEW SECT. S OF MILL ENTRANCE	2	2	1.562	24-38	175	0.05		16,807		595	17,062	160				35						4							
		20	SR 1375 - SIMPKINS RD	SR 1371 - LAKE WHEELER RD TO US 401	1	2	1.079	24-34	121	0.03	20	11,610		275	11,675	110										1							
TOTAL FOR PROJ NO. 2016CPT.05.04.20921.1							**32.106**		**3,736**	**1.00**	**100**	**324,936**	**578**	**14,297**	**364,355**	**3,610**	**445**	**888**	**300**	**2,581**	**48**	**16**	**10**	**12**	**12**	**134**	**35**	**10**	**25**	**4**	**5**	**4**
												325,514		**378,652**		**4,055**							**98**					**208**			**9**
GRAND TOTAL							**32.106**		**3,736**	**1.00**	**100**	**324,936**	**578**	**14,297**	**364,355**	**3,610**	**445**	**888**	**300**	**2,581**	**48**	**16**	**10**	**12**	**12**	**134**	**35**	**10**	**25**	**4**	**5**	**4**
												325,514		**378,652**		**4,055**							**98**					**208**			**9**

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	4770000000-E 4" WHITE COLD APPLIED PLASTIC, TYPE III LF	4770000000-E 4" YELLOW COLD APPLIED PLASTIC, TYPE III LF	4780000000-E 8" YELLOW COLD APPLIED PLASTIC, TYPE III LF	4810000000-E 4" WHITE PAINT LF	4810000000-E 4" YELLOW PAINT LF	4820000000-E 8" YELLOW PAINT LF	4820000000-E 8" WHITE PAINT LF	4830000000-E 16" WHITE PAINT LF	4835000000-E 24" WHITE PAINT LF	4840000000-N PAINT MSG SCHOOL EA	4840000000-N PAINT MSG RXR EA	4840000000-N PAINT MSG ONLY EA	4845000000-N PAINT LT ARROW EA	4845000000-N PAINT RT ARROW EA	4845000000-N PAINT STR & LT ARROW EA	4845000000-N PAINT STR & RT ARROW EA	4845000000-N PAINT STR ARROW EA	4850000000-E 4" LINE REMOVAL LF	4860000000-E 8" LINE REMOVAL LF	4900000000-N CRYSTAL & RED MARKERS EA	4900000000-N YELLOW & YELLOW MARKERS EA
2016CPT.05.04.20921.1	Wake	1	SR 1010 - TEN TEN RD	SR 2727 - CROWDER RD TO 485' EAST OF SR 2722 - OLD MCCULLERS RD	2	2	3.462	26-40	276	276		43,033	45,375	585			470	12			15					552		150	445
		2	SR 1107 - EAST ACADEMY ST	US 401 TO SR 2768 - JUDD PKWY	2,3	2	0.998	36				158	11,057	65	400		225	12			9	3						15	95
		3	SR 1112 - SPENCE FARM RD	SR 1111 - OLD POWELL RD TO SR 1101 PINEY GROVE-WILBON RD	1	2	1.159	20-21																					
		4	SR 1113 - WADE NASH RD	NC 55 TO SR 1101 - PINEY GROVE-WILBON RD SKIPPING NEW BRG PROJECT	1	2	1.636	20-28																				3	108
		5	SR 1115 - AVENT FERRY RD	JT .2 MI NORTH OF 55 BYP TO END OF MAINT.	1	2	0.46	22-48																					30
		6	SR 1126 - HONEYCUTT RD	SR 1101 - PINEY GROVE-WILBON RD TO SR 1116 - CASS-HOLT RD	2	2	0.871	20				9,198	9,198																
		7	SR 1152 - HOLLY SPRINGS RD	850' S OF SR 1385 - LILLY ATKINS RD TO 75' N OF SR 1319 - JONES FRANKLIN RD SKIPPING FROM BAKERSFIELD TO CAMPBELL	1,4	2	1.524	24-52																				135	169
		8	SR 1152 - W HOLLY SPRINGS RD	JT 500 FT EAST OF NC 55 TO NC 55 - MAIN ST	1	2	0.713	22-37																				38	70
		9	SR 1152 - HOLLY SPRINGS-NEW HILL RD	GREEN OAKS PKWY TO PVMT CHG	1	2	0.927	21-35																				14	77
		10	SR 1153 - TINGEN RD	SR 1011- SALEM ST TO US1	2	2	1.693	24-42				15,330	17,885	290	90	100.00	510	12	4		15	4	2	1					
		11	SR 1154 - WOODS CREEK RD	SR 1153 - OLD HOLLY SPRINGS-APEX RD TO SR 1149 - FRIENDSHIP RD	2	2	2.298	21				24,615	22,560																
		12	SR 1301 - SUNSET LAKE RD	.22 MI SOUTH OF SR 1152 - HOLLY SPRINGS RD TO US 401 - N MAIN ST	2	2	5.326	24-51	760	1,220	120	60,512	67,716	1,720	150	100.00	500	12	4	8	42	16	1	6	4	1,980	120	375	690
		13	SR 1303 - SMITH RD	SR 1010 - TEN TEN RD TO DEAD END	1	2	1.289	21-33																					
		14	SR 1305 - ARTHUR PIERCE RD	SR 1152 - HOLLY SPRINGS RD TO .24 MI E OF SR 1300 - KILDAIRE FARM RD	1	2	0.764	20																					
		15	SR 1375 - LAKE WHEELER RD	SR 1010 - TEN TEN RD TO US 401	1	2	3.927	24-50																				5	290
		16	SR 1503 - DONNY BROOK RD	US 401 TO SR 1375 - LAKE WHEELER RD	2	2	0.7	20-21				7,629	7,216				37				1		1					8	46
		17	SR 1601 - JENKS RD	NC 55 TO 540 PROJECT LIMIT	2	2	0.758	20-32				5,374	9,375	41							20			2					
		18	SR 1614 - SALEM CH RD	SR 1613 - DAVIS DR TO SR 1011- N SALEM ST	1	2	0.96	20-43																					
		19	SR 1371 - LAKE WHEELER RD	SR 1370 - TRYON RD TO SR 1379 - PENNY RD SKIPPING NEW SECT. S OF MILL ENTRANCE	2	2	1.562	24-38				17,402	17,062	160			35				4							18	135
		20	SR 1375 - SIMPKINS RD	SR 1371 - LAKE WHEELER RD TO US 401	1	2	1.079	24-34																				4	87
TOTAL FOR PROJ NO. 2016CPT.05.04.20921.1							**32.106**		**1,036**	**1,496**	**120**	**183,251**	**207,444**	**2,861**	**640**	**200**	**1,777**	**48**	**8**	**8**	**106**	**23**	**4**	**9**	**4**	**2,532**	**120**	**765**	**2,242**
									2,532			**390,695**		**3,501**				**64**			**146**							**3,007**	
GRAND TOTAL							**32.106**		**1,036**	**1,496**	**120**	**183,251**	**207,444**	**2,861**	**640**	**200**	**1,777**	**48**	**8**	**8**	**106**	**23**	**4**	**9**	**4**	**2,532**	**120**	**765**	**2,242**
									2,532			**390,695**		**3,501**				**64**			**146**							**3,007**	