

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.05.06.10911.1, etc.	9	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW CY	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1.25" MILLING SY	0" TO 1.5" MILLING SY	0" TO 1.25" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	CONCRETE CURB RAMP (Std. 848.06) EA	ADJUST MANHOLES EA	ADJUST METER OR VALVE BOX EA	TEMP SILT FENCE LF	WATTLE LF	SEED & MULCHING AC	INDUCTIVE LOOP LF	
2016CPT.05.06.10911.1	Vance	1	US 158 BUS	BEGIN C&G TO US 1 BUS	2	2	NO	NO	1.65	26-43				38,488						2,786	187	85							2,500	
TOTAL FOR MAP NO. 1									1.65					38,488						2,786	187	85							2,500	
TOTAL FOR PROJ NO. 2016CPT.05.06.10911.1									1.65					38,488						2,786	187	85							2,500	
2016CPT.05.06.10931.1	Warren	2	US 1	US 158 TO VA STATE LINE	3,4	2	NO	YES	7.804	24-34	1,506	377	15.06		1,267		625	279	10,584		678	700			10	9	1,095	2,740	10.95	212
2016CPT.05.06.10931.1	Warren	3	US 158	US 158 BUS TO HALIFAX CO	4	2	NO	YES	10.57	24-42	2,057	515	20.57		1,342				14,255		896	1,000	3			1,496	3,740	14.96		
TOTAL FOR PROJ NO. 2016CPT.05.06.10931.1									18.374		3,563	892	35.63		2,609		625	279	24,839		1,574	1,700	3	10	9	2,591	6,480	25.91	212	
2016CPT.05.06.20911.1	Vance	4	SR 1312 - PARHAM RD	US 1/US 158 BUS TO END PAVEMENT	1	2	NO	NO	0.985	18-35	142	50	1.90		196	250				920	65	20			1	130	330	1.30		
2016CPT.05.06.20911.1	Vance	5	SR 1335 - BURNSIDE RD	SR 1329 - STAGECOACH RD TO SR 1303 - HICKSBORO RD	4	2	NO	NO	3.038	20	456	300	6.08			165			3,164		199	350				441	1,110	4.41		
2016CPT.05.06.20911.1	Vance	6	SR 1366 - BULLOCKSVILLE PARK RD	EOM TO WARREN CO	5	2	NO	NO	3.05	21-22	458	305	6.10			430	1,697			2,764	269	500				442	1,110	4.42		
TOTAL FOR PROJ NO. 2016CPT.05.06.20911.1									7.073		1,056	655	14.08		196	845	1,697	3,164	3,684	533	870			1	1,013	2,550	10.13			
2016CPT.05.06.20931.1	Warren	7	SR 1114 - WATSON RD	SR 1100 - MANSON-AXTELL RD TO VANCE CO	1	2	NO	NO	1.684	20	252	126	3.37			138				1,434	101	500				244	610	2.44		
2016CPT.05.06.20931.1	Warren	8	SR 1620 - LICK SKILLET RD/PETE HARRIS RD	US 401 - TO SR 1625 - PARKTOWN RD	1	2	NO	NO	8.43	21-22	1,265	843	16.86			295				7,672	538	300				1,222	3,060	12.22		
TOTAL FOR PROJ NO. 2016CPT.05.06.20931.1									10.114		1,517	969	20.23			433				9,106	639	800				1,466	3,670	14.66		
GRAND TOTAL									37.211		6,136	2,516	69.94	38,488	2,609	196	1,903	1,976	28,003	15,576	2,933	3,455	3	10	10	5,070	12,700	50.70	2,712	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LENGTH	WIDTH	4413000000-E	4457000000-N	4685000000-E	4686000000-E	4695000000-E	4710000000-E	4721000000-E	4725000000-E					4810000000-E		4835000000-E	4845000000-N					4905000000-N						
									WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	TEMP TRAFFIC CONTROL LS	4" X 90 M WHITE THERMO LF	4" X 90 M YELLOW THERMO LF	4" X 120 M WHITE THERMO LF	4" X 120 M YELLOW THERMO LF	8" X 90 M WHITE THERMO LF	24" X 120 M WHITE THERMO LF	THERMO MSG SCHOOL 120 M EA	THERMO LT ARROW 90 M EA	THERMO RT ARROW 90 M EA	THERMO STR ARROW 90 M EA	THERMO STR & RT ARROW 90 M EA	THERMO MERGE ARROW 90 M EA	4" WHITE PAINT LF	4" YELLOW PAINT LF	24" WHITE PAINT LF	PAINT LT ARROW EA	PAINT RT ARROW EA	PAINT STR ARROW EA	PAINT STR & RT ARROW EA	PAINT MERGE ARROW EA	SNOW PLOWABLE MARKERS EA				
2016CPT.05.06.10911.1	Vance	1	US 158 BUS	BEGIN C&G TO US 1 BUS	2	2	1.65	26-43	185	0.06	160		3,865	17,210		260			8	3	4	6	3		4,025	17,210	260	8	3	4	6	3	300		
TOTAL FOR PROJ NO. 2016CPT.05.06.10911.1							1.65		185	0.06	160		3,865	17,210		260			8	3	4	6	3		4,025	17,210	260	8	3	4	6	3	300		
									160		21,075		260		24					21,235		24													
2016CPT.05.06.10931.1	Warren	2	US 1	US 158 TO VA STATE LINE	3,4	2	7.804	24-34	875	0.23	80,980	250	480	71,325	205	126	12																525		
2016CPT.05.06.10931.1	Warren	3	US 158	US 158 BUS TO HALIFAX CO	4	2	10.57	24-42	1,184	0.31	113,733		800	102,910		126	12																700		
TOTAL FOR PROJ NO. 2016CPT.05.06.10931.1							18.374		2,059	0.54	194,713	250	1,280	174,235	205	252	24																1,225		
									194,963		175,515		205		3																				
2016CPT.05.06.20911.1	Vance	4	SR 1312 - PARHAM RD	US 1/US 158 BUS TO END PAVEMENT	1	2	0.985	18-35	111	0.03	10,599		78	10,599																					
2016CPT.05.06.20911.1	Vance	5	SR 1335 - BURNSIDE RD	SR 1329 - STAGECOACH RD TO SR 1303 - HICKSBORO RD	4	2	3.038	20	341	0.07	32,689			32,689																					
2016CPT.05.06.20911.1	Vance	6	SR 1366 - BULLOCKSVILLE PARK RD	EOM TO WARREN CO	5	2	3.05	21-22	342	0.09	32,818		70	30,330																					
TOTAL FOR PROJ NO. 2016CPT.05.06.20911.1							7.073		794	0.19	76,106		148	73,618																					
									76,106		73,766																								
2016CPT.05.06.20931.1	Warren	7	SR 1114 - WATSON RD	SR 1100 - MANSON-AXTELL RD TO VANCE CO	1	2	1.684	20	189	0.03	18,120			17,296																					
2016CPT.05.06.20931.1	Warren	8	SR 1620 - LICK SKILLET RD/PETE HARRIS RD	US 401 - TO SR 1625 - PARKTOWN RD	1	2	8.43	21-22	945	0.18	90,707		94	79,853																					
TOTAL FOR PROJ NO. 2016CPT.05.06.20931.1							10.114		1,134	0.21	108,827		94	97,149																					
									108,827		97,243																								
GRAND TOTAL							37.211		4,172	1.00	379,806	250	5,387	362,212	205	512	24			8	3	4	9	3		4,025	17,210	260	8	3	4	6	3	1,525	
									380,056		367,599		205		27					21,235		24													