PROJECT NO.	SHEET NO.	TOTAL NO.
I-5790, I-5855	10	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	REPAIR OF JOINTED CONCRETE PAVEMENT SLAB SYD	GEOTEXTILE FOR SOIL STABIL-IZATION SY	#57 STONE TON	SHALLOW UNDERCUT CY	CLASS IV SUBGRADE STABILIZATION TON	INCIDENTAL STONE BASE TONS	MILLING ASPHALT PAVEMENT, 1½" DEPTH SY	ASPHALT CONC SURFACE COURSE, TYPE S9.5C TON	ASPHALT BINDER FOR PLANT MIX TONS	AC PLANT MIX (REPAIR) TONS	3" PATCHING EXISTING PAVEMENT TON	PATCHING CONCRETE PAVEMENT SPALLS SF	ASPHALT SURFACE TREATMENT, FOG SEAL SY	JOINT CONSTRUCTION, REPAIR & SEALING LF	JOINT REPAIR LB	DIAMOND GRINDING PCC SY	MILLED RUMBLE STRIPS IN EXISTING PCC SHOULDERS LF	PORTABLE LIGHTING LS	INDUCTIVE LOOP SAW CUT LF
I-5790	Guilford	1	I-85 NORTHBOUND	FROM SOUTH OF YOUNG'S MILL RD TO I-40 (17.12 - 20.49)	1	4	MD	NO	NO	3.335	48											2,663	491	35,218	85,796		73,704	35,220	0.39	
TOTAL FOR MAP NO. 1										**3.335**												**2,663**	**491**	**35,218**	**85,796**		**73,704**	**35,220**	**0.39**	
I-5790	Guilford	2	OFF RAMP TO YOUNG'S MILL ROAD	FROM I-85 NB TO YOUNG'S MILL RD	2	1		NO	NO	0.215	24						90						9		3,629		2,158			
		"	"		3	2		NO	NO	0.016	78							732	62	4										
TOTAL FOR MAP NO. 2										**0.231**							**90**	**732**	**62**	**4**			**9**		**3,629**		**2,158**			
I-5790	Guilford	3	ON RAMP TO I-85 NB	FROM YOUNG'S MILL RD TO I-85 NB	4	1		NO	NO	0.011	62							413	34	2					3,658					
		"	"		2	2		NO	NO	0.216	24						65									64.80	2,032			
TOTAL FOR MAP NO. 3										**0.227**							**65**	**413**	**34**	**2**					**3,658**	**64.80**	**2,032**			
I-5790	Guilford	4	OFF RAMP TO I-840	FROM I-85 NB TO I-840	1,5	2		NO	NO	0.507	24											405	31	5,354	8,348		6,631	5,352		
TOTAL FOR MAP NO. 4										**0.507**												**405**	**31**	**5,354**	**8,348**		**6,631**	**5,352**		
I-5790	Guilford	5	OFF RAMP TO MT HOPE CHURCH ROAD	FROM I-85 NB TO MT HOPE CH RD	6	1		NO	NO	0.483	29												1	1,984	7,905		3,967			
TOTAL FOR MAP NO. 5										**0.483**													**1**	**1,984**	**7,905**		**3,967**			
I-5790	Guilford	6	I-85 SOUTHBOUND	FROM I-40 TO S. OF YOUNG'S MILL RD (7.7 - 11.07)	1	4	MD	NO	NO	3.333	48	272	545	82	91	245					62	2,662	519	35,196	88,650		77,665	35,200		
TOTAL FOR MAP NO. 6										**3.333**		**272**	**545**	**82**	**91**	**245**					**62**	**2,662**	**519**	**35,196**	**88,650**		**77,665**	**35,200**		
I-5790	Guilford	7	ON RAMP TO I-85 SB	FROM I-40/I-85 BUS NB TO I-85 SB	6	1		NO	NO	0.124	24													509	2,093		1,163			
TOTAL FOR MAP NO. 7										**0.124**														**509**	**2,093**		**1,163**			
I-5790	Guilford	8	ON RAMP TO I-85 SB	FROM I-840 TO I-85 SB	5	2		NO	NO	0.331	32											264	15	1,359	6,289		4,659	3,495		
TOTAL FOR MAP NO. 8										**0.331**												**264**	**15**	**1,359**	**6,289**		**4,659**	**3,495**		
I-5790	Guilford	9	OFF RAMP TO YOUNG'S MILL ROAD	FROM I-85 SB TO YOUNG'S MILL RD	2,6	1		NO	NO	0.149	24						50						9	97	2,574	50.00	1,517			
		"	"		3	2		NO	NO	0.016	68							638	54	3										
TOTAL FOR MAP NO. 9										**0.165**							**50**	**638**	**54**	**3**			**9**	**97**	**2,574**	**50.00**	**1,517**			
I-5790	Guilford	10	ON RAMP TO I-85 SB	FROM YOUNG'S MILL RD TO I-85 SB	4	1		NO	NO	0.028	52							854	72	4										
		"	"		2	2		NO	NO	0.228	24						65						1		3,846		2,137			
TOTAL FOR MAP NO. 10										**0.256**							**65**	**854**	**72**	**4**					**3,846**		**2,137**			
TOTAL FOR PROJ NO. I-5790										**8.992**		**272**	**545**	**82**	**91**	**245**	**270**	**2,637**	**222**	**13**	**62**	**5,994**	**1,076**	**79,717**	**212,788**	**114.80**	**175,633**	**79,267**	**0.39**	
I-5855	Guilford	11	I-85 NORTHBOUND	FROM ELM-EUGENE TO SOUTH OF YOUNG'S MILL RD (11.70 - 17.12)	1	4	MD	NO	NO	5.436	48	334	667	100	111	300						4,341	999	57,404	147,772	135.90	131,152	57,420	0.61	
TOTAL FOR MAP NO. 11										**5.436**		**334**	**667**	**100**	**111**	**300**						**4,341**	**999**	**57,404**	**147,772**	**135.90**	**131,152**	**57,420**	**0.61**	
I-5855	Guilford	12	ON RAMP TO I-85 NB	FROM ELM-EUGENE TO I-85 NB	7	1		NO	NO	0.007	70						93	288	24	1				41						
		"	"		7	1		NO	NO	0.016	32							300	25	1				94						
		"	"		7	1		NO	NO	0.087	24							1,225	103	6				510						
		"	"		7	1		NO	NO	0.066	20							774	65	4				348						
		"	"		7	1		NO	NO	0.039	16							366	31	2				183						
TOTAL FOR MAP NO. 12										**0.215**							**93**	**2,953**	**248**	**14**				**1,176**						
I-5855	Guilford	13	OFF RAMP TO US 421 SB	FROM I-85 NB TO US 421 SB	8	1		NO	NO	0.137	16						184	1,286	109	6				1,125						
		"	"		7	1		NO	NO	0.288	16							2,703	229	14	12			1,352						
TOTAL FOR MAP NO. 13										**0.425**							**184**	**3,989**	**338**	**20**	**12**			**2,477**						
I-5855	Guilford	14	COLLECTOR RAMP	FROM I-85 NB TO I-85 NB	8	1		NO	NO	0.027	16							253	21	1				222						
		"	"		7	1		NO	NO	0.099	24							1,394	118	7				813						
		"	"		7	1		NO	NO	0.218	16							2,046	173	10				1,023						
		"	"		7	1		NO	NO	0.031	30							546	46	3				182						
		"	"		7	1		NO	NO	0.061	44																			
		"	"		7	1		NO	NO	0.029	28							476	40	2				238						
		"	"		7	1		NO	NO	0.028	30							493	42	2				230						
		"	"		7	1		NO	NO	0.198	16							1,859	157	9				929						
		"	"		7	1		NO	NO	0.045	30							792	67	4				211						
		"	"		7	1		NO	NO	0.048	28							789	67	4				479						
TOTAL FOR MAP NO. 14										**0.784**								**8,648**	**731**	**42**				**4,327**						
I-5855	Guilford	15	ON LOOP	FROM US 421 SB TO COLLECTOR TO I-85 NB	7	1		NO	NO	0.016	16							150	13	1				75						
		"	"		8	1		NO	NO	0.205	16							1,924	163	10				481						
TOTAL FOR MAP NO. 15										**0.221**								**2,074**	**176**	**11**				**556**						