

COMPUTED BY:     NAG     DATE:   1-27-16  

CHECKED BY:     NAG     DATE:   1-27-16  

**(1-27-16)**

PROJECT NO.

I-5784

SHEET NO.

11

**STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS**

**CABLE GUIDERAIL SUMMARY**

SURVEY LINE	BEG. MILE MARKER	END MILE MARKER	LOCATION	LENGTH (DOUBLE FACED) (LF)	END ANCHOR UNIT (EA)	INTERMEDIATE ANCHOR UNIT (EA)
I-95	84	84.69	MEDIAN	3,620	2	2
I-95	84.72	86.06	MEDIAN	7,075	2	6
I-95	87.53	88.79	MEDIAN	6,650	2	6
I-95	90.53	91.48	MEDIAN	5,100	2	4
I-95	91.61	92.46	MEDIAN	4,500	2	4
SUBTOTAL				26,945	10	22
TOTAL				26,945	10	22

**Additional Guiderail Posts = 20 EA**

Existing guardrail to be removed at locations shown above (see Guardrail Summary). Double Faced Cable Guiderail to be placed 4' from the centerline of the median or as directed by the Engineer.