

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.08.10.10531, etc	10	

## SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	AGGREGATE SHOULDER BORROW ALLOWED	LENGTH MI	WIDTH FT	BORROW EXCAVATION CY	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1.5" MILLING SY	0" TO 1.5" MILLING SY	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	MILLED RUMBLE STRIPS LF	LATEX MODIFIED MICRO SURFACING, TYPE III SY	ADJ. OF MAN-HOLES EA	ADJ. OF METER OR VALVE BOXES EA	TEMP. SILT FENCE LF	WATTLE LF	SEED & MULCHING AC
2016CPT.08.10.10531	Lee	1	US 1 SB	FROM CONSTRUCTION JT NEAR SR 1731 (QUAIL RIDGE DR) TO MOORE CO. LINE	1	2	MD	NO	NO	YES	4.109	34						105				1,020		81,961	1		825	130	5.98
		2	US 1 NB	FROM MOORE COUNTY LINE TO CONSTRUCTION JOINT NEAR SR 1731 (QUAIL RIDGE DR)	1	2	MD	NO	NO	YES	4.102	34							130				625		81,821	2		825	130
<b>TOTAL FOR PROJ NO. 2016CPT.08.10.10531</b>											<b>8.211</b>							<b>235</b>				<b>1,645</b>		<b>163,782</b>	<b>3</b>		<b>1,650</b>	<b>260</b>	<b>11.95</b>
2016CPT.08.10.20531	Lee	3	SR 1009 (CARBONTON RD)	FROM NC 42 TO US 1 BUS. (CARTHAGE ST)	2,3,4	2	2WU	NO	NO	YES	2.89	28	425		4.72	12,515		180	4,535		272	3,075			10	20	420	70	3.03
<b>TOTAL FOR PROJ NO. 2016CPT.08.10.20531</b>											<b>2.89</b>		<b>425</b>		<b>4.72</b>	<b>12,515</b>		<b>180</b>	<b>4,535</b>		<b>272</b>	<b>3,075</b>			<b>10</b>	<b>20</b>	<b>420</b>	<b>70</b>	<b>3.03</b>
2016CPT.08.10.10631	Moore	4	US 1 SB	FROM BRIDGE AT CRANE'S CREEK TO END OF GUARDRAIL NORTH OF SR 2005 (ALMA ST) OVERPASS	5	2	M2	NO	NO	YES	1.286	34	190		2.57	26,710		460		2,275	134		13,584				257	40	1.87
		5	US 1 SB	FROM END OF GUARDRAIL NORTH OF SR 2005 (ALMA ST) OVERPASS TO BRIDGE AT LITTLE RIVER (INCLUDE ON AND OFF RAMPS)	6	2	M2	NO	NO	YES	2.028	28-64	300		4.06	3,855	2,270	605		5,480	323	1,525	21,412				410	70	2.95
		6	US 1 SB	FROM BRIDGE AT LITTLE RIVER TO PAVEMENT JOINT PAST SR 1853 (CRYSTAL LAKE ROAD)	6	2	M2	NO	NO	YES	0.409	36-68	60		0.82	255		500		1,075	63	155	4,324				85	20	0.60
<b>TOTAL FOR PROJ NO. 2016CPT.08.10.10631</b>											<b>3.723</b>		<b>550</b>		<b>7.45</b>	<b>30,820</b>	<b>2,270</b>	<b>1,565</b>		<b>8,830</b>	<b>520</b>	<b>1,680</b>	<b>39,320</b>				<b>752</b>	<b>130</b>	<b>5.42</b>
2016CPT.08.10.20631	Moore	7	SR 1470 (NORTH MOORE RD)	FROM SR 1516 (CLARENCE RD TO NC 705)	7	2	2WU	NO	NO	YES	3.739	22	550	235	7.48			120	4,455		267	3,060					750	120	5.44
		8	SR 1661 (STANTON RD)	FROM US 15-501 TO LEE COUNTY LINE	7	2	2WU	NO	NO	YES	1.415	20	210	185	2.83			100	1,550		93	775					285	50	2.06
		9	SR 2015 (MURDOCK C RD)	FROM SR 2014 (MCLAUCHLIN RD) TO HARNETT COUNTY LINE	7	2	2WU	NO	NO	YES	0.73	20	110	80	1.46			115	800		48	760					150	30	1.06
		10	SR 1261 (BETHLEHEM CHURCH RD)	FROM SR 1210 (BEULAH HILL CHURCH RD) TO SR 1243 (PEACE RD)	7	2	2WU	NO	NO	YES	3.905	24	575	155	7.81	270	1,100	600	5,075		305	760					785	120	5.68
		11	SR 1835 (BLUES SIDING RD)	FROM US 15-501 TO LITTLE RIVER FARM RD	7	2	2WU	NO	NO	YES	1.434	20	215	35	2.87	165	445	100	1,530		92	365					290	50	1.04
<b>TOTAL FOR PROJ NO. 2016CPT.08.10.20631</b>											<b>11.223</b>		<b>1,660</b>	<b>690</b>	<b>22.45</b>	<b>435</b>	<b>1,545</b>	<b>1,035</b>	<b>13,410</b>		<b>805</b>	<b>5,720</b>					<b>2,260</b>	<b>370</b>	<b>15.28</b>
<b>GRAND TOTAL</b>											<b>26.047</b>		<b>2,635</b>	<b>690</b>	<b>34.62</b>	<b>43,770</b>	<b>3,815</b>	<b>3,015</b>	<b>17,945</b>	<b>8,830</b>	<b>1,597</b>	<b>12,120</b>	<b>39,320</b>	<b>163,782</b>	<b>13</b>	<b>20</b>	<b>5,082</b>	<b>830</b>	<b>35.68</b>