PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.12.06.10551 2017CPT.12.06.20551	15	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/ GENERAL WARNING SIGNING SF	4457000 TEMP. TRAFFIC CONTROL LS	4510000 LAW ENFORCEMENT HR	4700000000-E 12" X 90 M WHITE THERMO LF	12" X 90 M YELLOW THERMO LF	4705000-E 16" X 120 M WHITE THERMO LF	4710000 24" X 120 M WHITE THERMO LF	4721000000-E THERMO MSG ONLY 120 M EA	THERMO RXR 120 M EA	4725000000-E THERMO LT ARROW 90 M EA	THERMO RT ARROW 90 M EA	THERMO STR ARROW 90 M EA	THERMO MERGE ARROW 90M EA	THERMO STR & RT ARROW 90 M EA	THERMO STR & LT ARROW 90 M EA	4810000000-E 4" YELLOW PAINT LF	4" WHITE PAINT LF	4815000000-E 6" WHITE PAINT LF	6" YELLOW PAINT LF	4825000 12" WHITE PAINT LF	4835000 24" WHITE PAINT LF	4845000000-N PAINT ARROW LT EA	PAINT ARROW RT EA	PAINT ARROW MERGE EA	4847000000 POLY-UREA PAV. MARKING LINES (4", HRE) LF	4847100000 POLY-UREA PAV. MARKING LINES (6", HRE) LF	4847110000 POLY-UREA PAV. MARKING LINES (8", HRE) LF	4847120000 POLY-UREA PAV. MARKING LINES (12", HRE) LF	4855000 6" LINE REMOVAL LF	4905000000-N SNOW PLOWABLE MARKERS EA
2017CPT.12.06.10551	Lincoln	1	US 321 (NB LANES & RAMPS)	FROM HIGH SHOALS BRIDGE TO 2000' N. OF NC 27/150 BRIDGE	1,7	2	MD	5.07	28	1,257	*	50				14			3	3		9					36,900	30,200	1,450	14	3	3	9		67,100		1,450	1,600	425
		2	US 321-B (GENERALS BLVD)	FROM NC 27/150 TO END C&G 500' N. OF SR 1282	2,8	3	MU	2.23	24-36	425						265	8		66	8			4		12,000	1,000				65	24	3		52,000					400
		3	NC 150 (CROUSE BYPASS)	FROM GASTON CO TO A POINT 1500' E. OF SR 2098	9	4	MD	2.00	60	360			110	75		440	8		30	10	30												54,500		1250			620
TOTAL FOR PROJ NO. 2017CPT.12.06.10551								**9.30**		**2,042**	**1**	**50**	**110**	**75**		**719**	**16**		**99**	**21**	**30**	**9**	**4**		**12,000**	**1,000**	**36,900**	**30,200**	**1,450**	**79**	**27**	**6**	**9**	**106,500**	**67,100**	**1,250**	**1,450**	**1,600**	**1,445**
													185				**16**		**163**						**13,000**		**67,100**					**42**							
2017CPT.12.06.20551	Lincoln	4	SR 1439 (UNITY CHURCH RD)	FROM NC 16 BUS. TO EOM	2	2	2WU	2.38	20	175	*					26				1				1	49,000	50,500												
		5	SR 1385 (SCHRONCE RD)	FROM NC 73 TO SR 1383	2	2	2WU	1.24	20	175															26,000	26,300												
		6	SR 1360 (BREVARD PL RD)	FROM SR 1359 TO BRIDGE #015	2	2	2WU	1.99	20	246															41,000	42,250												
		7	SR 1282 (BETHEL CH RD)	FROM US 321B TO SR 1005	2	2	2WU	1.54	20	175						24									32,500	32,650												
		8	SR 1218 (WILFONG RD)	FROM SR 1008 TO CUL-DE-SAC	2	2	2WU	0.76	20	175															16,200	16,200												
		9	SR 1550 (HIDDEN VALLEY AVE)	FROM SR 1001 TO SR 1551	4	2	2WU	0.14	18	125																												
		10	SR 1551 (WHISPERING PINES RD)	FROM SR 1552 TO EOM	4	2	2WU	0.26	18																													
		11	SR 1552 (LAUREL HILL/MIDOAK)	FROM SR 1551 TO EOM	4	2	2WU	0.26	18																													
		12	SR 1638 (PRUITT HOUSER ST)	FROM SR 1334 TO EOM	5	2	2WU	0.15	20	125																												
		13	SR 2006 (HAZELWOOD LN)	FROM SR 1005 TO SR 2007	6	2	2WU	0.09	20	100																												
		14	SR 2007 (HAZELWOOD LN)	FROM SR 2006 TO SR 1005	6	2	2WU	0.23	20	100																												
		15	SR 2028 (RIVER VILLAGE LN)	FROM SR 1268 TO CUL-DE-SAC	3	2	2WU	0.18	18	125																												
		16	SR 1600 (SIPE RD)	FROM SR 1599 TO SR 1602	4	2	2WU	0.14	18																3,000	3,000												
		17	SR 1601 (DORSET LN)	FROM SR 1598 TO SR 1600	4	2	2WU	0.34	18																7,300	7,300												
		18	SR 1598 (LINCOLNVIEW RD)	FRO SR 1597 TO SR 1599	2	2	2WU	0.41	18	125															8,750	8,750												
		19	SR 1599 (BETTERBROOK LN)	FROM SR 1598 TO SR 1600	4	2	2WU	0.34	18	125															7,300	7,300												
		20	SR 1602 (BEXLEY LN)	FROM SR 1598 TO SR 1600	4	2	2WU	0.34	18																7,300	7,300												
		21	SR 1661 (PINE VILLAGE DR)	FROM NC 27 TO SR 1726	6	2	2WU	0.04	20	125																												
		22	SR 1726 (QUARTZ TRAIL)	FROM SR 1730 TO SR SR 1727	6	2	2WU	0.12	20																													
		23	SR 1730 (CHESTNUT RD)	FROM SR 1726 TO SR 1729	6	2	2WU	0.22	20																													
		24	SR 1727 (BIRCH ST)	FROM SR 1726 TO SR 1729	6	2	2WU	0.17	20																													
		25	SR 1729 (ELM ST)	FROM SR 1730 TO SR 1320	6	2	2WU	0.20	20																													
		26	SR 1728 (POPLAR ST)	FROM SR 1730 TO SR 1320	6	2	2WU	0.16	20																													
		27	SR 1320 (RANGE RD)	FROM NC 27 TO EOM	4	2	2WU	0.59	20	125					100	50		4																				
		28	SR 1450 (MCINTOSH RD)	FROM NC 16 BUS. TO EOM	2	2	2WU	0.42	18	100																												
		29	SR 1955 (STERLING CT)	FROM SR 1450 TO CUL-DE-SAC	4	2	2WU	0.30	18																													
		30	SR 1935 (DALMATION ST)	FROM NC 73 TO SR 1936	6	2	2WU	0.14	20	100																												
		31	SR 1936 (DACHSHUND LN)	FROM SR 1935 TO CUL-DE-SAC	6	2	2WU	0.22	20																													
		32	SR 1937 (PUG LN)	FROM SR 1936 TO CUL-DE-SAC	6	2	2WU	0.28	18																													
		33	SR 1964 (AUSTIN SHORES)	FROM SR 1674 TO CUL-DE-SAC	6	2	2WU	0.21	18																													
		34	SR 1674 (WHITE OAK LN)	FROM SR 1378 TO EOM	6	2	2WU	0.11	18	100																												
		35	SR 1939 (MARINER LN)	FROM SR 1377 TO CUL-DE-SAC	5	2	2WU	0.15	18	75																												
		36	SR 1590 (CHERRY PT RD)	FROM NC 16 BUS. TO EOM	6	2	2WU	0.34	18	100																												
		37	SR 1744 (LUCKY CRK LN)	FROM SR 1590 TO CUL-DE-SAC	6	2	2WU	0.49	18																													
		38	SR 1717 (MALLARD RD)	FROM SR 1479 TO CUL-DE-SAC	6	2	2WU	0.41	18																													
		39	SR 1716 (CAPTAINS WAY)	FROM SR 1441 TO SR 1717	6	2	2WU	0.02	20	100																												
		40	SR 1479 (YACHT CLUB DR)	FROM SR 1441 TO CUL-DE-SAC	6	2	2WU	0.22	20	100																												
		41	SR 1787 (LITHIA PARK DR)	FROM US 321-B TO EOM	4	2	2WU	0.17	18	75																												
		42	SR 1548 (RHYNE FOREST RD)	FROM NC 27 TO SR 1683	2	2	2WU	0.24	18	100															5,000	5,100												
		43	SR 1605 (GILROY RD)	FROM EOM TO EOM	4	2	2WU	0.16	18																													
		44	SR 1683 (GRAY FOX LN)	FROM SR 1548 TO EOM	4	2	2WU	0.09	18																													
		45	SR 1442 (BROOKWOOD DR)	FROM SR 1335 TO SR 1335	6	2	2WU	1.00	18	125																												
		46	SR 1566 (BROOKHAVEN DR)	FROM SR 1442 TO SR 1442	6	2	2WU	0.28	18																													
		47	SR 1324 (CATAWBA HTS RD)	FROM SR 1001 TO SR 1325	4	2	2WU	0.19	18	125																												
		48	SR 1325 (LAKE ST)	FROM SR 1001 TO EOM	4	2	2WU	0.56	18	125																												
		49	SR 1792 (GRANT DR)	FROM SR 1393 TO EOM	6	2		0.18	18																													
TOTAL FOR PROJ NO. 2017CPT.12.06.20551								**18.47**		**3,246**	**1**				**100**	**100**		**4**		**1**				**1**	**203,350**	**206,650**												
																	4		**2**						**410,000**													
GRAND TOTAL								**27.77**		**5,288**	**1**	**50**	**110**	**75**	**100**	**819**	**16**	**4**	**99**	**22**	**30**	**9**	**4**	**1**	**215,350**	**207,650**	**36,900**	**30,200**	**1,450**	**79**	**27**	**6**	**9**	**106,500**	**67,100**	**1,250**	**1,450**	**1,600**	**1,445**
													185				**20**		**165**						**423,000**		**67,100**					**42**							