

<p><b>SIGN NUMBER:</b> SP-1      <b>BACKG COLOR:</b> Fluorescent Orange  <b>TYPE:</b> STATIONARY      <b>COPY COLOR:</b> Black  <b>QUANTITY:</b> SEE PLANS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>SYMBOL</th> <th>X</th> <th>Y</th> <th>WID</th> <th>HT</th> </tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </table> <p><b>SIGN WIDTH:</b> 4'-6"  <b>HEIGHT:</b> 1'-0"  <b>TOTAL AREA:</b> 4.5 Sq.Ft.</p> <p><b>BORDER TYPE:</b> INSET  <b>RECESS:</b> 0.47"  <b>WIDTH:</b> 0.63"  <b>RADII:</b> 1.5"</p> <p style="text-align: center;"><b>MAT'L:</b> 0.080" (2.0 mm) ALUMINUM</p>	SYMBOL	X	Y	WID	HT																															<p><b>DESIGN BY:</b> R DRAYTON      <b>CHECKED BY:</b> S MILLER  <b>PROJECT ID:</b> U-2707      <b>DIV:</b> 9  <b>DATE:</b> Nov 05, 2015</p>	<div style="text-align: center;"> </div> <p><b>BORDER</b>  <b>R=1.5"</b>  <b>TH=0.63"</b>  <b>IN=0.47"</b></p>
SYMBOL	X	Y	WID	HT																																	
<p><b>USE NOTES:</b> 1,2</p> <p>1. Legend and border shall be direct applied black non-reflective sheeting.          2. Background shall be NC GRADE B fluorescent orange retroreflective sheeting.</p>																																					
<p>Spacing Factor is 1 unless specified otherwise</p>																																					

**LETTER POSITIONS**

Letter spacings are to start of next letter													Series/Size
	H	A	M	P	T	O	N		R	D			Text Length
	5.1	4.2	4.7	5.3	4.1	3.8	4.7	3.4	6	4.4	3.4	5.1	C 2000
													43.9

FILENAME: U-2707 Sign Design NORTH CAROLINA D.O.T. SIGN DETAIL

I:\2015\12\8\2015\G:\Transportation\TRI3.017.00 NCDOT 2012 Traffic LSA\TRI3.017.02 (U-2707)\TMP\U-2707 TMP-2.dgn

1025 Wade Avenue  
 Raleigh, NC 27605  
 Tel: 919-789-9977  
 Fax: 919-789-9591  
 License: C-2197

APPROVED: *Steve Miller*  
09BC0C15CEE8488

DATE: 12/16/2015

SEAL

**DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED**



**SPECIAL SIGN DESIGN**