

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.05.08.10731.1, 2016CPT.05.08.20731.1	10	

## SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BORROW	INCIDENTAL STONE BASE	SHOULDER RECONSTRUCTION	1 1/2" MILLING	.75" MILLING	INCIDENTAL MILLING	SURFACE COURSE, SF9.5B	SURFACE COURSE, SF9.5A	LEVELING COURSE, TYPE SF9.5A	SURFACE COURSE, S4.75A	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	CONCRETE CURB RAMP (Std. 848.05)	REMOVE AND REPLACE 6" CONCRETE DRIVEWAY	REMOVE AND REPLACE 2' - 6" CURB AND GUTTER	TEMPORARY SILT FENCE	WATTLE	SEED & MULCHING	INDUCTIVE LOOP	
										MI	FT	CY	TONS	SMI	SY	SY	SY	TONS	TON	TONS	TONS	TON	TONS	EA	SY	LF	LF	LF	AC	LF	
2016CPT.05.08.10731.1	Person	1	NC 49	CASWELL CO TO BEGIN C&G	1	2	2WU	NO	YES	11.55	32-44	3,465	300	23.10			1,500	20,328				1,220	2,000				500	100	16.50		
<b>TOTAL FOR MAP NO. 1</b>										11.55		3,465	300	23.10			1,500	20,328				1,220	2,000			500	100	16.50			
2016CPT.05.08.10731.1	Person	2	NC 157 GUESS RD	ORANGE CO TO SR 1107 (HURDLE MILLS RD)	1	2	2WU	NO	YES	2.5	24-25	750	60	5.00	304		550	3,221				193	500				400	100	3.60		
<b>TOTAL FOR MAP NO. 2</b>										2.5		750	60	5.00	304		550	3,221				193	500			400	100	3.60			
2016CPT.05.08.10731.1	Person	3	US 501	SR 1524 ALLIE CLAY RD. TO VIRGINA	1	2	2WU	NO	YES	9	24-42	2,700	260	18.00			2,000	12,478				749	900				2,000	500	13.10		
<b>TOTAL FOR MAP NO. 3</b>										9		2,700	260	18.00			2,000	12,478				749	900			2,000	500	13.10			
<b>TOTAL FOR PROJ NO. 2016CPT.05.08.10731.1</b>										23.05		6,915	620	46.10	304		4,050	36,027				2,162	3,400			2,900	700	33.20			
2016CPT.05.08.20731.1	Person	4	SR 1111 ROBERT WHITFIELD RD	NC 49 TO SR 1107 UNION GROVE CHURCH RD.	2	2	2WU	NO	NO	2.25	20-21	675	100	4.50	90		500		2,330	150		165	500				400	100	3.20		
<b>TOTAL FOR MAP NO. 4</b>										2.25		675	100	4.50	90		500		2,330	150		165	500			400	100	3.20			
2016CPT.05.08.20731.1	Person	5	SR 1125 NED MOORE RD	SR 1123 DICK HOLEMAN RD TO ORANGE COUNTY	3	2	2WU	NO	NO	2.4	20-21	360	130	4.80		29,079			2,534			170	300				400	100	3.50		
<b>TOTAL FOR MAP NO. 5</b>										2.4		360	130	4.80		29,079			2,534			170	300			400	100	3.50			
2016CPT.05.08.20731.1	Person	6	SR 1202 CC ANDREWS RD	US 501 TO SR 1125 NED MOORE RD	3	2	2WU	NO	NO	1	20-21	150	60	2.00		11,921			1,039			70	150							1.50	
<b>TOTAL FOR MAP NO. 6</b>										1		150	60	2.00		11,921			1,039			70	150						1.50		
2016CPT.05.08.20731.1	Person	7	SR 1128 TOM OAKLEY RD	SR 1129 FRANK TIMBERLAKE RD TO PAVEMENT CHANGE	2	2	2WU	NO	NO	0.7	20	210	30	1.40			400		716			48	300				400	100	1.00		
<b>TOTAL FOR MAP NO. 7</b>										0.7		210	30	1.40			400		716			48	300			400	100	1.00			
2016CPT.05.08.20731.1	Person	8	SR 1133 CLAY LONG RD	NC 157 TO SR 1129 FRANK TIMBERLAKE RD	2	2	2WU	NO	NO	2.75	20	825	100	5.40			400		2,813			188	300				400	100	3.90		
<b>TOTAL FOR MAP NO. 8</b>										2.75		825	100	5.40			400		2,813			188	300			400	100	3.90			
2016CPT.05.08.20731.1	Person	9	SR 1749 WELDON PAINTER RD	US 501 TO DEAD END	2	2	2WU	NO	NO	0.6	20-21	180	40	1.20			200		626			42	200				400	100	0.90		
<b>TOTAL FOR MAP NO. 9</b>										0.6		180	40	1.20			200		626			42	200			400	100	0.90			
2016CPT.05.08.20731.1	Person	10	SR 1769 WOODY DR	SR 1749 TO CUL-DE-SAC	4	2	2WU	NO	NO	0.5	20-21	25									270	18	50								
<b>TOTAL FOR MAP NO. 10</b>										0.5		25								270	18	50									
2016CPT.05.08.20731.1	Person	11	SR 1773 ANN DRIVE	SR 1769 TO CUL-DE-SAC	4	2	2WU	NO	NO	0.4	20-21	20									211	14	50								
<b>TOTAL FOR MAP NO. 11</b>										0.4		20								211	14	50									
2016CPT.05.08.20731.1	Person	12	SR 1775 FORK JUNCTION	SR 1773 TO DEAD END	4	2	2WU	NO	NO	0.3	18-19	20									144	10	10								
<b>TOTAL FOR MAP NO. 12</b>										0.3		20								144	10	10									
2016CPT.05.08.20731.1	Person	13	SR 1711 KERMIT DUNCAN RD	SR 1708 ANTIOCH CHURCH RD TO SR 1709 DINK ASHLEY RD	2	2	2WU	NO	NO	1.7	20-21	510	90	3.40			400		1,766			118	300				400	100	2.50		
<b>TOTAL FOR MAP NO. 13</b>										1.7		510	90	3.40			400		1,766			118	300			400	100	2.50			
2016CPT.05.08.20731.1	Person	14	SR 1771 RIVER OAKS DRIVE	SR 1709 DINK ASHLEY ROAD TO DEAD END	4	2	2WU	NO	NO	0.5	18-19		25								249	17	75								
<b>TOTAL FOR MAP NO. 14</b>										0.5			25							249	17	75									
2016CPT.05.08.20731.1	Person	15	SR 1780 OAKS LANE	SR 1771 TO END STATE MAINTENANCE	4	2	2WU	NO	NO	0.5	18		20								219	15	50								
<b>TOTAL FOR MAP NO. 15</b>										0.5			20							219	15	50									
2016CPT.05.08.20731.1	Person	16	SR 1772 SCENIC DRIVE	SR 1771 TO DEAD END	4	2	2WU	NO	NO	0.1	18-19		5								57	4	10								
<b>TOTAL FOR MAP NO. 16</b>										0.1			5							57	4	10									
2016CPT.05.08.20731.1	Person	17	SR 1721 MT HARMONY CH RD	US 158 TO SR 1715 (HELENA MORIAH RD)	5	2	2WU	NO	NO	7	20-21		240		84,945				7,403			496	500								
<b>TOTAL FOR MAP NO. 17</b>										7			240		84,945				7,403			496	500								
2016CPT.05.08.20731.1	Person	18	SR 1741 CHAMBERS LOOP RD	FROM US 501 TO SR 1742	2	2	2WU	NO	NO	1	20	300	60	2.00			250		1,023	50		72	200							1.40	
<b>TOTAL FOR MAP NO. 18</b>										1		300	60	2.00			250		1,023	50		72	200						1.40		
2016CPT.05.08.20731.1	Person	19	SR 1742 CHAMBERS LOOP RD	SR 1741 TO US 501	2	2		NO	NO	1.5	20	450	64	3.00			250		1,534	50		106	100							2.20	
<b>TOTAL FOR MAP NO. 19</b>										1.5		450	64	3.00			250		1,534	50		106	100							2.20	
2016CPT.05.08.20731.1	Person	20	SR 1743 HOWARD CLAYTON RD	SR 1742 TO DEAD END	2	2	2WU	NO	NO	0.2	20	60	8	0.40					205			14	75							0.20	
<b>TOTAL FOR MAP NO. 20</b>										0.2		60	8	0.40					205			14	75							0.20	
2016CPT.05.08.20731.1	Person	21	SR 1120 BERRY PIERCE RD	OCL TO SR 1134 (SATTERFIELD RD)	2	2	2WU	NO	NO	3	20-21	900	84	6.00			900		3,238	30		219	350				800	200	4.00		
<b>TOTAL FOR MAP NO. 21</b>										3		900	84	6.00			900		3,238	30		219	350			800	200	4.00			
2016CPT.05.08.20731.1	Person	22	SR 1174 AUBREY CLAYTON RD	SR 1102 GORDONTON RD TO SR 1162 WILSON RD	2	2	2WU	NO	NO	1.1	20	330	52	2.20			400		1,125	100		81	150							1.60	
<b>TOTAL FOR MAP NO. 22</b>										1.1		330	52	2.20			400		1,125	100		81	150							1.60	
2016CPT.05.08.20731.1	Person	23	SR 1552 CEDAR GROVE CHURCH RD	SR 1536 TO SR 1536	2	2	2WU	NO	NO	2.3	20-21	690	100	4.50			800		2,484			166	300							3.00	
<b>TOTAL FOR MAP NO. 23</b>										2.3		690	100	4.50			800		2,484			166	300						3.00		
2016CPT.05.08.20731.1	Person	24	SR 1763 WOODROW ASHLEY RD	SR 1711 TO DEAD END	4	2	2WU	NO	NO	0.3	18		20								131	9	100								
<b>TOTAL FOR MAP NO. 24</b>										0.3			20							131	9	100									
2016CPT.05.08.20731.1	Person	25	SR 1774 CRYSTAL LAKE RD	SR 1711 TO DEAD END	4	2	2WU	NO	NO	0.1	18-19		15								56	4	20								
<b>TOTAL FOR MAP NO. 25</b>										0.1			15							56	4	20									
2016CPT.05.08.20731.1	Person	26	SR 1567 PIXLEY PRITCHARD RD	US 158 TO GRANVILLE COUNTY	2	2	2WU	NO	NO	5.7	20-21	5,130	300	11.40	450		600		5,967	1,000		460	1,000				800	80	8.30		
<b>TOTAL FOR MAP NO. 26</b>										5.7		5,130	300	11.40	450		600		5,967	1,000		460	1,000								