

| | | |
|---|-----------|-----------|
| PROJECT NO. | SHEET NO. | TOTAL NO. |
| 2016CPT.12.04.10021, 2016CPT.12.04.20021 2016CPT.12.04.20022 | 12 | |

SUMMARY OF QUANTITIES

| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP | LANES | FINAL SURFACE TESTING REQUIRED | WARM MIX ASPHALT REQUIRED | LENGTH MI | WIDTH FT | SOIL CEMENT BASE (FULL DEPTH RECLAMATION) SY | AGGREGATE SHOULDER BORROW TON | PORTLAND CEMENT FOR SOIL CEMENT BASE TON | INCIDENTAL STONE BASE TONS | SHOULDER RECONSTRUCTION SMI | 0" TO 1.5" MILLING SY | INCIDENTAL MILLING SY | BASE COURSE, B25.0B TONS | SURFACE COURSE, S9.5B TONS | LEVELING COURSE, S9.5B TONS | ASPHALT BINDER FOR PLANT MIX TONS | PATCHING EXISTING PAVEMENT TONS | ADJ. OF CATCH BASIN EA | ADJ. OF METER OR VALVE BOX EA | | |
|---|-----------|--------|-----------------------------------|---|-------------|-------|--------------------------------|---------------------------|---------------|-------------------------|--|-------------------------------|--|----------------------------|-----------------------------|-----------------------|-----------------------|--------------------------|----------------------------|-----------------------------|-----------------------------------|---------------------------------|------------------------|-------------------------------|----------|--|
| 2016CPT.12.04.10021 | Alexander | 1 | NC 16 | 0.4 MILES NORTH OF SR 1405 (JOLLY CEMETARY RD.) TO WILKES CO. LINE | 1 2 3 | 2 | NO | NO | 5.104 | 24-32 43-44 55-57 | | 900 | | 200 | 11.00 | | 500 | | 9,300 | 1,400 | | 649 | 100 | | | |
| TOTAL FOR MAP NO. 1 | | | | | | | | | 5.104 | | | 900 | | 200 | 11.00 | | 500 | | 9,300 | 1,400 | | 649 | 100 | | | |
| TOTAL FOR PROJ NO. 2016CPT.12.04.10021 | | | | | | | | | 5.104 | | | 900 | | 200 | 11.00 | | 500 | | 9,300 | 1,400 | | 649 | 100 | | | |
| 2016CPT.12.04.20021 | Alexander | 2 | SR 1491 (HILL RIVER RD.) | FROM SR 1001 (SULPHUR SPRING RD.) TO SR 1492 (DUNCAN LN.) | 7 | 2 | NO | NO | 0.648 | 18-22 | | | | 80 | | | 100 | | 1,081 | | | 65 | | | | |
| TOTAL FOR MAP NO. 2 | | | | | | | | | 0.648 | | | | | 80 | | | 100 | | 1,081 | | | 65 | | | | |
| 2016CPT.12.04.20021 | Alexander | 3 | SR 1001 (SULPHUR SPRINGS RD.) | FROM NC 90 TO SR 1503 (HIDDENITE CHURCH RD.) | 6 | 2 | NO | NO | 0.691 | 19-26 | | | | 50 | | 450 | 200 | | 1,030 | 275 | | 80 | 150 | 1 | 6 | |
| TOTAL FOR MAP NO. 3 | | | | | | | | | 0.691 | | | | | 50 | | 450 | 200 | | 1,030 | 275 | | 80 | 150 | 1 | 6 | |
| 2016CPT.12.04.20021 | Alexander | 4 | SR 1419 (ROCKY SPRINGS RD.) | FROM SR 1412 (BLACK OAK RIDGE RD.) TO SR 1001 (SULPHUR SPRINGS RD.) | 5 | 2 | NO | NO | 5.36 | 18 | | | | 225 | | 500 | 800 | 3,650 | 6,730 | 3,760 | | 809 | 700 | | | |
| TOTAL FOR MAP NO. 4 | | | | | | | | | 5.36 | | | | | 225 | | 500 | 800 | 3,650 | 6,730 | 3,760 | | 809 | 700 | | | |
| 2016CPT.12.04.20021 | Alexander | 5 | SR 1647 (WILDWOOD CIRCLE) | FROM SR 1609 (COUNTY HOME RD.) TO SR 1647 (WILDWOOD CIRCLE) | 4 | 2 | NO | NO | 0.717 | 20-22 | | | | 20 | | | | | 875 | 375 | | 77 | 200 | | | |
| TOTAL FOR MAP NO. 5 | | | | | | | | | 0.717 | | | | | 20 | | | | | 875 | 375 | | 77 | 200 | | | |
| 2016CPT.12.04.20021 | Alexander | 6 | SR 1657 (ISENHOURL PARK RD.) | FROM NC 16 TO DEAD END | 4 | 2 | NO | NO | 0.265 | 20-22 | | | | 30 | | | | | 350 | 35 | | 23 | 45 | | | |
| TOTAL FOR MAP NO. 6 | | | | | | | | | 0.265 | | | | | 30 | | | | | 350 | 35 | | 23 | 45 | | | |
| 2016CPT.12.04.20021 | Alexander | 7 | SR 1658 (ISENHOURL PARK RD. EXT.) | FROM SR 1657 (ISENHOURL PARK RD.) TO DEAD END | 4 | 2 | NO | NO | 0.129 | 20-22 | | | | 10 | | | | | 185 | 20 | | 12 | 45 | | | |
| TOTAL FOR MAP NO. 7 | | | | | | | | | 0.129 | | | | | 10 | | | | | 185 | 20 | | 12 | 45 | | | |
| 2016CPT.12.04.20021 | Alexander | 8 | SR 1662 (ST. JAMES LANE) | FROM SR 1658 (ISENHOURL PARK RD. EXT.) TO DEAD END | 4 | 2 | NO | NO | 0.072 | 20-22 | | | | 10 | | | | | 100 | 10 | | 7 | 10 | | | |
| TOTAL FOR MAP NO. 8 | | | | | | | | | 0.072 | | | | | 10 | | | | | 100 | 10 | | 7 | 10 | | | |
| 2016CPT.12.04.20021 | Alexander | 9 | SR 1313 (THREE FORKS CHURCH RD.) | FROM SR 1307 (ALL HEALING SPRING) TO SR 1311 (GILL CHILDRESS RD) | 5 | 2 | NO | NO | 0.444 | 18 | | | | 15 | | | 100 | 300 | 620 | 350 | | 73 | 100 | | | |
| TOTAL FOR MAP NO. 9 | | | | | | | | | 0.444 | | | | | 15 | | | 100 | 300 | 620 | 350 | | 73 | 100 | | | |
| 2016CPT.12.04.20021 | Alexander | 10 | SR 1208 (SHILOH CHURCH RD.) | FROM NC 127 TO NC 127 | 4 | 2 | NO | NO | 1.209 | 20-22 | | | | 30 | | | 200 | | 1,770 | 500 | | 139 | 50 | | 3 | |
| TOTAL FOR MAP NO. 10 | | | | | | | | | 1.209 | | | | | 30 | | | 200 | | 1,770 | 500 | | 139 | 50 | | 3 | |
| 2016CPT.12.04.20021 | Alexander | 11 | SR 1290 (STARNES CIRCLE DR.) | FROM SR 1148 (RIVER HILLS CT.) TO DEAD END | 4 | 2 | NO | NO | 0.421 | 20-22 | | | | 30 | | | | | 550 | 55 | | 37 | 155 | | | |
| TOTAL FOR MAP NO. 11 | | | | | | | | | 0.421 | | | | | 30 | | | | | 550 | 55 | | 37 | 155 | | | |
| TOTAL FOR PROJ NO. 2016CPT.12.04.20021 | | | | | | | | | 9.956 | | | | | 500 | | 950 | 1,400 | 3,950 | 13,291 | 5,380 | | 1,322 | 1,455 | 1 | 9 | |
| 2016CPT.12.04.20022 | Alexander | 2 | SR 1491 (HILL RIVER RD.) | FROM SR 1001 (SULPHUR SPRINGS RD.) TO SR 1492 (DUNCAN LN.) | 7 | 2 | NO | NO | 0.648 | 18-22 | 8,300.00 | | 335.00 | | | | | | | | | | | | | |
| TOTAL FOR MAP NO. 2 | | | | | | | | | 0.648 | | 8,300.00 | | 335.00 | | | | | | | | | | | | | |
| TOTAL FOR PROJ NO. 2016CPT.12.04.20022 | | | | | | | | | 0.648 | | 8,300.00 | | 335.00 | | | | | | | | | | | | | |
| GRAND TOTAL | | | | | | | | | 15.708 | | 8,300.00 | 900 | 335.00 | 700 | 11.00 | 950 | 1,900 | 3,950 | 22,591 | 6,780 | 1,971 | 1,555 | 1 | 9 | | |