PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.06.08.10091.1, etc	12	

THERMOPLASTIC AND PAINT QUANTITIES

										4457000000-N	4413000000-E	4685000000-E		4686000000-E		4695000000-E		469700000	4710000000-I	4725000000-E				
PROJECT	COUNTY	MAP	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	LENGTH	WIDTH	TEMP. TRAFFIC CONTROL	WORK ZONE ADVANCE/ GENERAL WARNING SIGNING	4" X 90 M WHITE THERMO	4" X 90 M YELLOW THERMO	4" X 120 M YELLOW THERMO	4" X 120 M WHITE THERMO	8" X 90 M WHITE THERMO	8" X 90 M YELLOW THERMO	8" X 120 M WHITE THERMO	24" X 120 M WHITE THERMO	THERMO LT ARROW 90 M	THERMO RT ARROW 90 M	THERMO STR ARROW 90 M	THERMO STR & RT ARROW 90 M	THERMO MERGE ARROW 90 M
NO		NO			NO			MI	FT	LS	SF	LF	LF	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA
2016CPT.06.08.10091.1	Bladen	1	NC 53-A	FROM SR 1560 TO SR 1515	1	2	2WU	4.53	25		507	48,200		33,740					60					
2016CPT.06.08.10091.1	Bladen	2	NC 53-B	FROM SR 1515 TO TIMBERLODGE VILLAGE DR.	2	2	2WU	0.5	31		126	5,410		4,250			120			2				
2016CPT.06.08.10091.1	Bladen	3	NC 53-C	FROM TIMBERLODGE VILLAGE DR. TO US 701	3	2	2WU	2.16	29		242	22,810		14,300										
2016CPT.06.08.10091.1	Bladen	4	NC 131	FROM NC 211 BYP. TO NC 410	4	2	2WU	4.89	24	*	548	51,900		40,550	425	100	780		40	3	1	1	1	
2016CPT.06.08.10091.1	Bladen	5	NC 410-A	FROM NC 131 TO SR 1003	5	2	2WU	3.17	24		355	32,600		28,490	325		2,020		310	3	4			
2016CPT.06.08.10091.1	Bladen	6	NC 410-B	FROM SR 1003 TO NC 87	6	4	MU	0.13	40		126			1,370	500						4			
2016CPT.06.08.10091.1	Bladen	9	NC 210	FROM PENDER CL TO NC 53	8	2	2WU	3.71	25		416	39,500		27,440										
TOTAL FOR PROJ NO. 2016CPT.06.08.10091.1								**19.09**			**2,320**	**200,420**		**150,140**	**1,250**	**100**	**2,920**		**410**	**8**	**9**	**1**	**1**	
												200,420		**151,390**		**3,020**						**19**		
2016CPT.06.08.20091.1	Bladen	7	SR 1208	FROM NC 131 TO END MAINT.	7	2	2WU	0.55	20		62													
2016CPT.06.08.20091.1	Bladen	8	SR 1225	FROM SR 1208 TO DEAD END	7	2	2WU	0.1	20	*	11													
TOTAL FOR PROJ NO. 2016CPT.06.08.20091.1								**0.65**			**73**													
2016CPT.06.08.10241.1	Columbus	10	NC 214-A	FROM US 74 BUS. TO SIXTEENTH ST.	9	2	2WU	14.87	23		1,665	157,990		92,360		1,090		50	25		1			
2016CPT.06.08.10241.1	Columbus	11	NC 214-B	FROM SIXTEENTH ST. TO SEVENTH ST.	10	2	2WU	0.45	36	*	126	4,750		4,750										
2016CPT.06.08.10241.1	Columbus	12	NC 214-C	SEVENTH ST. TO BEGIN DIVIDED HWY.	11	2	2WU	1.29	24		144	13,620		8,580					20					
2016CPT.06.08.10241.1	Columbus	13	NC 214-D	FROM BEGIN DIVIDED HWY. TO US 74	12	4	MD	1.31	44		147	13,540	13,540	1,600	3,985	1,100	300		24	12		19	4	5
TOTAL FOR PROJ NO. 2016CPT.06.08.10241.1								**17.92**			**2,082**	**189,900**	**13,540**	**107,290**	**3,985**	**2,190**	**300**	**50**	**69**	**12**	**1**	**19**	**4**	**5**
												203,440		**111,275**		**2,490**						**41**		
2016CPT.06.08.20241.1	Columbus	14	SR 1731	FROM SR 1740 TO SR 1730	8	2	2WU	4.76	20		533													
2016CPT.06.08.20241.1	Columbus	15	SR 1735	FROM SR 1730 TO NC 214	8	2	2WU	5.74	20	*	643													
TOTAL FOR PROJ NO. 2016CPT.06.08.20241.1								**10.5**			**1,176**													
GRAND TOTAL								**48.16**		**1**	**5,651**	**390,320**	**13,540**	**257,430**	**5,235**	**2,290**	**3,220**	**50**	**479**	**20**	**10**	**20**	**5**	**5**
												403,860		**262,665**		**5,510**						**60**		

THERMOPLASTIC AND PAINT QUANTITIES

										4721000000-E		4810000000-E		4820000000-E		4835000000-	4845000000-N					4900000000-N	
PROJECT	COUNTY	MAP	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	LENGTH	WIDTH	THERMO MSG SCHOOL 120 M	THERMO MSG ONLY 120 M	4" YELLOW PAINT	4" WHITE PAINT	8" WHITE PAINT	8" YELLOW PAINT	24" WHITE PAINT	PAINT LT ARROW	PAINT RT ARROW	PAINT STR ARROW	PAINT STR & RT ARROW	PAINT MERGE ARROW	YELLOW & YELLOW MARKERS	CRYSTAL & RED MARKERS
NO		NO			NO			MI	FT	EA	EA	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA
2016CPT.06.08.10091.1	Bladen	1	NC 53-A	FROM SR 1560 TO SR 1515	1	2	2WU	4.53	25			33,740										300	
2016CPT.06.08.10091.1	Bladen	2	NC 53-B	FROM SR 1515 TO TIMBERLODGE VILLAGE DR.	2	2	2WU	0.5	31			4,250					2					33	
2016CPT.06.08.10091.1	Bladen	3	NC 53-C	FROM TIMBERLODGE VILLAGE DR. TO US 701	3	2	2WU	2.16	29			14,300										143	
2016CPT.06.08.10091.1	Bladen	4	NC 131	FROM NC 211 BYP. TO NC 410	4	2	2WU	4.89	24													330	28
2016CPT.06.08.10091.1	Bladen	5	NC 410-A	FROM NC 131 TO SR 1003	5	2	2WU	3.17	24	12												207	90
2016CPT.06.08.10091.1	Bladen	6	NC 410-B	FROM SR 1003 TO NC 87	6	4	MU	0.13	40		8											13	
2016CPT.06.08.10091.1	Bladen	9	NC 210	FROM PENDER CL TO NC 53	8	2	2WU	3.71	25													250	
TOTAL FOR PROJ NO. 2016CPT.06.08.10091.1								**19.09**		**12**	**8**	**52,290**					**2**					**1,276**	**118**
											20	**52,290**							**2**			**1,394**	
2016CPT.06.08.20091.1	Bladen	7	SR 1208	FROM NC 131 TO END MAINT.	7	2	2WU	0.55	20														
2016CPT.06.08.20091.1	Bladen	8	SR 1225	FROM SR 1208 TO DEAD END	7	2	2WU	0.1	20														
TOTAL FOR PROJ NO. 2016CPT.06.08.20091.1								**0.65**															
2016CPT.06.08.10241.1	Columbus	10	NC 214-A	FROM US 74 BUS. TO SIXTEENTH ST.	9	2	2WU	14.87	23			92,360		1,140		25		1				987	
2016CPT.06.08.10241.1	Columbus	11	NC 214-B	FROM SIXTEENTH ST. TO SEVENTH ST.	10	2	2WU	0.45	36			4,750										30	
2016CPT.06.08.10241.1	Columbus	12	NC 214-C	SEVENTH ST. TO BEGIN DIVIDED HWY.	11	2	2WU	1.29	24			8,580				20						85	
2016CPT.06.08.10241.1	Columbus	13	NC 214-D	FROM BEGIN DIVIDED HWY. TO US 74	12	4	MD	1.31	44			15,140	17,540	1,100	300	24	12		19	4	5	15	200
TOTAL FOR PROJ NO. 2016CPT.06.08.10241.1								**17.92**				**120,830**	**17,540**	**2,240**	**300**	**69**	**12**	**1**	**19**	**4**	**5**	**1,117**	**200**
												138,370		**2,540**					**41**			**1,317**	
2016CPT.06.08.20241.1	Columbus	14	SR 1731	FROM SR 1740 TO SR 1730	8	2	2WU	4.76	20			34,860	49,800									310	
2016CPT.06.08.20241.1	Columbus	15	SR 1735	FROM SR 1730 TO NC 214	8	2	2WU	5.74	20			44,360	63,360									400	
TOTAL FOR PROJ NO. 2016CPT.06.08.20241.1								**10.5**				**79,220**	**113,160**									**710**	
												192,380										**710**	
GRAND TOTAL								**48.16**		**12**	**8**	**252,340**	**130,700**	**2,240**	**300**	**69**	**14**	**1**	**19**	**4**	**5**	**3,103**	**318**
											20	**383,040**		**2,540**					**43**			**3,421**	