

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.12.06.10231, 2016CPT.12.06.20231	11	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	AGGREGATE SHOULDER BORROW TON	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1½" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	LEVELING COURSE, S9.5C TONS	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	RETROFIT EXISTING CURB RAMP std.848.06 EA	ADJ. OF DROP INLETS EA	ADJ. OF MAN-HOLES EA	ADJ. OF METER OR VALVE BOXES EA	CONVERT EXISTING DI TO CB EA	FRAME W/ GRATE & HOOD std 840.03 TYPE 'E' EA	PORTABLE LIGHTING LS					
2016CPT.12.06.10231	Cleveland	1	US 74 (ANDREW JACKSON HWY)	SR-2244 (HARMON RD) TO 528 FT W OF GROVE ST	1 2 3	4	NO	NO	4.61 0.96 0.20	VAR. 58-96 VAR. 58-115 VAR. 58-120	3,633	360	20.56		4,980				20,534	1,881	1,334	4,581		8					*					
TOTAL FOR MAP NO. 1 - PROJ NO. 2016CPT.12.06.10231									5.77		3,633	360	20.56		4,980				20,534	1,881	1,334	4,581		8										
2016CPT.12.06.20231	Cleveland	2	SR-1121 (WESSON RD)	SR-1253 TO SR-1151	4 5 6	2	NO	NO	0.25 0.70 1.85	VAR. 36-37 20 20	893	75	5.10	5,970	465	317	3,287	553			247	985			7	10								
TOTAL FOR MAP NO. 2									2.8		893	75	5.10	5,970	465	317	3,287	553			247	985			7	10								
2016CPT.12.06.20231	Cleveland	3	SR-1161 (N. MAIN ST. / MCBRAYER HOMESTEAD RD)	NC-150 TO SR-1159	7 4 6 8	2	NO	NO	0.06 0.79 0.90 0.13	VAR. 36-37 VAR. 36-37 VAR. 24-36 VAR.25-36	338	80	1.93	18,885			3,284	325			218	926	5		11	10	12	12						
TOTAL FOR MAP NO. 3									1.88		338	80	1.93	18,885			3,284	325			218	926	5		11	10	12	12						
2016CPT.12.06.20231	Cleveland	4	SR-1343 (CHATFIELD RD)	NC-226 TO NC-226	6	2	NO	NO	4.22	VAR. 18-19	1,477	120	8.44		88		4,375	232			278	665												
TOTAL FOR MAP NO. 4									4.22		1,477	120	8.44		88		4,375	232			278	665												
2016CPT.12.06.20231	Cleveland	5	SR-1416 (BOYD CT)	SR-1343 TO DE	9	2	NO	NO	0.18	19		10			34		187	10			12	23												
TOTAL FOR MAP NO. 5									0.18			10			34		187	10			12	23												
2016CPT.12.06.20231	Cleveland	6	SR-1229 (SERVICE RD)	DE TO DE	6 10	2	NO	NO	1.48 0.05	VAR. 20-30 VAR. 20-26	537	30	3.01		240		1,856	152			121	655		1	1									
TOTAL FOR MAP NO. 6									1.53		537	30	3.01		240		1,856	152			121	655			1	1								
TOTAL FOR PROJ NO. 2016CPT.12.06.20231									10.61		3,245	315	18.48	24,855	827	317	12,989	1,272			876	3,254	5		1	19	20	12	12					
GRAND TOTAL									16.38		6,878	675	39.04	24,855	5,807	317	12,989	1,272			20,534	1,881	2,210	7,835	5	9	19	20	12	12			1	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LENGTH	WIDTH	4413000000	4457000000-N	4510000000-N	4695000000-E	4710000000	4725000000-E					4810000000-E		4847000000-E		4847100000-E	48471200	4905000000-N				
									WORK ZONE ADVANCE/ GENERAL WARNING SIGNING SF	TEMPORARY TRAFFIC CONTROL LS	LAW ENFORCEMENT HR	8" X 90 M YELLOW THERMO LF	24" X 120 M WHITE THERMO LF	THERMO MSG SCHOOL EA	THERMO RT ARROW 90 M EA	THERMO STR & RT ARROW 90 M EA	THERMO STR ARROW 90 M EA	THERMO LT ARROW 90 M EA	4" YELLOW PAINT LF	4" WHITE PAINT LF	4" WHITE POLYUREA (HRE) LF	4" YELLOW POLYUREA (HRE) LF	6" WHITE POLYUREA (HRE) LF	6" YELLOW POLYUREA (HRE) LF	12" WHITE POLYUREA (HRE) LF	SNOW PLOW-ABLE MARKERS EA			
2016CPT.12.06.10231	Cleveland	1	US 74 (ANDREW JACKSON HWY)	SR-2244 (HARMON RD) TO 528 FT W OF GROVE ST	1 2 3	2	4.61 0.96 0.20	VAR. 58-96 VAR. 58-115 VAR. 58-120	664	*	16		580		11	13	77	72							80,624	60,932	3,150	800	
TOTAL FOR PROJ NO. 2016CPT.12.06.10231									664		16		580		11	13	77	72							80,624	60,932	3,150	800	
														173							141,556								
2016CPT.12.06.20231	Cleveland	2	SR-1121 (WESSON RD)	SR-1253 TO SR-1151	4 5 6	2	0.25 0.70 1.85	VAR. 36-37 20 20	388	*										60,256	59,826								
TOTAL FOR MAP NO. 2									388												120,082								
2016CPT.12.06.20231	Cleveland	3	SR-1161 (N. MAIN ST. / MCBRAYER HOMESTEAD RD)	NC-150 TO SR-1159	7 4 6 8	2	0.06 0.79 0.90 0.13	VAR. 36-37 VAR. 36-37 VAR. 24-36 VAR.25-36	308	*		50	105	6		2		7					10,300	20,100			135		
TOTAL FOR MAP NO. 3									308			50	105	6		9		7				30,400							135
2016CPT.12.06.20231	Cleveland	4	SR-1343 (CHATFIELD RD)	NC-226 TO NC-226	6	2	4.22	VAR. 18-19	404	*											75,704	90,814							
TOTAL FOR MAP NO. 4									404												166,518								
2016CPT.12.06.20231	Cleveland	5	SR-1416 (BOYD CT)	SR-1343 TO DE	9	2	0.18	19	84	*																			
TOTAL FOR MAP NO. 5									84																				
2016CPT.12.06.20231	Cleveland	6	SR-1229 (SERVICE RD)	DE TO DE	6 10	2	1.48 0.05	VAR. 20-30 VAR. 20-26	260	*											33,571	33,571							
TOTAL FOR MAP NO. 6									260											67,142									
TOTAL FOR PROJ NO. 2016CPT.12.06.20231									1,444		50	105	6		2		7		169,531	184,211	10,300	20,100						135	
														9					353,742		30,400								
GRAND TOTAL									2,108	1	16	50	685	6	11	15	77	79	169,531	184,211	10,300	20,100	80,624	60,932	3,150	935			
														182					353,742		30,400		141,556						