



NOTE:

WHEN PREPARING THE SURFACE FOR LMC OVERLAY-VES ADJACENT TO A PREVIOUSLY PLACED LMC-VES STAGE, THE PREVIOUSLY PLACED LMC-VES SHALL BE REMOVED FOR A DISTANCE OF 4-INCHES FROM THE LMC-VES EDGE. THE SURFACE OF THE NEW STAGE AREA, ALONG WITH THE 4 INCH OVERLAY AREA, SHALL BE PREPARED AS PER THE OVERLAY SURFACE PREPARATION SPECIAL PROVISIONS. NEW LMC-VES SHALL BE PLACED IN THE 4-INCH OVERLAP, AS PART OF NEW LMC-VES STAGE PLACEMENT.

SEE TRAFFIC MANAGEMENT PLANS FOR LANE WIDTHS, SEQUENCE AND OTHER TRAFFIC CONTROL MEASURES FOR STAGING OF OVERLAY SURFACE PREPARATION AND LMC-VES PLACEMENT.




TYPICAL SECTION



SECTION THRU DECK
STAGED LMC-VES OVERLAY JOINT
(AS NEEDED)

PROJECT NO. I-5731
CUMBERLAND COUNTY
BRIDGE NO. 26



4/14/2016

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH SUPERSTRUCTURE						SHEET NO.
TYPICAL SECTION & LATEX MODIFIED CONCRETE-VES						S-4
REVISIONS						TOTAL SHEETS
NO.	BY:	DATE:	NO.	BY:	DATE:	37
1			3			
2			4			

DRAWN BY : M. WELDON DATE : 02/2016
CHECKED BY : W. SMITH DATE : 02/2016

14-APR-2016 17:00
R:\Structures\DCN\401.005.15731.SMU.S4.TS.26.DGN
f0sefnlo