PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.05.09.10351.1, 2016CPT.05.09.20351.1	14	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4510000000-N LAW ENFORCEMENT HR	4685000000-E 4" X 90 M WHITE THERMO LF	4685000000-E 4" X 90 M YELLOW THERMO LF	4686000000-E 4" X 120 M WHITE THERMO LF	4686000000-E 4" X 120 M YELLOW THERMO LF	4695000000-E 8" X 90 M YELLOW THERMO LF	4695000000-E 8" X 90 M WHITE THERMO LF	4697000000-E 8" X 120 M WHITE THERMO LF	4711000000-E 24" X 120 M WHITE THERMO LF	4721000000-E THERMO MSG SCHOOL 120 M EA	4725000000-E THERMO LT ARROW 90 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E THERMO STR & LT ARROW 90 M EA	4725000000-E THERMO STR & RT ARROW 90 M EA	4810000000-E 4" YELLOW PAINT LF	4810000000-E 4" WHITE PAINT LF	4820000000-E 8" YELLOW PAINT LF	4820000000-E 8" WHITE PAINT LF	4835000000-E 24" WHITE PAINT LF	4845000000-N PAINT LT ARROW EA	4845000000-N PAINT STR & RT ARROW EA	4845000000-N PAINT STR & LT ARROW EA	4845000000-N PAINT RT ARROW EA	4905000000-N SNOW PLOWABLE MARKERS EA
2016CPT.05.09.10351.1	Franklin	1	NC 39	JT WEST OF SR 1731 - CHEVES RD TO US 401	1	2	10.22	25-44	1,169	0.21	10	107,380	330	1,258	108,150	150		116	345	24	19												825
TOTAL FOR MAP NO. 1							**10.22**		**1,169**	**0.21**	**10**	**107,380**	**330**	**1,258**	**108,150**	**150**		**116**	**345**	**24**	**19**												**825**
2016CPT.05.09.10351.1	Franklin	2	NC 56	JT WEST OF US 1 TO SR 1222 - WILL MITCHINER RD	1,2	2	4.46	26-50	500	0.11	10	40,100		785	48,246	328	1,000	340	140		9	1	1	4	8,585	1,220	135	340	140	5	4	1	1	400
TOTAL FOR MAP NO. 2							**4.46**		**500**	**0.11**	**10**	**40,100**		**785**	**48,246**	**328**	**1,000**	**340**	**140**		**9**	**1**	**1**	**4**	**8,585**	**1,220**	**135**	**340**	**140**	**5**	**4**	**1**	**1**	**400**
TOTAL FOR PROJ NO. 2016CPT.05.09.10351.1							**14.68**		**1,669**	**0.32**	**20**	**147,480**	**330**	**2,043**	**156,396**	**478**	**1,000**	**456**	**485**	**24**	**28**	**1**	**1**	**4**	**8,585**	**1,220**	**135**	**340**	**140**	**5**	**4**	**1**	**1**	**1,225**
												147,810		**158,439**		**1,478**					**34**				**9,805**		**475**			**11**				
2016CPT.05.09.20351.1	Franklin	3	SR 1002 - SEVEN PATHS RD	NC 581 TO NASH CO	1	2	7.765	19-20	870	0.11		83,551		288	75,660																		
TOTAL FOR MAP NO. 3							**7.765**		**870**	**0.11**		**83,551**		**288**	**75,660**																		
2016CPT.05.09.20351.1	Franklin	4	SR 1127 - POCOMOKE RD	NC 56 TO SR 1141 - GORDON MOORE RD	1	2	4.88	20-21	547	0.08		52,509		180	37,475																		
TOTAL FOR MAP NO. 4							**4.88**		**547**	**0.08**		**52,509**		**180**	**37,475**																		
2016CPT.05.09.20351.1	Franklin	5	SR 1141 - POCOMOKE RD	SR 1127 - POCOMOKE RD TO GRANVILLE CO	1	2	0.531	20-21	60	0.01		5,714		50	5,548																		
TOTAL FOR MAP NO. 5							**0.531**		**60**	**0.01**		**5,714**		**50**	**5,548**																		
2016CPT.05.09.20351.1	Franklin	6	SR 1235 - DYKING RD	SR 1003 - SIMS BRIDGE RD TO NC 39	1	2	5.326	20-32	606	0.09		58,126		225	55,450		220																
TOTAL FOR MAP NO. 6							**5.326**		**606**	**0.09**		**58,126**		**225**	**55,450**		**220**																
2016CPT.05.09.20351.1	Franklin	7	SR 1418 - T K ALLEN RD	SR 1002 - DUKE VALENTINE WYNNE RD TO NC 561	1	2	3	19	336	0.04		32,280			26,016																		
TOTAL FOR MAP NO. 7							**3**		**336**	**0.04**		**32,280**			**26,016**																		
2016CPT.05.09.20351.1	Franklin	8	SR 1436 - LAUREL MILL CENTERVILLE RD	NC 561 TO NC 561	1	2	7.42	19-20	832	0.11		79,839		190	78,356				100	12													
TOTAL FOR MAP NO. 8							**7.42**		**832**	**0.11**		**79,839**		**190**	**78,356**				**100**	**12**													
2016CPT.05.09.20351.1	Franklin	9	SR 1438 - RAYMOND THARRINGTON RD	SR 1436 - LAUREL MILL RD TO NC 561	1	2	2.1	19	236	0.03		22,596			22,176																		
TOTAL FOR MAP NO. 9							**2.1**		**236**	**0.03**		**22,596**			**22,176**																		
2016CPT.05.09.20351.1	Franklin	10	SR 1457 - DOUGLAS WILLIAMS RD	SR 1456 - BALDY MURPHY RD TO SR 1451 - LEONARD RD	3	2	1.948	20-21	219	0.04		20,960		122	19,675																		
TOTAL FOR MAP NO. 10							**1.948**		**219**	**0.04**		**20,960**		**122**	**19,675**																		
2016CPT.05.09.20351.1	Franklin	11	SR 1602 - LEONARD FARM RD	SR 1601 - GEORGE LEONARD RD TO NC 56	1	2	1.43	18	161	0.03		15,387			14,715																		
TOTAL FOR MAP NO. 11							**1.43**		**161**	**0.03**		**15,387**			**14,715**																		
2016CPT.05.09.20351.1	Franklin	12	SR 1611 - SLEDGE RD	SR 1609 - BAPTIST CHURCH RD TO SR 1636 - SYKES RD	1	2	2.33	19-20	261	0.04		25,071		50	24,000																		
TOTAL FOR MAP NO. 12							**2.33**		**261**	**0.04**		**25,071**		**50**	**24,000**																		
2016CPT.05.09.20351.1	Franklin	13	SR 1203 - GREEN HILL RD	VANCE COUNTY TO NC 56	3	2	5.025	19-20	563	0.10		54,069		50	46,795																		
TOTAL FOR MAP NO. 13							**5.025**		**563**	**0.10**		**54,069**		**50**	**46,795**																		
TOTAL FOR PROJ NO. 2016CPT.05.09.20351.1							**41.755**		**4,691**	**0.68**		**450,102**		**1,155**	**405,866**		**220**		**100**	**12**													
												450,102		**407,021**		**220**																	
GRAND TOTAL							**56.435**		**6,360**	**1.00**	**20**	**597,582**	**330**	**3,198**	**562,262**	**478**	**1,220**	**456**	**585**	**36**	**28**	**1**	**1**	**4**	**8,585**	**1,220**	**135**	**340**	**140**	**5**	**4**	**1**	**1**	**1,225**
												597,912		**565,460**		**1,698**					**34**				**9,805**		**475**			**11**				