

PROJECT REFERENCE NO.		SHEET NO.
R-5770		3
STATE PROJECT	F.A. PROJECT NO.	DESCRIPTION
44671.3.1	NC FLAP DOT 143(1)	CONST.

SURFACING SCHEDULE

ITEM NO	DESCRIPTION
C1	PROP. APPROX. 1 1/4" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A AT AN AVERAGE RATE OF 137.5 LBS.PER.SQ.YD
C2	PROP. APPROX. 1" ASPHALT CONCRETE SURFACE COURSE, (LEVELING) TYPE SF9.5A AT AN AVERAGE RATE OF 100 LBS. PER.SQ.YD LOCATIONS AS DIRECTED BY PROJECT ENGINEER
D1	PROP. APPROX. 3" ASPHALT CONCRETE INTERMEDIATE COURSE TYPE I19.OB, AT A AVERAGE RATE OF 342 LBS PER SQ. YD.
V1	MILLED ASPHALT PAVEMENT 3" AT AREAS OF DISTRESS LOCATIONS AND WIDTH AS DIRECTED BY PROJECT ENGINEER
T	SHOULDER RECONSTRUCTION
T1	SHOULDER RECONSTRUCTION AT LOCATION'S WHERE DROP OFF EXCEEDS 1 1/2" AS DIRECTED BY PROJECT ENGINEER
U	EXISTING ASPHALT
X	ULTRA THIN BOND WEAR COURSE
<p>*NOTE*</p> <p>* ALL PAVED BULBOUTS AND PARKING AREAS WILL BE RESURFACED</p> <p>*LEVELING AT SPOT LOCATIONS AS DIRECTED BY PROJECT ENGINEER</p>	