

PROJECT NO.	SHEET NO.	TOTAL NO.
R-5770	5	

SUMMARY OF QUANTITIES(ALT.1)

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	SHOULDER RECONSTRUCTION SMI	3" MILLING SY	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, SF9.5A TONS	SURFACE COURSE, (LEVELING), SF9.5A TN	ASPHALT BINDER FOR PLANT MIX TONS
44671.3.1	Graham	1	NC 143 CHEROHALA SKYWAY	FROM TN LINE TO SR-1159 AT SANTEETLAH GAP	1	2	2WU	NO	YES	18.36	24	36.72	7,500	1,465	19,635	2,145	1,515
TOTAL FOR MAP NO. 1										18.36		36.72	7,500	1,465	19,635	2,145	1,515
TOTAL FOR PROJ NO. 44671.3.1										18.36		36.72	7,500	1,465	19,635	2,145	1,515
GRAND TOTAL										18.36		36.72	7,500	1,465	19,635	2,145	1,515

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E	4457000000-N	4710000000-E	4810000000-E		4890000000-E		4905000000-N
										WORK ZONE ADVANCE/GENERAL WARNING SIGNS SF	TEMPORARY TRAFFIC CONTROL LS	24" X 120 M WHITE THERMO LF	4" YELLOW PAINT LF	4" WHITE PAINT LF	50 MIL 4" WHITE THERMO LF	50 MIL 4" YELLOW THERMO LF	SNOW PLOWABLE MARKERS EA
44671.3.1	Graham	1	NC 143 CHEROHALA SKYWAY	FROM TN LINE TO SR-1159 AT SANTEETLAH GAP	1	2	2WU	18.36	24	2,262.0	1	100	194,000	2,880	194,000	194,000	1,860
TOTAL FOR MAP NO. 1										2,262	1	100	194,000	2,880	194,000	194,000	1,860
TOTAL FOR PROJ NO. 44671.3.1										2,262	1	100	194,000	2,880	194,000	194,000	1,860
GRAND TOTAL										2,262	1	100	194,000	2,880	194,000	194,000	1,860