


**TOTAL BILL OF MATERIAL**

BRIDGE NO.	GROOVING BRIDGE FLOORS	CLASS AA CONCRETE	REINFORCING STEEL	CLASS II. SURFACE PREPARATION	CLASS III. SURFACE PREPARATION	LATEX MODIFIED CONCRETE OVERLAY	PLACING & FINISHING OF LATEX MODIFIED CONC OVERLAY	◆ SHOTCRETE REPAIRS	◆ CONCRETE REPAIRS	EPOXY RESIN INJECTION	FOAM JOINT SEALS	CLEANING & REPAINTING OF BRIDGE #__	PAINTING CONTAINMENT FOR BRIDGE #__	POLLUTION CONTROL	ELASTOMERIC CONCRETE	BEAM REPAIR	EPOXY COATING	BRIDGE JOINT DEMOLITION	SCARIFYING BRIDGE DECK	HYDRO-DEMOLITION OF BRIDGE DECK	STEEL KEEPER ANGLE ASSEMBLY	ANCHOR BOLT REPAIR	BRIDGE JACKING
	SO. FT.	CU. YDS.	LBS.	SO. YDS.	SO. YDS.	CU. YDS.	SO. YDS.	CU. FT.	CU. FT.	LIN. FT.	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	CU. FT.	LBS.	SO. FT.	SO. FT.	SO. YDS.	SO. YDS.	EA.	EA.	EA.
183	—	—	—	—	—	—	—	180.7	70.9	129.5	—	LUMP SUM	LUMP SUM	LUMP SUM	—	1 *	714	—	—	—	—	6	9
205	—	—	—	—	—	—	—	21.3	—	24.0	—	—	—	—	—	—	—	—	—	—	—	—	—
208	—	—	—	—	—	—	—	24.7	—	142.8	—	—	—	—	—	—	—	—	—	—	—	—	—
209	4,280	3.8	320	4.7	—	29.0	515	20.5	—	5.6	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	21.0	—	—	40	515	515	—	—	—
222	4,280	3.8	320	0.2	—	28.7	515	33.6	—	15.8	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	21.0	—	—	40	515	515	—	—	—
223	5,178	6.0	366	25.0	8.8	36.6	623	40.9	—	5.0	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	24.4	—	—	46	623	623	—	—	—
224	5,178	4.8	366	12.4	2.3	35.6	623	71.7	—	3.5	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	24.4	—	—	46	623	623	—	—	—
228	17,526	—	—	1.8	—	117.5	2,114	634.3	62.3	41.4	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	40.0	50	656	160	2,114	2,114	4	—	4
230	17,526	—	—	11.1	—	118.2	2,114	493.2	—	70.0	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	40.0	45	656	160	2,114	2,114	—	—	—
231	5,610	4.6	332	—	—	37.5	676	8.0	17.8	—	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	22.0	—	—	42	676	676	—	—	—
232	5,610	4.6	332	2.1	—	37.7	676	6.4	—	7.6	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	22.0	—	—	42	676	676	—	—	—
TOTAL	65,188	27.6	2,036	57.3	11.1	440.8	7,856	1,535.3	151.0	445.2	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	214.8	96 *	2,026	576	7,856	7,856	4	6	13

\* THE FLANGE REPAIR ON BRIDGE NO. 183 WILL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR "BEAM REPAIR". A TOKEN QUANTITY IS REPORTED ON THE TOTAL BILL OF MATERIAL.  
 ◆ QUANTITY HAS BEEN INCREASED DUE TO THE POTENTIAL FOR FURTHER DETERIORATION SINCE THE FIELD INSPECTION BY STRUCTURES MANAGEMENT UNIT.

PROJECT NO. I-5756  
HAYWOOD COUNTY  
 BRIDGE NO. 183, 205, 208, 209,  
222, 223, 224, 228, 230, 231, 232

DocuSigned by:  
*John A. Yannaccone*  
 7BC36E9C  


4/5/2016

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH	
<b>TOTAL BILL OF MATERIAL</b>	
REVISIONS	
NO.	DATE
1	3
2	4
SHEET NO. S-1	
TOTAL SHEETS 116	

DRAWN BY : J. YANNACCONE DATE : 10/15  
 CHECKED BY : S. WANCE DATE : 1/16

DOCUMENT NOT CONSIDERED  
 FINAL UNLESS ALL  
 SIGNATURES COMPLETED