## STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

## PAVEMENT MARKING PLAN WILSON COUNTY

LOCATION: BRIDGE NO. 109 OVER TOWN CREEK ON SR 1002 (TOWN CREEK ROAD)

## GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) STATE FORCES WILL INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME

MARKING

MARKER

PROJECT REFERENCE NO.

B - 5313

PMP-1

TOWN CREEK ROAD

THERMOPLASTIC

NONE

- B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.
- C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.
- D) PASSING ZONES WILL BE DETERMINED IN THE FIELD AND MUST BE APPROVED BY:
- E) REMOVE ALL RESIDUE AND SURFACE LAITANCE BY ACCEPTABLE METHODS ON CONCRETE BRIDGE DECKS PRIOR TO PLACING (THERMOPLASTIC) PAVEMENT MARKING MATERIAL.

## INDEX

ROADWAY STANDARD DRAWING

PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C.,

PAVEMENT MARKINGS - BRIDGES

GUARDRAIL END DELINEATION

CONSIDERED A PART OF THESE PLANS:

1205.02

1205.12

1261.01

1261.02

1262.01

DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE

PAVEMENT MARKINGS - TWO-LANE AND MULTILANE ROADWAYS

GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING

GUARDRAIL AND BARRIER DELINEATORS - TYPES AND MOUNTING

SHEET NO.

DESCRIPTION

PMP-1

PAVEMENT MARKING PLAN TITLE AND

SCHEDULE SHEET

PMP-2

PAVEMENT MARKING DETAIL

YELLOW DOUBLE CENTER THERMOPLASTIC(4", 120 MIL)

Pavement Marking Schedule

PAVEMENT MARKINGS

TIP Project # B-5313

DESCRIPTION FINAL

WHITE EDGELINE THERMOPLASTIC(4", 90 MIL)

PLAN PREPARED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

AYMAN I. ALQUDWAH, PE SIGNING & DELINEATION REGIONAL ENGINEER BARRY NOWLIN SIGNING & DELINEATION PROJECT DESIGN TECHNICIAN

