


GRADE DATA

-0.7101% -0.3002%

PI STA. = 20+04.90
 GRADE INSET -L- (RT)
 EL. = 589.96
 L = 39.79'




SECTION ALONG RIGHT LANE CONTROL LINE

SECTION AT END BENTS AND BENT ARE TAKEN AT RIGHT ANGLES

220'-0" (TOTAL LENGTH OF BRIDGE) (FILL FACE TO FILL FACE)

107'-0" (SPAN A)

113'-0" (SPAN B)



PLAN

PILES & DRILLED PIERS NOT SHOWN FOR CLARITY

I HEREBY CERTIFY THESE PLANS ARE THE AS-BUILT PLANS

HORIZONTAL CURVE DATA

PI STA. = 15+90.27 -SRVRD-
 Δ = 109°-02'-43.5" (RT)
 D = 44°-04'-25.2"
 L = 247.42'
 T = 182.41'
 R = 130.00'

PROJECT NO. B-5123
 CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 1 OF 3 REPLACES BRIDGE #14

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
GENERAL DRAWING
 FOR BRIDGE ON US 29
 ROCKY RIVER & SERVICE RD.
 BETWEEN SR 1300 AND SR 1305

(RIGHT LANE)

REVISIONS				SHEET NO.
NO.	BY:	DATE:	NO.	DATE:
1			3	
2			4	

TOTAL SHEETS 74



DocuSigned by:
 Emily E. Murray
 CA897AEDC684E...
 3/1/2016

DocuSigned by:
 vipul a. patel
 1C157DE15D464A...
 3/1/2016

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

DRAWN BY : N.D. AIUTO DATE : 11/19/15
 CHECKED BY : K.D. LAYNE DATE : 11/20/15
 DESIGN ENGINEER OF RECORD: H.A. LOCKLEAR DATE : 12/7/15

FOUNDATION NOTES

FOR PILES, SEE GEOTECHNICAL SPECIAL PROVISIONS AND SECTION 450 OF THE STANDARD SPECIFICATIONS.

PILES AT END BENT 1 ARE DESIGNED FOR A FACTORED RESISTANCE OF 110 TONS PER PILE.

DRIVE PILES AT END BENT 1 TO A REQUIRED DRIVING RESISTANCE OF 183 TONS PER PILE.

FOR DRILLED PIERS, SEE GEOTECHNICAL SPECIAL PROVISIONS AND SECTION 411 OF THE STANDARD SPECIFICATIONS.

DRILLED PIERS AT BENT 1 ARE DESIGNED FOR A FACTORED RESISTANCE OF 725.0 TONS PER PIER. CHECK FIELD CONDITIONS FOR THE REQUIRED TIP RESISTANCE OF 60.0 TSF.

PERMANENT STEEL CASINGS MAY BE REQUIRED FOR DRILLED PIERS AT BENT 1. IF REQUIRED, DO NOT EXTEND PERMANENT CASINGS BELOW ELEVATION 542.0 (LT), 544.0 (CT), AND 546.0 (RT) WITHOUT PRIOR APPROVAL FROM THE ENGINEER. THE ENGINEER WILL DETERMINE THE NEED FOR PERMANENT CASINGS.

INSTALL DRILLED PIERS AT BENT 1 TO A TIP ELEVATION NO HIGHER THAN 529.0 (LT), 533.0 (CT), AND 537.0 (RT) WITH THE REQUIRED TIP RESISTANCE.

THE SCOUR CRITICAL ELEVATION FOR BENT 1 IS ELEVATION 534.5 (LT), 537.8 (CT), AND 541.0 (RT) SCOUR CRITICAL ELEVATIONS ARE USED TO MONITOR POSSIBLE SCOUR PROBLEMS DURING THE LIFE OF THE STRUCTURE.


SID INSPECTIONS ARE REQUIRED FOR DRILLED PIERS AT BENT 1. FOR SID INSPECTIONS, SEE SECTION 411 OF THE STANDARD SPECIFICATIONS.

CSL TUBES ARE REQUIRED AND CSL TESTING MAY BE REQUIRED FOR DRILLED PIERS. THE ENGINEER WILL DETERMINE THE NEED FOR CSL TESTING. FOR CSL TESTING, SEE SECTION 411 OF THE STANDARD SPECIFICATIONS.

SPT IS REQUIRED FOR DRILLED PIERS AT BENT 1 FOR SPT TESTING, SEE SECTION 411 OF THE STANDARD SPECIFICATIONS.

PILES AT END BENT 2 ARE DESIGNED FOR A FACTORED RESISTANCE OF 110 TONS PER PILE.

DRIVE PILES AT END BENT 2 TO A REQUIRED DRIVING RESISTANCE OF 183 TONS PER PILE.



INTEGRAL
END BENT 1

BENT 1


INTEGRAL
END BENT 2

FOUNDATION LAYOUT

DIMENSIONS LOCATING PILES ARE SHOWN TO THE CENTERLINE OF PILES

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 2 OF 3




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
GENERAL DRAWING
 FOR BRIDGE ON US 29 OVER
 ROCKY RIVER & SERVICE RD.
 BETWEEN SR 1300 AND SR 1305
 (RIGHT LANE)

DRAWN BY : N.D. AIUTO DATE : 11/18/15
 CHECKED BY : K.D. LAYNE DATE : 11/20/15
 DESIGN ENGINEER OF RECORD : H.A. LOCKLEAR DATE : 12/7/15

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS
2			4			74

BM #2: RAILROAD SPIKE IN BASE OF POWER POLE
66.4' RIGHT. STA. 18+01.44 -L-, EL. 587.42



LOCATION SKETCH

NOTES

ASSUMED LIVE LOAD = HL-93 OR ALTERNATE LOADING.
 THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS.
 THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.
 FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.
 FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.
 FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.
 FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.
 FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.
 FOR PLACING LOAD ON STRUCTURE MEMBERS, SEE SPECIAL PROVISIONS.
 THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE BARS FROM WHICH THE SAMPLES ARE TAKEN MUST THEN BE SPLICED WITH REPLACEMENT BARS OF THE SIZE AND LENGTH OF THE SAMPLE PLUS A MINIMUM LAP SPLICE OF THIRTY BAR DIAMETERS. PAYMENT FOR THE SAMPLES OF REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.
 THE ELEVATION AND CLEARANCE SHOWN ON THE PLANS AT THE POINTS OF MINIMUM VERTICAL CLEARANCE ARE FROM THE BEST INFORMATION AVAILABLE. PRIOR TO BEGINNING BRIDGE CONSTRUCTION, VERIFY THE ELEVATION ON THE EXISTING PAVEMENT AND CHECK THE CLEARANCE. REPORT ANY VARIATIONS TO THE ENGINEER. ANY PLAN REVISIONS NECESSARY TO ACHIEVE THE REQUIRED MINIMUM VERTICAL CLEARANCE WILL BE PROVIDED BY THE DEPARTMENT.
 FOR MAINTENANCE AND PROTECTION OF TRAFFIC BENEATH PROPOSED STRUCTURE, SEE SPECIAL PROVISIONS.
 PRESTRESSED CONCRETE DECK PANELS MAY BE USED IN LIEU OF METAL STAY-IN-PLACE FORMS IN ACCORDANCE WITH ARTICLE 420-3 OF THE STANDARD SPECIFICATIONS.

REMOVABLE FORMS MAY BE USED IN LIEU OF METAL STAY-IN-PLACE FORMS IN ACCORDANCE WITH ARTICLE 420-3 OF THE STANDARD SPECIFICATIONS.
 NEEDLE BEAMS WILL NOT BE ALLOWED UNLESS OTHERWISE CALLED FOR ON THE PLANS OR APPROVED BY THE ENGINEER.
 THE CLASS AA CONCRETE IN THE BRIDGE DECK SHALL CONTAIN FLY ASH OR GROUND GRANULATED BLAST FURNACE SLAG AT THE SUBSTITUTION RATE SPECIFIED IN ARTICLE 1024-1 AND IN ACCORDANCE WITH ARTICLES 1024-5 AND 1024-6 OF THE STANDARD SPECIFICATIONS. NO PAYMENT WILL BE MADE FOR THIS SUBSTITUTION AS IT IS CONSIDERED INCIDENTAL TO THE COST OF THE REINFORCED CONCRETE DECK SLAB.
 THE MATERIAL SHOWN IN THE CROSS-HATCHED AREA SHALL BE EXCAVATED FOR A DISTANCE OF 40 FT. EACH SIDE OF CENTERLINE ROADWAY AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR UNCLASSIFIED STRUCTURE EXCAVATION. SEE SECTION 412 OF THE STANDARD SPECIFICATIONS.

FOR LIMITS OF TEMPORARY SHORING FOR MAINTENANCE OF TRAFFIC, SEE TRAFFIC CONTROL PLANS. FOR PAY ITEM FOR TEMPORARY SHORING FOR MAINTENANCE OF TRAFFIC, SEE ROADWAY PLANS.

THE EXISTING STRUCTURE CONSISTING OF 4 SPANS @ 52'-6" ON REINFORCED CONCRETE DECK GIRDERS WITH A CLEAR ROADWAY WIDTH OF 28'-0" ON REINFORCED CONCRETE CAPS ON TIMBER PILES AT END BENTS AND REINFORCED CONCRETE POST AND WEB ON SPREAD FOOTINGS AT BENTS AND PEDESTRIAN WALKWAY ATTACHED TO THE STRUCTURE WITH TIMBER DECK ON I-BEAMS AND REINFORCED CONCRETE END BENT CAPS AND BENTS ON STEEL CAPS AND STEEL PILES LOCATED AT THE PROPOSED STRUCTURE SHALL BE REMOVED. THE EXISTING BRIDGE IS PRESENTLY NOT POSTED FOR LOAD LIMIT. SHOULD THE STRUCTURAL INTEGRITY OF THE BRIDGE DETERIORATE DURING CONSTRUCTION OF THE PROPOSED BRIDGE, A LOAD LIMIT MAY BE POSTED AND MAY BE REDUCED AS FOUND NECESSARY DURING THE LIFE OF THE PROJECT. FOR REMOVAL OF EXISTING STRUCTURES, SEE SPECIAL PROVISIONS.

THE SUBSTRUCTURE OF THE EXISTING BRIDGE INDICATED ON THE PLANS IS FROM THE BEST INFORMATION AVAILABLE. SINCE THIS INFORMATION IS SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT OF TRANSPORTATION FOR ANY DELAYS OR ADDITIONAL COST INCURRED BASED ON DIFFERENCES BETWEEN THE EXISTING BRIDGE SUBSTRUCTURE SHOWN ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

REMOVAL OF THE EXISTING BRIDGE SHALL BE PERFORMED IN A MANNER THAT PREVENTS DEBRIS FROM FALLING INTO THE WATER. THE CONTRACTOR SHALL SUBMIT DEMOLITION PLANS FOR REVIEW AND REMOVE THE BRIDGE IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS.

THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH "HEC 18-EVALUATING SCOUR AT BRIDGES."

FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.

FOR ASBESTOS ASSESSMENT FOR BRIDGE DEMOLITION AND RENOVATION ACTIVITIES, SEE SPECIAL PROVISIONS.

TOTAL BILL OF MATERIAL

	REMOVAL OF EXISTING STRUCTURES	4'-0" DIA. DRILLED PIERS IN SOIL	4'-0" DIA. DRILLED PIERS NOT IN SOIL	PERMANENT STEEL CASING FOR 4'-0" DIA. DRILLED PIER	SID INSPECTIONS	SPT TESTING	CSL TESTING	UNCLASSIFIED STRUCTURE EXCAVATION	REINFORCED CONCRETE DECK SLAB	GROOVING BRIDGE FLOORS	CLASS A CONCRETE	BRIDGE APPROACH SLABS	REINFORCING STEEL
	LUMP SUM	LIN. FT.	LIN. FT.	LIN. FT.	EACH	EACH	EACH	LUMP SUM	SQ. FT.	SQ. FT.	CU. YDS.	LUMP SUM	LBS.
SUPERSTRUCTURE									12,412	12,241		LUMP SUM	
END BENT 1											46.2		6,152
BENT 1		60.0	33.0	63.0	1	1	1				55.3		17,888
END BENT 2											46.0		6,141
TOTAL	LUMP SUM	60.0	33.0	63.0	1	1	1	LUMP SUM	12,412	12,241	147.5	LUMP SUM	30,181

	SPIRAL COLUMN REINFORCING STEEL	MODIFIED 63" PRESTRESSED CONCRETE GIRDERS	HP 12X53 STEEL PILES	TWO BAR METAL RAIL	CONCRETE BARRIER RAIL	1'-2" X 2'-6" CONCRETE PARAPET	4" SLOPE PROTECTION	RIP RAP CLASS II (2'-0" THICK)	GEOTEXTILE FOR DRAINAGE	ELASTOMERIC BEARINGS	ASBESTOS ASSESSMENT
	LBS.	NO. LIN. FT.	NO. LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	SQ. YDS.	TONS	SQ. YDS.	LUMP SUM	LUMP SUM
SUPERSTRUCTURE		14 1,516.08		210.05	486.44	218.23				LUMP SUM	LUMP SUM
END BENT 1			11 525				410				
BENT 1	3,442										
END BENT 2			11 360					525	585		
TOTAL	3,442	14 1,516.08	22 885	210.05	486.44	218.23	410	525	585	LUMP SUM	LUMP SUM

HYDRAULIC DATA


DESIGN DISCHARGE	= 10,070 C.F.S.
FREQUENCY OF DESIGN FLOOD	= 50 YRS.
DESIGN HIGH WATER ELEVATION	= 576.10
DRAINAGE AREA	= 87.5 SQ.MI.
BASE DISCHARGE (Q100)	= 12,060 C.F.S.
BASE HIGH WATER ELEVATION	= 577.21

OVERTOPPING FLOOD DATA

OVERTOPPING DISCHARGE	= 33,000 C.F.S.
FREQUENCY OF OVERTOPPING FLOOD	= 500+ YRS.
OVERTOPPING FLOOD ELEVATION	= 588.90

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 3 OF 3



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
GENERAL DRAWING
 FOR BRIDGE ON US 29 OVER
 ROCKY RIVER & SERVICE RD.
 BETWEEN SR 1300 AND SR 1305
 (RIGHT LANE)

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS
2			4			74

DRAWN BY : N.D. AIUTO DATE : 11/18/15
 CHECKED BY : K.D. LAYNE DATE : 11/20/15
 DESIGN ENGINEER OF RECORD: H.A. LOCKLEAR DATE : 12/7/15

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

STR. #2

LOAD FACTORS:

DESIGN LOAD RATING FACTORS	LIMIT STATE	γ_{DC}	γ_{DW}
	STRENGTH I	1.25	1.50
	SERVICE III	1.00	1.00

LOAD AND RESISTANCE FACTOR RATING (LRFD) SUMMARY FOR PRESTRESSED CONCRETE GIRDERS

LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING #	MINIMUM RATING FACTORS (RF)	TONS = W X RF	STRENGTH I LIMIT STATE										SERVICE III LIMIT STATE					COMMENT NUMBER			
						LIVELOAD FACTORS	MOMENT					SHEAR					LIVELOAD FACTORS	MOMENT						
							DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)		DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN		GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	
DESIGN LOAD RATING	HL-93(Inv)	N/A	1	1.01	--	1.75	0.781	1.49	A	ER	51.938	0.822	1.39	A	ER	72.713	0.80	0.781	1.01	B	ER	54.938		
	HL-93(0pr)	N/A	--	1.81	--	1.35	0.781	1.93	A	ER	51.938	0.822	1.81	A	ER	72.713	N/A	--	--	--	--	--		
	HS-20(Inv)	36.000	2	1.44	51.931	1.75	0.781	2.10	A	ER	51.938	0.822	1.78	A	ER	72.713	0.80	0.781	1.44	B	ER	54.938		
	HS-20(0pr)	36.000	--	2.3	82.949	1.35	0.781	2.72	A	ER	51.938	0.822	2.30	A	ER	72.713	N/A	--	--	--	--	--		
LEGAL LOAD RATING	SV	SNSH	13.500	--	3.47	46.786	1.40	0.781	6.26	A	ER	51.938	0.822	5.36	A	ER	72.713	0.80	0.781	3.47	B	ER	54.938	
		SNGARBS2	20.000	--	2.49	49.815	1.40	0.781	4.52	A	ER	51.938	0.822	3.79	A	ER	72.713	0.80	0.781	2.49	B	ER	54.938	
		SNAGRIS2	22.000	--	2.32	51.088	1.40	0.781	4.22	A	ER	51.938	0.822	3.51	A	ER	72.713	0.80	0.781	2.32	B	ER	54.938	
		SNCOTTS3	27.250	--	1.72	46.921	1.40	0.781	3.11	A	ER	51.938	0.822	2.67	A	ER	72.713	0.80	0.781	1.72	B	ER	54.938	
		SNAGGRS4	34.925	--	1.4	49.016	1.40	0.781	2.54	A	ER	51.938	0.822	2.20	A	ER	72.713	0.80	0.781	1.40	B	ER	54.938	
		SNS5A	35.550	--	1.38	48.874	1.40	0.781	2.49	A	ER	51.938	0.822	2.22	A	ER	72.713	0.80	0.781	1.37	B	ER	54.938	
		SNS6A	39.950	--	1.25	49.819	1.40	0.781	2.26	A	ER	51.938	0.822	2.02	A	ER	72.713	0.80	0.781	1.25	B	ER	54.938	
	SNS7B	42.000	--	1.19	49.855	1.40	0.781	2.15	A	ER	51.938	0.822	1.98	A	ER	72.713	0.80	0.781	1.19	B	ER	54.938		
	TTST	TNAGRIT3	33.000	--	1.52	50.044	1.40	0.781	2.75	A	ER	51.938	0.822	2.41	A	ER	72.713	0.80	0.781	1.52	B	ER	54.938	
		TNT4A	33.075	--	1.52	50.251	1.40	0.781	2.76	A	ER	51.938	0.822	2.36	A	ER	72.713	0.80	0.781	1.52	B	ER	54.938	
		TNT6A	41.600	--	1.23	51.124	1.40	0.781	2.23	A	ER	51.938	0.822	2.09	A	ER	31.163	0.80	0.781	1.23	B	ER	54.938	
		TNT7A	42.000	--	1.23	51.580	1.40	0.781	2.23	A	ER	51.938	0.822	2.05	A	ER	72.713	0.80	0.781	1.23	B	ER	54.938	
		TNT7B	42.000	--	1.25	52.649	1.40	0.781	2.28	A	ER	51.938	0.822	1.94	A	ER	72.713	0.80	0.781	1.25	B	ER	54.938	
		TNAGRIT4	43.000	--	1.21	51.817	1.40	0.781	2.19	A	ER	51.938	0.822	1.88	A	ER	72.713	0.80	0.781	1.21	B	ER	54.938	
TNAGT5A		45.000	--	1.14	51.398	1.40	0.781	2.08	A	ER	51.938	0.822	1.86	A	ER	72.713	0.80	0.781	1.14	B	ER	54.938		
TNAGT5B	45.000	3	1.13	51.017	1.40	0.781	2.06	A	ER	51.938	0.822	1.79	A	ER	72.713	0.80	0.781	1.13	B	ER	54.938			

NOTES:

MINIMUM RATING FACTORS ARE BASED ON THE STRENGTH I AND SERVICE III LIMIT STATES.
ALLOWABLE STRESSES FOR SERVICE III LIMIT STATE ARE AS REQUIRED FOR DESIGN.

CONTROLLING LOAD RATING

1 DESIGN LOAD RATING (HL-93)


2 DESIGN LOAD RATING (HS-20)

3 LEGAL LOAD RATING **

** SEE CHART FOR VEHICLE TYPE


GIRDER LOCATION

I - INTERIOR GIRDER
EL - EXTERIOR LEFT GIRDER
ER - EXTERIOR RIGHT GIRDER



LRFR SUMMARY

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 LRFR SUMMARY FOR
 PRESTRESSED
 CONCRETE GIRDERS
 (NON-INTERSTATE TRAFFIC)

ASSEMBLED BY : H. A. LOCKLEAR DATE : 2/22/16
 CHECKED BY : T. H. CARROLL DATE : 2/29/16
 DRAWN BY : MAA 1/08
 CHECKED BY : GM/DI 2/08
 REV. 11/2/08RR MAA/GM
 REV. 10/1/11 MAA/GM
 DESIGN ENGINEER OF RECORD:
 H. A. LOCKLEAR DATE : 2/29/16

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-41
1			3			TOTAL SHEETS 74
2			4			

NOTES


PROVIDE 1/4" HIGH BEAM BOLSTERS UPPER AT 4'-0" CTS. ATOP THE METAL STAY-IN-PLACE FORMS TO SUPPORT THE BOTTOM MAT OF 'A' BARS. WHEN USING REMOVABLE FORMS, PROVIDE CONTINUOUS HIGH CHAIRS FOR METAL DECK (C.H.C.M.) @ 4'-0" CTS. WITH A HEIGHT TO SUPPORT THE BOTTOM MAT OF 'A' BARS A CLEAR DISTANCE OF 2 1/2" ABOVE THE TOP OF THE REMOVABLE FORM.

LONGITUDINAL STEEL MAY BE SHIFTED SLIGHTLY, AS NECESSARY, TO AVOID INTERFERENCE WITH STIRRUPS IN PRESTRESSED CONCRETE GIRDERS.

PREVIOUSLY CAST CONCRETE IN A CONTINUOUS UNIT SHALL HAVE ATTAINED A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI BEFORE ADDITIONAL CONCRETE IS CAST IN THE UNIT.


FOR WING ELEVATIONS AND DETAILS, SEE "PLAN OF SPAN DETAILS" SHEETS.

* FOR INTERMEDIATE STEEL DIAPHRAGM DETAILS, SEE "INTERMEDIATE STEEL DIAPHRAGMS FOR 63" MODIFIED BULB TEE PRESTRESSED CONCRETE GIRDERS" SHEET.




TYPICAL SECTION
(SHOWING BENT DIAPHRAGMS)


TYPICAL SECTION
(SHOWING INTERMEDIATE DIAPHRAGMS)




DETAIL "A"



SECTION THROUGH BENT DIAPHRAGM




BENT DIAPHRAGM BLOCK-OUT DETAIL



PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 1 OF 2



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

**SUPERSTRUCTURE
 TYPICAL SECTION**


(RIGHT LANE)

REVISIONS						SHEET NO. S-42
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 74
2			4			


DRAWN BY: N.D. AIUTO DATE: 10/30/15
 CHECKED BY: K.D. LAYNE DATE: 11/5/15
 DESIGN ENGINEER OF RECORD: H.A. LOCKLEAR DATE: 12/7/15

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

STR. #2




TYPICAL SECTION AT INTEGRAL END BENT



SECTION THROUGH INTEGRAL END BENT

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-
 SHEET 2 OF 2



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH



SUPERSTRUCTURE
 TYPICAL SECTION

(RIGHT LANE)

DRAWN BY: N.D'AIUTO DATE: 10/30/15
 CHECKED BY: K.D.LAYNE DATE: 11/5/15
 DESIGN ENGINEER OF RECORD: H.A.LOCKLEAR DATE: 12/7/15

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS						SHEET NO. S-43
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 74
2			4			




PLAN OF SPAN A

INTERMEDIATE STEEL DIAPHRAGMS NOT SHOWN FOR CLARITY. FOR DETAILS, SEE "INTERMEDIATE STEEL DIAPHRAGMS FOR MODIFIED BULB TEE PRESTRESSED CONCRETE GIRDERS" SHEET
 SEE "PLAN OF SPAN DETAILS" FOR ADDITIONAL REINFORCING STEEL IN WINGS
 SEE SHEET 2 OF 4 FOR TRANSVERSE CONSTRUCTION JOINT DETAIL

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 1 OF 4






STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUPERSTRUCTURE
 PLAN OF SPAN A
 (RIGHT LANE)

DRAWN BY: N.D. AIUTO DATE: 11/9/15
 CHECKED BY: K.D. LAYNE DATE: 11/13/15
 DESIGN ENGINEER OF RECORD: I.H. CARROLL DATE: 12/7/15

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS						SHEET NO. S-44 TOTAL SHEETS 74
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			STR. #2
2			4			



PLAN OF SPAN B


INTERMEDIATE STEEL DIAPHRAGMS NOT SHOWN FOR CLARITY. FOR DETAILS, SEE "INTERMEDIATE STEEL DIAPHRAGMS FOR MODIFIED BULB TEE PRESTRESSED CONCRETE GIRDERS" SHEET)
SEE "PLAN OF SPAN DETAILS" SHEETS FOR ADDITIONAL REINFORCING STEEL IN WINGS

TRANSVERSE CONSTRUCTION JOINT

NOTE: REINFORCING STEEL IN SLAB NOT SHOWN. LONGITUDINAL REINFORCING STEEL SHALL BE CONTINUOUS THROUGH JOINT.

PROJECT NO. B-5123
CABARRUS COUNTY
STATION: 21+44.10 -L-

SHEET 2 OF 4




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
SUPERSTRUCTURE
PLAN OF SPAN B
(RIGHT LANE)

DRAWN BY : N.D'AIUTO DATE : 11/9/15
CHECKED BY : K.D.LAYNE DATE : 11/13/15
DESIGN ENGINEER OF RECORD: I.H.CARROLL DATE : 12/7/15


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS						SHEET NO. S-45
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 74
2			4			


STR. #2




PLAN OF LEFT WING
@ END BENT 1




PLAN OF RIGHT WING
@ END BENT 1




ELEVATION OF LEFT WING
@ END BENT 1



SECTION A-A




SECTION B-B



ELEVATION OF RIGHT WING
@ END BENT 1

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 3 OF 4








STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUBSTRUCTURE
 PLAN OF SPAN
 DETAILS
 (RIGHT LANE)

DRAWN BY: N.D.AIUTO DATE: 11/9/15
 CHECKED BY: K.D.LAYNE DATE: 11/13/15
 DESIGN ENGINEER OF RECORD: T.H.CARROLL DATE: 12/7/15

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS						SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:	S-46	
1			3			TOTAL SHEETS	74
2			4				



ELEVATION OF LEFT WING @ END BENT 2


SECTION A-A

SECTION B-B

ELEVATION OF RIGHT WING @ END BENT 2

PROJECT NO. B-5123
 CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 4 OF 4




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUBSTRUCTURE
 PLAN OF SPAN DETAILS
 (RIGHT LANE)

DRAWN BY: N.D'AIUTO DATE: 11/9/15
 CHECKED BY: K.D.LAYNE DATE: 11/13/15
 DESIGN ENGINEER OF RECORD: T.H.CARROLL DATE: 12/7/15


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-47
1			3			TOTAL SHEETS
2			4			74



GIRDER LAYOUT

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH


**SUPERSTRUCTURE
 GIRDER LAYOUT**

(RIGHT LANE)



REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-48
1			3			TOTAL SHEETS
2			4			74

DRAWN BY : T. H. CARROLL DATE : 10/29/15
 CHECKED BY : H.A. LOCKLEAR DATE : 11/1/15
 DESIGN ENGINEER OF RECORD: H. A. LOCKLEAR DATE : 2/29/16

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED



* FOR S7 BARS, SEE
DETAIL "C" OF
PRESTRESSED
CONCRETE GIRDER
CONTINUOUS FOR LIVE
LOAD DETAILS SHEET




AT END OF GIRDER AT C OF GIRDER
0.6" Ø LOW RELAXATION STRAND LAYOUT

DEBONDING LEGEND
● FULLY BONDED STRANDS
◊ STRANDS DEBONDED FOR 12'-0" FROM END OF GIRDER

0.6" Ø L. R. GRADE 270 STRANDS		
AREA (SQUARE INCHES)	ULTIMATE STRENGTH (LBS. PER STRAND)	APPLIED PRESTRESS (LBS. PER STRAND)
0.217	58,600	43,950

REINFORCING STEEL FOR ONE GDR					
BAR	NUMBER	SIZE	TYPE	LENGTH	WEIGHT
S1	154	#4	1	6'-1"	626
S2	24	#6	1	6'-1"	219
S3	12	#4	2	8'-5"	67
S4	72	#4	3	3'-0"	144
S6	176	#5	4	4'-4"	795
* S7	30	#5	STR	3'-8"	115
S8	2	#5	2	9'-0"	19
S9	30	#5	STR	3'-3"	102
S10	2	#3	STR	1'-10"	1
S11	8	#5	5	10'-0"	83
S12	16	#4	STR	8'-0"	86
S13	2	#5	4	3'-8"	8


* NOTE: S7 BARS SHALL BE BENT BEFORE SHIPMENT. HEAT BENDING SHALL NOT BE ALLOWED.






ALL BAR DIMENSIONS ARE OUT-TO-OUT.

QUANTITIES FOR ONE GIRDER			
	REINFORCING STEEL	8,500 PSI CONCRETE	0.6" Ø L.R. STRANDS
	LB.	C.Y.	No.
	2,265	20.9	38

GIRDERS REQUIRED		
NUMBER	LENGTH	TOTAL LENGTH
7	105'-3 1/2"	737'-0 1/2"



SHOWING INTERMEDIATE STEEL DIAPHRAGM
REINFORCING STEEL FOR ONE GIRDER



PROJECT NO. B-5123
CABARRUS COUNTY
STATION: 21+44.10 -L-

SHEET 1 OF 3




REVISIONS				SHEET NO.
NO.	BY:	DATE:	NO.	DATE:
1			3	
2			4	

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD
63" PRESTRESSED CONCRETE
MODIFIED BULB TEE
CONTINUOUS FOR LIVE LOAD
SPAN A
(RIGHT LANE)

ASSEMBLED BY : T. H. CARROLL DATE : 10/29/15
CHECKED BY : H.A. LOCKLEAR DATE : 11/1/15
DRAWN BY : EEM 2/6/97 REV. 10/1/11 MAA/GM DESIGN ENGINEER OF RECORD:
CHECKED BY : VAP 2/6/97 REV. 6/13 MAA/GM H.A. LOCKLEAR DATE : 2229/16
REV. 1/15 MAA/TMG

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

TOTAL SHEETS 74




* FOR S7 BARS, SEE
DETAIL "C" OF
PRESTRESSED
CONCRETE GIRDER
CONTINUOUS FOR LIVE
LOAD DETAILS SHEET

0.6" Ø L. R. GRADE 270 STRANDS		
AREA (SQUARE INCHES)	ULTIMATE STRENGTH (LBS. PER STRAND)	APPLIED PRESTRESS (LBS. PER STRAND)
0.217	58,600	43,950

REINFORCING STEEL FOR ONE GDR					
BAR	NUMBER	SIZE	TYPE	LENGTH	WEIGHT
S1	166	#4	1	6'-1"	675
S2	24	#6	1	6'-1"	219
S3	12	#4	2	8'-5"	67
S4	72	#4	3	3'-0"	144
S6	188	#5	4	4'-4"	850
* S7	30	#5	STR	3'-8"	115
S8	2	#5	2	9'-0"	19
S9	32	#5	STR	3'-3"	108
S10	2	#3	STR	1'-10"	1
S11	8	#5	5	10'-0"	83
S12	16	#4	STR	8'-0"	86
S13	2	#5	4	3'-8"	8

* NOTE: S7 BARS SHALL BE BENT BEFORE SHIPMENT. HEAT BENDING SHALL NOT BE ALLOWED.






- DEBONDING LEGEND**
- FULLY BONDED STRANDS
 - ▲ STRANDS DEBONDED FOR 4'-0" FROM END OF GIRDER
 - ◆ STRANDS DEBONDED FOR 12'-0" FROM END OF GIRDER

ALL BAR DIMENSIONS ARE OUT-TO-OUT.

QUANTITIES FOR ONE GIRDER		
REINFORCING STEEL	9,500 PSI CONCRETE	0.6" Ø L.R. STRANDS
LB.	C.Y.	No.
2,375	22.0	44


GIRDERS REQUIRED		
NUMBER	LENGTH	TOTAL LENGTH
7	111'-3 1/2"	779'-0 1/2"



PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 2 OF 3

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 63" PRESTRESSED CONCRETE
 MODIFIED BULB TEE
 CONTINUOUS FOR LIVE LOAD
 SPAN B
 (RIGHT LANE)




ASSEMBLED BY: T. H. CARROLL DATE: 10/29/15
 CHECKED BY: H. A. LOCKLEAR DATE: 11/1/15
 DRAWN BY: EEM 2/6/97 REV. 10/1/11 MAA/GM DESIGN ENGINEER OF RECORD:
 CHECKED BY: VAP 2/6/97 REV. 6/13 MAA/GM H. A. LOCKLEAR DATE: 2228/16
 REV. 1/15 MAA/TMG


DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS				SHEET NO.
NO.	BY:	DATE:	NO.	DATE:
1			3	
2			4	

TOTAL SHEETS: 74




DETAIL "C"



EMBEDDED PLATE "B-1" DETAILS FOR 63" MODIFIED BULB TEES

(2 REQ'D PER GIRDER)



SECTION "F"

(SEE NOTES)

NOTES

ALL PRESTRESSING STRANDS SHALL BE 7-WIRE LOW-RELAXATION GRADE 270 STRANDS AND SHALL CONFORM TO AASHTO M203 EXCEPT FOR SAMPLING REQUIREMENTS WHICH SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

ALL REINFORCING STEEL SHALL BE GRADE 60.

EMBEDDED PLATE "B-1" SHALL BE GALVANIZED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

ANCHOR STUDS SHALL CONFORM TO AASHTO M169 GRADES 1010 THROUGH 1020 OR APPROVED EQUAL, AND SHALL MEET THE TYPE "B" REQUIREMENTS OF SUBSECTION 7.3 OF THE ANSI/AASHTO/AWS D1.5 BRIDGE WELDING CODE.

AT ENDS OF GIRDERS TO BE EMBEDDED IN CONCRETE DIAPHRAGMS OR END WALLS, PRESTRESSING STRANDS MAY EXTEND A MAXIMUM OF 2" BEYOND THE GIRDER ENDS. OTHERWISE, PRESTRESSING STRANDS SHALL BE CUT FLUSH WITH THE GIRDER ENDS.

THE TRANSFER OF LOAD FROM THE ANCHORAGES TO THE GIRDER SHALL BE DONE WHEN CONCRETE HAS REACHED A COMPRESSIVE STRENGTH OF NOT LESS THAN 6,700 PSI FOR SPAN A AND 7500 PSI FOR SPAN B.

DEPENDING ON THE TYPE OF SYSTEM USED TO SUPPORT THE DECK SLAB FORMS, PRESET ANCHORS MAY BE NECESSARY IN THE PRESTRESSED CONCRETE GIRDER.

THE TOP SURFACE OF THE GIRDER, EXCLUDING THE OUTSIDE 4", SHALL BE RAKED TO A DEPTH OF 1/4".

A 2" x 2" CHAMFER IS ALLOWED AT THE INTERSECTION OF THE WEB AND THE BOTTOM FLANGE OF THE 63" MODIFIED BULB TEES.

THE CONTRACTOR HAS THE OPTION TO PROVIDE, AT NO ADDITIONAL COST TO THE DEPARTMENT, 2 ADDITIONAL STRANDS AT THE TOP OF THE GIRDER TO FACILITATE TYING OF THE REINFORCING STEEL. THESE STRANDS SHALL BE PULLED TO A LOAD OF 4,500 lbs.

DEAD LOAD DEFLECTION TABLE FOR GIRDERS

0.6" Ø LOW RELAXATION	SPAN A																					
	GIRDERS 1 THROUGH 7																					
	TWENTIETH POINTS	0.0	0.05	0.10	0.15	0.20	0.25	0.30	0.35	0.40	0.45	0.50	0.55	0.60	0.65	0.70	0.75	0.80	0.85	0.90	0.95	0.0
CAMBER (GIRDER ALONE IN PLACE)	↑	0.000	0.038	0.074	0.109	0.140	0.168	0.192	0.211	0.225	0.233	0.236	0.233	0.225	0.211	0.192	0.168	0.140	0.109	0.074	0.038	0.000
* DEFLECTION DUE TO SUPERIMPOSED D.L.	↓	0.000	0.018	0.035	0.051	0.066	0.079	0.091	0.099	0.106	0.109	0.112	0.109	0.106	0.099	0.091	0.079	0.066	0.051	0.035	0.018	0.000
FINAL CAMBER	↑	0	1/4"	1/2"	11/16"	7/8"	11/16"	13/16"	13/8"	17/16"	11/2"	11/2"	11/2"	17/16"	13/8"	13/16"	11/16"	7/8"	11/16"	1/2"	1/4"	0


DEAD LOAD DEFLECTION TABLE FOR GIRDERS

0.6" Ø LOW RELAXATION	SPAN B																					
	GIRDERS 1 THROUGH 7																					
	TWENTIETH POINTS	0.0	0.05	0.10	0.15	0.20	0.25	0.30	0.35	0.40	0.45	0.50	0.55	0.60	0.65	0.70	0.75	0.80	0.85	0.90	0.95	0.0
CAMBER (GIRDER ALONE IN PLACE)	↑	0.000	0.043	0.086	0.125	0.162	0.194	0.222	0.244	0.260	0.269	0.273	0.269	0.260	0.244	0.222	0.194	0.162	0.125	0.086	0.043	0.000
* DEFLECTION DUE TO SUPERIMPOSED D.L.	↓	0.000	0.021	0.042	0.060	0.079	0.093	0.108	0.117	0.126	0.129	0.132	0.129	0.126	0.117	0.108	0.093	0.079	0.060	0.042	0.021	0.000
FINAL CAMBER	↑	0	1/4"	1/2"	13/16"	1"	13/16"	13/8"	11/2"	15/8"	11/16"	11/16"	11/16"	15/8"	11/2"	13/8"	13/16"	1"	13/16"	1/2"	1/4"	0

* INCLUDES FUTURE WEARING SURFACE EXCEPT GIRDER 1.
ALL VALUES ARE SHOWN IN FEET (DECIMAL FORM), EXCEPT "FINAL CAMBER", WHICH IS GIVEN IN INCHES (FRACTION FORM).

PROJECT NO. B-5123
CABARRUS COUNTY
STATION: 21+44.10 -L-

SHEET 3 OF 3



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD
PRESTRESSED CONCRETE GIRDER
CONTINUOUS FOR LIVE LOAD
DETAILS
(RIGHT LANE)

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-51
1			3			TOTAL SHEETS 74
2			4			

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

ASSEMBLED BY : T. H. CARROLL DATE : 10/29/15
CHECKED BY : H.A. LOCKLEAR DATE : 11/1/15

DRAWN BY : ELR 11/91 REV. 10/1/11 MAA/GM DESIGN ENGINEER OF RECORD:
CHECKED BY : GRP 11/91 REV. 1/15 MAA/TMG H.A. LOCKLEAR DATE : 12-29-15
REV. 2/15 MAA/TMG

STRUCTURAL STEEL NOTES

ALL INTERMEDIATE DIAPHRAGM STEEL AND CONNECTOR PLATES SHALL BE AASHTO M270 GRADE 50 OR APPROVED EQUAL.

TENSION ON THE ASTM A325 BOLTS THROUGH THE ANGLE MEMBER SHALL BE CALIBRATED USING DIRECT TENSION INDICATOR WASHERS IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

TENSION ON THE ASTM A449 BOLTS THROUGH THE GIRDER WEB SHALL BE SNUG TIGHTENED FOLLOWED BY AN ADDITIONAL 1/4 TURN.

THE PLATES, BENT PLATES, AND ANGLES SHALL BE GALVANIZED OR METALLIZED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS. FOR THERMAL SPRAYED COATINGS (METALLIZATION), SEE SPECIAL PROVISIONS.

FOR METALLIZATION, APPLY AN 8 MIL THICK 99.99 PERCENT ZINC (W-Zn-1) THERMAL SPRAYED COATING WITH A 0.5 MIL THICK SEAL COAT TO ALL STEEL DIAPHRAGM SURFACES IN ACCORDANCE WITH THE THERMAL SPRAYED COATINGS SPECIAL PROVISION AND SECTION 442 OF THE STANDARD SPECIFICATIONS.

GALVANIZE THE HIGH STRENGTH BOLTS, NUTS, WASHERS AND DIRECT TENSION INDICATORS IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

USE AN ASTM F436 HARDENED WASHER WITH STANDARD AND SLOTTED HOLES UNDER EACH BOLT HEAD AND NUT.


FOR BOLTS THROUGH THE GIRDER WEB, PROVIDE SUFFICIENT LENGTH OF THREADS ON ALL BOLTS TO ACCOMMODATE WASHERS AND THE THICKNESS OF CONNECTING MEMBER PLUS AT LEAST 1/4" PROJECTION BEYOND THE NUT.

INTERMEDIATE DIAPHRAGM ASSEMBLY SHALL COMPLY WITH SECTION 1072 OF THE STANDARD SPECIFICATIONS.

SUBMIT TWO SETS OF WORKING DRAWINGS FOR THE INTERMEDIATE DIAPHRAGM ASSEMBLY FOR REVIEW, COMMENTS AND ACCEPTANCE. AFTER REVIEW, COMMENTS, AND ACCEPTANCE, SUBMIT SEVEN SETS FOR DISTRIBUTION.


IN THE EXTERIOR BAYS, PLACE TEMPORARY STRUTS BETWEEN PRESTRESSED GIRDERS ADJACENT TO THE STEEL DIAPHRAGMS. STRUTS SHALL REMAIN IN PLACE 3 DAYS AFTER CONCRETE IS PLACED.

THE COST OF THE STEEL DIAPHRAGMS AND ASSEMBLIES SHALL BE INCLUDED IN THE UNIT PRICE BID FOR PRESTRESSED CONCRETE GIRDERS.




PART SECTION AT INTERMEDIATE DIAPHRAGM

SEE TYPICAL SECTION FOR VARYING GIRDER SPACING.




ANGLE END

(L 3 X 3 X 5/16)




SECTION Y-Y

CONNECTOR PLATE DETAIL




CONNECTION DETAILS



BOLT WITH DTI ASSEMBLY DETAIL

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 INTERMEDIATE STEEL
 DIAPHRAGMS FOR 63" MODIFIED
 BULB TEE PRESTRESSED
 CONCRETE GIRDERS
 (RIGHT LANE)

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-52
1			3			TOTAL SHEETS
2			4			74

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED










ASSEMBLED BY : T. H. CARROLL DATE : 10/29/15
 CHECKED BY : H.A. LOCKLEAR DATE : 11/1/15

DRAWN BY : RWW 11/09
 CHECKED BY : GM 11/09

ADDED 11/23/09R
 REV. 10/1/11 MAA/GM


DESIGN ENGINEER OF RECORD:
 H.A. LOCKLEAR DATE : 11/29/16

01-MAR-2016 10:56
 R:\Structures\Plans\Str02\B5123.SD_C*.02.dgn
 ndaluto



MAXIMUM ALLOWABLE SERVICE LOADS	
D.L.+L.L. (NO IMPACT)	
TYPE IV	225 k
TYPE V	365 k

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 ELASTOMERIC BEARING
 DETAILS
 PRESTRESSED CONCRETE GIRDER
 SUPERSTRUCTURE
 (RIGHT LANE)


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-53
1			3			TOTAL SHEETS 74
2			4			


ASSEMBLED BY : T. H. CARROLL	DATE : 10/29/15		
CHECKED BY : H.A. LOCKLEAR	DATE : 11/1/2015		
DRAWN BY : EEM 2/97	REV. 10/1/11	MAA/GM	DESIGN ENGINEER OF RECORD:
CHECKED BY : VAP 2/97	REV. 6/13	AAC/MAA	T. H. CARROLL
	REV. 1/15	MAA/TMG	DATE : 12/7/15



PLAN OF CONCRETE BARRIER RAIL



PLAN



SECTION THROUGH RAIL


1/2" EXP. JT. MAT'L HELD IN PLACE WITH GALVANIZED NAILS.
 (NOTE: OMIT EXP. JT. MAT'L. WHEN SLIP FORM IS USED.)

NOTES


THE BARRIER RAIL IN EACH CONTINUOUS UNIT SHALL NOT BE CAST UNTIL ALL SLAB CONCRETE IN THAT UNIT HAS BEEN CAST AND HAS REACHED A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI.

ALL REINFORCING STEEL IN BARRIER RAILS SHALL BE EPOXY COATED.


GROOVED CONTRACTION JOINTS, 1/2" IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE BARRIER RAIL AND IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. THE CONTRACTION JOINT SHALL BE LOCATED AT EACH THIRD POINT BETWEEN BARRIER RAIL EXPANSION JOINTS. ONLY ONE CONTRACTION JOINT IS REQUIRED AT MIDPOINT OF BARRIER RAIL SEGMENTS LESS THAN 20 FEET IN LENGTH AND NO CONTRACTION JOINTS ARE REQUIRED FOR THOSE SEGMENTS LESS THAN 10 FEET IN LENGTH.



BILL OF MATERIAL					
FOR CONCRETE BARRIER RAIL ONLY					
BAR NO.	SIZE	TYPE	LENGTH	WEIGHT	
* B1	22	#5	STR	15'-8"	359
* B2	66	#5	STR	27'-7"	1899
* B3	22	#5	STR	12'-8"	291
* S1	218	#5	1	4'-8"	1061
* S2	214	#5	2	7'-0"	1562
* S3	4	#5	2	5'-4"	22
* EPOXY COATED REINFORCING STEEL				LBS.	5,194
CLASS AA CONCRETE				C.Y.	29.7
CONCRETE BARRIER RAIL				LN. FT.	218.22




SIDE VIEW
 END VIEW
 END OF RAIL DETAILS



BARRIER RAIL DETAILS

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-
 SHEET 1 OF 2



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 3'-6" CONCRETE BARRIER RAIL
 (RIGHT LANE)

ASSEMBLED BY : K. D. LAYNE	DATE : 11/3/15
CHECKED BY : N. D'ALUIO	DATE : 11/9/15
DRAWN BY : ARB 5/87	REV. 10/1/11 MAA/GM
CHECKED BY : SJD 9/87	REV. 7/12 MAA/GM
	REV. 6/13 MAA/GM

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 74
2			4			

NOTES

THE GUARDRAIL ANCHOR ASSEMBLY SHALL CONSIST OF A 1/4" HOLD-DOWN PLATE AND 4 - 1/8" Ø BOLTS WITH NUTS AND WASHERS, RUBRAIL, AND ADHESIVELY ANCHORED BOLTS.

THE HOLD-DOWN PLATE SHALL CONFORM TO AASHTO M270 GRADE 36. AFTER FABRICATION, THE HOLD-DOWN PLATE SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH AASHTO M111.

BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A307 AND NUTS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M291. BOLTS, NUTS AND WASHERS SHALL BE GALVANIZED. (AT THE CONTRACTOR'S OPTION, STAINLESS STEEL BOLTS, NUTS AND WASHERS MAY BE USED AS AN ALTERNATE FOR THE 1/8" Ø GALVANIZED BOLTS, NUTS AND WASHERS. THEY SHALL CONFORM TO OR EXCEED THE MECHANICAL REQUIREMENTS OF ASTM A307. THE USE OF THIS ALTERNATE SHALL BE APPROVED BY THE ENGINEER.)




THE GUARDRAIL ANCHOR ASSEMBLY IS REQUIRED AT ALL POINTS WHERE APPROACH GUARDRAIL IS TO BE ATTACHED TO THE END OF BARRIER RAIL. FOR POINTS OF ATTACHMENT, SEE SKETCH.

AFTER INSTALLATION, THE EXPOSED THREAD OF THE BOLT SHALL BE BURRED WITH A SHARP POINTED TOOL.


THE COST OF THE GUARDRAIL ANCHOR ASSEMBLY SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR CONCRETE BARRIER RAIL.

THE 1 1/4" Ø HOLES SHALL BE FORMED OR DRILLED WITH A CORE BIT. IMPACT TOOLS WILL NOT BE PERMITTED. ANY CONCRETE DAMAGED BY THIS WORK SHALL BE REPAIRED TO THE SATISFACTION OF THE ENGINEER.


THE C6 X 8.2 RUBRAIL IS TO BE ADHESIVELY ANCHORED TO THE RAIL USING THREE 3/4" Ø X 6" BOLTS WITH WASHERS. LEVEL ONE FIELD TESTING IS REQUIRED, AND THE YIELD LOAD OF THE 3/4" Ø BOLT IS 12 KIPS. FOR ADHESIVELY ANCHORED ANCHOR BOLTS OR DOWELS, SEE STANDARD SPECIFICATIONS. SEE ROADWAY STANDARD 862.03 FOR DETAILS AND LOCATION OF THE RUBRAIL.



**SECTION E-E
GUARDRAIL ANCHOR ASSEMBLY DETAILS**




LOCATION OF ANCHORS FOR GUARDRAIL



* DENOTES GUARDRAIL ANCHOR ASSEMBLY

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 2 OF 2




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
**GUARDRAIL ANCHORAGE
 FOR 3'-6" BARRIER RAIL**
 (RIGHT LANE)

ASSEMBLED BY : K. D. LAYNE	DATE : 11/3/15
CHECKED BY : N. D'AJUTO	DATE : 11/9/15
DRAWN BY : TLA 5/06	REV. 10/1/11 MAA/GM
CHECKED BY : GM 5/06	REV. 7/12 MAA/GM
	REV. 6/13 MAA/GM

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-55
1			3			TOTAL SHEETS
2			4			74



PLAN OF CONCRETE BARRIER RAIL

NOTES

THE BARRIER RAIL IN EACH CONTINUOUS UNIT SHALL NOT BE CAST UNTIL ALL SLAB CONCRETE IN THAT UNIT HAS BEEN CAST AND HAS REACHED A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI.

ALL REINFORCING STEEL IN BARRIER RAILS SHALL BE EPOXY COATED.


GROOVED CONTRACTION JOINTS, 1/2" IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE BARRIER RAIL AND IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. THE CONTRACTION JOINT SHALL BE LOCATED AT EACH THIRD POINT BETWEEN BARRIER RAIL EXPANSION JOINTS. ONLY ONE CONTRACTION JOINT IS REQUIRED AT MIDPOINT OF BARRIER RAIL SEGMENTS LESS THAN 20 FEET IN LENGTH AND NO CONTRACTION JOINTS ARE REQUIRED FOR THOSE SEGMENTS LESS THAN 10 FEET IN LENGTH.

LONGITUDINAL BARS IN THE RAIL MAY BE FIELD CUT TO AVOID DRAIN SLOTS.

** THE CONTRACTOR MAY USE ADHESIVELY ANCHORED #5 S4 & S5 BARS, LEVEL 2 FIELD TESTING IS REQUIRED, AND THE YIELD LOAD OF THE #5 S4 & S5 IS 18.6 KIPS. FOR ADHESIVELY ANCHORED ANCHOR BOLTS OR DOWLES, SEE STANDARD SPECIFICATIONS.


BAR TYPE		BILL OF MATERIAL				
		FOR CONCRETE BARRIER RAIL ONLY				
		BAR	NO.	SIZE	TYPE	LENGTH
* B1	22	#5	STR	15'-8"	359	
* B2	66	#5	STR	27'-7"	1899	
* B3	22	#5	STR	12'-8"	291	
* S4	218	#5	3	4'-3"	966	
* S5	218	#5	STR	4'-1"	928	
		* EPOXY COATED REINFORCING STEEL		LBS.	4,443	
		CLASS AA CONCRETE		C.Y.	30.9	
		CONCRETE BARRIER RAIL		LIN. FT.	218.22	

ALL BAR DIMENSIONS ARE OUT TO OUT.



BARRIER RAIL DETAILS

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-



SHEET 1 OF 2

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

3'-7" CONCRETE BARRIER RAIL

(RIGHT LANE)

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-56
1			3			TOTAL SHEETS
2			4			74

ASSEMBLED BY : K. D. LAYNE DATE : 11/3/15
 CHECKED BY : N. D'AIUTO DATE : 11/9/15

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

NOTES

THE GUARDRAIL ANCHOR ASSEMBLY SHALL CONSIST OF A 1/4" HOLD-DOWN PLATE AND 4 - 1/8" Ø BOLTS WITH NUTS AND WASHERS, RUBRAIL, AND ADHESIVELY ANCHORED BOLTS.

THE HOLD-DOWN PLATE SHALL CONFORM TO AASHTO M270 GRADE 36. AFTER FABRICATION, THE HOLD-DOWN PLATE SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH AASHTO M111.

BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A307 AND NUTS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M291. BOLTS, NUTS AND WASHERS SHALL BE GALVANIZED. (AT THE CONTRACTOR'S OPTION, STAINLESS STEEL BOLTS, NUTS AND WASHERS MAY BE USED AS AN ALTERNATE FOR THE 1/8" Ø GALVANIZED BOLTS, NUTS AND WASHERS. THEY SHALL CONFORM TO OR EXCEED THE MECHANICAL REQUIREMENTS OF ASTM A307. THE USE OF THIS ALTERNATE SHALL BE APPROVED BY THE ENGINEER.)




THE GUARDRAIL ANCHOR ASSEMBLY IS REQUIRED AT ALL POINTS WHERE APPROACH GUARDRAIL IS TO BE ATTACHED TO THE END OF BARRIER RAIL. FOR POINTS OF ATTACHMENT, SEE SKETCH.

AFTER INSTALLATION, THE EXPOSED THREAD OF THE BOLT SHALL BE BURRED WITH A SHARP POINTED TOOL.



THE COST OF THE GUARDRAIL ANCHOR ASSEMBLY SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR CONCRETE BARRIER RAIL.

THE 1 1/4" Ø HOLES SHALL BE FORMED OR DRILLED WITH A CORE BIT. IMPACT TOOLS WILL NOT BE PERMITTED. ANY CONCRETE DAMAGED BY THIS WORK SHALL BE REPAIRED TO THE SATISFACTION OF THE ENGINEER.

THE C6 X 8.2 RUBRAIL IS TO BE ADHESIVELY ANCHORED TO THE RAIL USING THREE 3/4" Ø X 6" BOLTS WITH WASHERS. LEVEL ONE FIELD TESTING IS REQUIRED, AND THE YIELD LOAD OF THE 3/4" Ø BOLT IS 12 KIPS. FOR ADHESIVELY ANCHORED ANCHOR BOLTS OR DOWELS, SEE STANDARD SPECIFICATIONS. SEE ROADWAY STANDARD 862.03 FOR DETAILS AND LOCATION OF THE RUBRAIL.



LOCATION OF ANCHORS FOR GUARDRAIL



**SECTION E-E
GUARDRAIL ANCHOR ASSEMBLY DETAILS**

ASSEMBLED BY : K. D. LAYNE	DATE : 11/3/15
CHECKED BY : N. D'AJUTO	DATE : 11/9/15
DRAWN BY : TLA 5/06	REV. 10/1/11 MAA/GM
CHECKED BY : GM 5/06	REV. 7/12 MAA/GM
	REV. 6/13 MAA/GM

01-MAR-2016 10:56
R:\Structures\Plans\Str02\B5123.SD_BR_02.dgn
ndajuto

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED




PROJECT NO. B-5123
CABARRUS COUNTY
STATION: 21+44.10 -L-

SHEET 2 OF 2

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD
GUARDRAIL ANCHORAGE
FOR 3'-7" BARRIER RAIL
(RIGHT LANE)


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-57
1			3			TOTAL SHEETS
2			4			74

STR. #2 STD. NO. GRA2




ELEVATION


NOTE: FOR ATTACHMENT OF METAL RAIL TO END POST, SEE STANDARD NO. BMR2.




PLAN



SECTION THROUGH PARAPET AND RAIL



RIVET DETAIL




FRONT ELEVATION

SIDE ELEVATION


DETAILS OF POST

ASSEMBLED BY : K. D. LAYNE	DATE : 11/3/15
CHECKED BY : N. D'AJUTO	DATE : 11/9/15
DRAWN BY : EEM 6/94	REV. 5/1/06 TLA/GM
CHECKED BY : ROW 6/94	REV. 10/1/11 MAA/GM
	REV. 6/13 MAA/GM

01-MAR-2016 10:56
R:\Structures\Plans\Str02\B5123.SD_MR_02.dgn
ndaluto



PLAN



FRONT ELEVATION

SIDE ELEVATION

POST BASE DETAILS

NOTES

AT THE CONTRACTOR'S OPTION, METAL RAIL MAY BE EITHER ALUMINUM OR GALVANIZED STEEL IN ACCORDANCE WITH THE REQUIREMENTS OF THE GENERAL NOTES AND THE FOLLOWING SPECIFICATIONS FOR THE ALTERNATE MATERIALS; HOWEVER, THE CONTRACTOR WILL BE REQUIRED TO USE THE SAME RAIL MATERIAL ON ALL STRUCTURES ON THE PROJECT FOR WHICH METAL RAIL IS DESIGNATED.

UNLESS OTHERWISE REQUIRED IN THE CONTRACT DOCUMENTS, THE CONTRACTOR HAS THE OPTION TO USE AN ALTERNATE TO THE 2 BAR METAL RAIL. THE ALTERNATE RAIL SHALL MEET THE REQUIREMENTS OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS AND MUST BE LISTED ON THE DEPARTMENT'S APPROVED PRODUCTS LIST (APL) UNDER "2 BAR METAL RAIL ALTERNATE". ADJUSTMENTS TO THE CONCRETE PARAPET WILL NOT BE ALLOWED.

ALUMINUM RAILS

MATERIAL FOR POSTS, BASES AND RAILS, EXPANSION BARS AND CLAMP BARS SHALL BE ASTM B-221 ALLOY 6061-T6. MATERIAL FOR RIVETS SHALL BE ASTM B316 ALLOY 6061-T6. RIVETS SHALL BE STANDARD BUTTON HEAD AND CONE POINT COLD DRIVEN AS PER DRAWING.

THE BASE OF RAIL POSTS, OR ANY OTHER ALUMINUM SURFACE IN CONTACT WITH CONCRETE SHALL BE THOROUGHLY COATED WITH AN ALUMINUM IMPREGNATED CAULKING COMPOUND OF APPROVED QUALITY.

MATERIAL FOR SHIMS TO BE ASTM B209 ALLOY 6061-T6.

GALVANIZED STEEL RAILS

MATERIAL AND GALVANIZING ARE TO CONFORM TO THE FOLLOWING SPECIFICATIONS:

POST, POST BASES, RAILS, EXPANSION BARS AND CLAMP BARS: AASHTO M270 GRADE 36 STRUCTURAL STEEL - GALVANIZED TO AASHTO M111.

RIVETS: RIVETS SHALL MEET THE REQUIREMENTS OF ASTM A502 FOR GRADE 1 RIVETS.

THE CUT ENDS OF GALVANIZED STEEL RAILING, AFTER GRINDING SMOOTH SHALL BE GIVEN TWO COATS OF ZINC RICH PAINT MEETING THE REQUIREMENTS OF FEDERAL SPECIFICATION MIL-P-26915 USAF TYPE 1, OR OF FEDERAL SPECIFICATIONS TT-P-641.

SHIMS: SHIMS SHALL MEET THE REQUIREMENTS OF ASTM A570 FOR GRADE 33 OR A611 FOR GRADE C AND SHALL BE GALVANIZED IN ACCORDANCE WITH AASHTO M111.

RAIL CAPS: RAIL CAPS SHALL MEET THE REQUIREMENTS OF ASTM A570 FOR GRADE 33 OR A611 FOR GRADE C AND SHALL BE GALVANIZED IN ACCORDANCE WITH AASHTO M111.

GENERAL NOTES

RAILING SHALL BE CONTINUOUS FROM END POST TO END POST OF BRIDGE. EACH JOINT IN RAIL LENGTH SHALL BE SPLICED AS DETAILED. PANEL LENGTHS OF RAIL SHALL BE ATTACHED TO A MINIMUM OF THREE POSTS.

FOR END OF RAIL TO CLEAR FACE OF CONCRETE END POST DIMENSION, SEE STANDARD NO. BMR2.

CAP SCREWS SHALL BE ASTM F593 ALLOY 305 STAINLESS STEEL. WASHERS SHALL MEET THE REQUIREMENTS OF ASTM F844 EXCEPT THEY SHALL BE MADE FROM ALLOY 304 STAINLESS STEEL.

CERTIFIED MILL REPORTS ARE REQUIRED FOR RAILS AND POSTS. SHOP INSPECTION IS NOT REQUIRED.

METAL RAIL POSTS SHALL BE SET NORMAL TO CURB GRADE.

METHOD OF MEASUREMENT FOR METAL RAILS: FOR LENGTH OF METAL RAILS TO BE PAID FOR, SEE THE STANDARD SPECIFICATIONS.

CURVED RAIL USAGE: WHERE RAILS ARE TO BE USED ON BRIDGES ON HORIZONTAL AND/OR VERTICAL CURVATURE THE CONTRACTOR MAY, AT HIS OPTION, HAVE THE REQUIRED CURVATURE IN THE RAIL FORMED IN THE SHOP OR IN THE FIELD. IN EITHER EVENT, THE RAIL SHALL CONFORM WITHOUT BUCKLING OR KINKING TO THE REQUIRED CURVATURE IN A UNIFORM MANNER ACCEPTABLE TO THE ENGINEER.

TO INSURE FUTURE IDENTIFICATION OF THE FABRICATOR, A PERMANENT IDENTIFYING MARK SHALL BE PLACED ON EACH POST. THE METHOD OF MARKING AND LOCATION SHALL BE SUCH THAT IT DOES NOT DETRACT FROM THE APPEARANCE OF THE POST, BUT REMAINS VISIBLE AFTER RAIL PLACEMENT.

SHIMS SHALL BE USED AS NECESSARY FOR POST ALIGNMENT.

ALLOY 6351-T5 MAY BE SUBSTITUTED FOR ALLOY 6061-T6 WHERE APPLICABLE.


MINOR VARIATIONS IN DETAILS OF METAL RAIL WILL BE CONSIDERED. DETAILS OF SUCH VARIATIONS, IF DESIRED, SHALL BE SUBMITTED FOR APPROVAL.

GROOVED CONTRACTION JOINTS, 1/2" IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE PARAPET AND IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. A CONTRACTION JOINT SHALL BE LOCATED AT EACH THIRD POINT BETWEEN PARAPET EXPANSION JOINTS. ONLY ONE CONTRACTION JOINT IS REQUIRED AT MIDPOINT OF PARAPET SEGMENTS LESS THAN 20 FEET IN LENGTH AND NO CONTRACTION JOINTS ARE REQUIRED FOR THOSE SEGMENTS LESS THAN 10 FEET IN LENGTH.

PAY LENGTH = 210.05 LIN. FT.

PROJECT NO. B-5123
CABARRUS COUNTY
STATION: 21+44.10 -L-

SHEET 1 OF 4






STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD
2 BAR METAL RAIL
(RIGHT LANE)

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-58
1			3			TOTAL SHEETS
2			4			74

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

STR. #2 STD. NO. BMR3



4-BOLT METAL RAIL ANCHOR ASSEMBLY

(37 ASSEMBLIES REQUIRED)

NOTES


STRUCTURAL CONCRETE ANCHOR ASSEMBLY

THE STRUCTURAL CONCRETE ANCHOR ASSEMBLY SHALL CONSIST OF THE FOLLOWING COMPONENTS :


- A. FERRULES SHALL BE MADE FROM STEEL MEETING THE REQUIREMENTS OF AASHTO M169, GRADE 12L14 AND SHALL HAVE A MINIMUM LENGTH OF THREADS OF 2" FOR 3/4" FERRULES.
- B. 4 - 3/4" Ø X 2 1/2" BOLTS WITH WASHERS. BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A307. BOLTS AND WASHERS SHALL BE GALVANIZED. AT THE CONTRACTOR'S OPTION, STAINLESS STEEL BOLTS AND WASHERS MAY BE USED AS AN ALTERNATE FOR THE 3/4" Ø X 2" GALVANIZED BOLTS AND WASHERS. THEY SHALL CONFORM TO OR EXCEED THE MECHANICAL REQUIREMENTS OF ASTM A307. THE USE OF THIS ALTERNATE SHALL BE APPROVED BY THE ENGINEER.
- C. WIRE STRUT SHOWN IN THE CONCRETE ANCHOR ASSEMBLY DETAIL IS THE MINIMUM ALLOWABLE SIZE AND SHALL HAVE A MINIMUM TENSILE STRENGTH OF 100,000 PSI. AS AN OPTION, A 7/16" Ø WIRE STRUT WITH A MINIMUM TENSILE STRENGTH OF 90,000 PSI IS ACCEPTABLE.
- D. THE METAL RAIL ANCHOR ASSEMBLIES TO BE HOT DIPPED GALVANIZED TO CONFORM TO REQUIREMENTS OF AASHTO M111.
- E. THE COST OF THE METAL RAIL ANCHOR ASSEMBLY WITH BOLTS AND WASHERS COMPLETE IN PLACE SHALL BE INCLUDED IN THE PRICE BID FOR LINEAR FEET OF METAL RAIL.
- F. BOLTS TO BE TIGHTENED ONE-HALF TURN WITH A WRENCH FROM A FINGER-TIGHT POSITION.

THE CONTRACTOR MAY USE ADHESIVELY ANCHORED ANCHOR BOLTS IN PLACE OF THE METAL RAIL ANCHOR ASSEMBLY. LEVEL ONE FIELD TESTING IS REQUIRED, AND THE YIELD LOAD OF THE 3/4" Ø BOLT IS 10 KIPS. FOR ADHESIVELY ANCHORED ANCHOR BOLTS OR DOWELS, SEE THE STANDARD SPECIFICATIONS.

WHEN ADHESIVELY ANCHORED ANCHOR BOLTS ARE USED, BOLTS SHALL MEET THE REQUIREMENTS OF ASTM F593 ALLOY 304 STAINLESS STEEL WITH MINIMUM 75,000 PSI ULTIMATE STRENGTH. NUTS SHALL MEET THE REQUIREMENTS OF ASTM F594 ALLOY 304 STAINLESS STEEL AND WASHERS SHALL MEET THE REQUIREMENTS OF ASTM F844 EXCEPT THEY SHALL BE MADE FROM ALLOY 304 STAINLESS STEEL.




EXPANSION BAR DETAILS




SHIM DETAILS

NOTE: SHIMS MAY BE CUT ALONG PERMITTED CUTLINE OR SLOTTED TO EDGE OF PLATE TO FACILITATE PLACEMENT.



CLAMP BAR DETAIL


(4 REQUIRED PER POST)



CLAMP ASSEMBLY

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 2 OF 4



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 2 BAR METAL RAIL


(RIGHT LANE)

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-59
1			3			TOTAL SHEETS
2			4			74


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

STR. #2 STD. NO. BMR4

ASSEMBLED BY : K. D. LAYNE	DATE : 11/3/15
CHECKED BY : N. D'AJUTA	DATE : 11/9/15
DRAWN BY : EEM 6/94	REV. 8/16/99 MAB/LES
CHECKED BY : ROW 6/94	REV. 5/1/06R KMM/GM
	REV. 10/1/11 MAA/GM



SPAN A




SPAN B

PLAN OF RAIL POST SPACING

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 3 OF 4





STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

SUPERSTRUCTURE
 PLAN OF RAIL
 POST SPACING
 (RIGHT LANE)


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-60
1			3			TOTAL SHEETS
2			4			74

DRAWN BY : K. D. LAYNE DATE : 11/3/15
 CHECKED BY : N. D'AIUTO DATE : 11/9/15
 DESIGN ENGINEER OF RECORD: T. H. CARROLL DATE : 11/9/15

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED



DETAILS FOR ATTACHING METAL RAIL TO END POST



STRUCTURAL CONCRETE INSERT

* EACH WELDED ATTACHMENT OF WIRE TO FERRULE SHALL DEVELOP THE TENSILE STRENGTH OF THE WIRE.

NOTES

STRUCTURAL CONCRETE INSERT

THE STRUCTURAL CONCRETE INSERT ASSEMBLY SHALL CONSIST OF THE FOLLOWING COMPONENTS:

- A. FERRULES SHALL BE MADE FROM STEEL MEETING THE REQUIREMENTS OF AASHTO M169, GRADE 12L14 AND SHALL HAVE A MINIMUM LENGTH OF THREADS OF 1 1/2".
- B. 1 - 3/4" Ø X 1 5/8" BOLT WITH WASHER. BOLT SHALL CONFORM TO THE REQUIREMENTS OF ASTM A307. BOLT AND WASHER SHALL BE GALVANIZED. (AT THE CONTRACTOR'S OPTION, STAINLESS STEEL BOLT AND WASHER MAY BE USED AS AN ALTERNATE FOR THE 3/4" Ø X 1 5/8" GALVANIZED BOLT AND WASHER. THEY SHALL CONFORM TO OR EXCEED THE MECHANICAL REQUIREMENTS OF ASTM A307. THE USE OF THIS ALTERNATE SHALL BE APPROVED BY THE ENGINEER.)
- C. WIRE STRUT SHOWN IN THE CONCRETE INSERT ASSEMBLY DETAIL IS THE MINIMUM ALLOWABLE SIZE AND SHALL HAVE A MINIMUM TENSILE STRENGTH OF 100,000 PSI. AS AN OPTION, A 1/16" Ø WIRE STRUT WITH A MINIMUM TENSILE STRENGTH OF 90,000 PSI IS ACCEPTABLE.

NOTES

METAL RAIL TO END POST CONNECTION

THE METAL RAIL TO END POST CONNECTION SHALL CONSIST OF THE FOLLOWING COMPONENTS:

- A. 1/2" PLATES SHALL CONFORM TO AASHTO M270 GRADE 36 AND SHALL BE GALVANIZED AFTER FABRICATION.
- B. 3/4" STRUCTURAL CONCRETE INSERT SHALL HAVE A WORKING LOAD SHEAR CAPACITY OF 4800 LBS. THE FERRULES SHALL ENGAGE A 3/4" Ø X 1 5/8" BOLT WITH 2" O.D. WASHER IN PLACE. THE 3/4" Ø X 1 5/8" BOLT SHALL HAVE N. C. THREADS.
- C. CAP SCREWS FOR RAIL ATTACHMENT TO ANGLE SHALL CONFORM TO THE REQUIREMENTS OF ASTM F593 ALLOY 305 STAINLESS STEEL. CAP SCREWS TO BE CENTERED IN SLOTS AT 60°F.
- D. STANDARD CLAMP BARS (SEE METAL RAIL SHEET).
- E. 1/2" Ø PIPE SLEEVES (IF REQUIRED) TO BE GALVANIZED.

THE COST OF THE STANDARD CLAMP BARS AND CAP SCREWS USED IN THE METAL RAIL TO END POST CONNECTION SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR LINEAR FEET OF 1 OR 2 BAR METAL RAILS.


THE 3/4" STRUCTURAL CONCRETE INSERT WITH BOLT SHALL BE ASSEMBLED IN THE SHOP.

THE COST OF THE 3/4" STRUCTURAL CONCRETE INSERT ASSEMBLY, AND THE 1/2" PLATES COMPLETE IN PLACE SHALL BE INCLUDED IN THE VARIOUS PAY ITEMS.

THE CONTRACTOR, AT HIS OPTION, MAY USE AN ADHESIVE BONDING SYSTEM IN LIEU OF THE STRUCTURAL CONCRETE INSERT EMBEDDED IN THE END POST. IF THE ADHESIVE BONDING SYSTEM IS USED, THE 3/4" Ø X 1 5/8" BOLT WITH WASHER SHALL BE REPLACED WITH A 3/4" Ø X 6 1/2" BOLT AND 2" O.D. WASHER. ALL SPECIFICATIONS THAT APPLY TO THE 3/4" Ø X 1 5/8" BOLT SHALL APPLY TO THE 3/4" Ø X 6 1/2" BOLT. FIELD TESTING OF THE ADHESIVE BONDING SYSTEM IS NOT REQUIRED.

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 4 OF 4



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 RAIL POST SPACINGS
 AND
 END OF RAIL DETAILS
 FOR TWO BAR METAL RAILS
 (RIGHT LANE)



ASSEMBLED BY : K. D. LAYNE	DATE : 11/3/15
CHECKED BY : N. D'AUTO	DATE : 11/9/15
DRAWN BY : FCJ 1/88	REV. 5/7/03 RWW/JTE
CHECKED BY : CRK 3/89	REV. 5/1/06 TLA/GM
	REV. 10/1/11 MAA/GM

01-MAR-2016 10:56
 R:\Structures\Plans\Str02\B5123_SD_MR_02.dgn
 ndaluto


DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-61
1			3			TOTAL SHEETS
2			4			74


STR. #2 STD. NO. BMR2




PLAN OF PARAPET




PLAN OF END POST




PLAN OF PARAPET



END VIEW




ELEVATION



SECTION THROUGH PARAPET

PARAPET AND END POST FOR TWO BAR RAIL

BAR TYPES



ALL BAR DIMENSIONS ARE OUT TO OUT.

BILL OF MATERIAL

PARAPET AND END POSTS


BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
* B1	16	#5	STR	15'-8"	261
* B2	48	#5	STR	27'-7"	1,381
* B3	16	#5	STR	12'-8"	211
* E1	4	#7	STR	2'-6"	20
* E2	4	#7	STR	3'-0"	25
* E3	4	#7	STR	3'-6"	29
* E4	4	#7	STR	4'-0"	33
* E5	4	#7	STR	4'-4"	35
* F1	4	#6	STR	1'-10"	11
* F2	2	#6	STR	3'-4"	10
* F3	2	#6	STR	3'-11"	12
* F4	2	#6	STR	3'-0"	9
* F5	2	#6	STR	3'-8"	11
* S1	218	#5	1	5'-5"	1,232
* S2	218	#5	2	5'-6"	1,251

* EPOXY COATED
REINFORCING STEEL = LBS. 4,531

CLASS AA CONCRETE = C.Y. 24.0

1'-2" x 2'-6"
CONCRETE PARAPET = LIN. FT. 218.23

PROJECT NO. B-5123
CABARRUS COUNTY
STATION: 21+44.10 -L-




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
1'-2" PARAPET AND
END POST DETAILS
FOR TWO BAR
METAL RAIL
(RIGHT LANE)


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	5-62
1			3			TOTAL SHEETS
2			4			74

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

DRAWN BY: K.D. LAYNE DATE: 11/3/15
CHECKED BY: N.D. AIUTO DATE: 11/9/15
DESIGN ENGINEER OF RECORD: T.H. CARROLL DATE: 12/7/15




LAYOUT FOR COMPUTING AREA REINFORCED CONCRETE DECK SLAB (SQ. FT. = 12,412)



POUR SEQUENCE


← ⊕ → = INDICATES POUR NUMBER AND DIRECTION OF POUR



OPTIONAL POUR SEQUENCE

POUR ② CAN NOT BE STARTED UNTIL BOTH ADJACENT ① POURS REACH A MINIMUM OF 3,000 PSI.

REINFORCING BAR SCHEDULE											
BAR NO.	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR NO.	NO.	SIZE	TYPE	LENGTH	WEIGHT
*A1	339	#5	STR	56'-1"	19800	*B1	149	#5	STR	21'-5"	3328
A2	339	#5	STR	56'-1"	19800	*B2	78	#4	STR	26'-9"	1394
*A101	4	#5	STR	53'-2"	222	*B3	150	#5	STR	39'-5"	6167
*A102	4	#5	STR	50'-0"	209	*B4	74	#5	STR	33'-3"	2566
*A103	4	#5	STR	46'-9"	195	B5	172	#5	STR	56'-2"	10076
*A104	4	#5	STR	43'-7"	182	*B6	78	#4	STR	28'-3"	1472
*A105	4	#5	STR	40'-4"	168	*B7	149	#5	STR	22'-8"	3523
*A106	4	#5	STR	37'-2"	155	H1	9	#5	STR	13'-11"	131
*A107	4	#5	STR	33'-11"	142	H2	9	#5	STR	13'-8"	128
*A108	4	#5	STR	30'-9"	128	H3	13	#5	STR	14'-4"	194
*A109	4	#5	STR	27'-6"	115	H4	13	#5	STR	14'-1"	191
*A110	4	#5	STR	24'-4"	102	H5	13	#5	STR	12'-7"	118
*A111	4	#5	STR	21'-1"	88	H6	13	#5	STR	12'-10"	120
*A112	4	#5	STR	17'-11"	75	H7	9	#5	STR	15'-2"	206
*A113	4	#5	STR	14'-8"	61	H8	9	#5	STR	15'-5"	209
*A114	4	#5	STR	11'-6"	48	K1	42	#4	STR	23'-3"	652
*A115	4	#5	STR	8'-4"	35	K2	4	#4	STR	5'-2"	14
*A116	4	#5	STR	5'-1"	21	K3	2	#4	STR	6'-7"	9
A201	4	#5	STR	53'-2"	222	K4	18	#4	STR	8'-4"	100
A202	4	#5	STR	50'-0"	209	K5	4	#4	STR	5'-0"	13
A203	4	#5	STR	46'-9"	195	K6	4	#4	STR	5'-9"	15
A204	4	#5	STR	43'-7"	182	K7	20	#4	STR	6'-7"	88
A205	4	#5	STR	40'-4"	168	K8	16	#4	STR	3'-6"	37
A206	4	#5	STR	37'-2"	155	K9	20	#4	STR	4'-5"	59
A207	4	#5	STR	33'-11"	142	K10	10	#4	STR	5'-10"	39
A208	4	#5	STR	30'-9"	128	K11	90	#4	STR	7'-6"	451
A209	4	#5	STR	27'-6"	115	K12	2	#4	STR	5'-4"	7
A210	4	#5	STR	24'-4"	102	K13	10	#4	STR	4'-7"	31
A211	4	#5	STR	21'-1"	88	K14	6	#4	5	5'-10"	23
A212	4	#5	STR	17'-11"	75	K15	6	#4	6	11'-5"	46
A213	4	#5	STR	14'-8"	61	K16	6	#4	5	5'-6"	22
A214	4	#5	STR	11'-6"	48	K17	24	#4	6	10'-9"	172
A215	4	#5	STR	8'-4"	35						
A216	4	#5	STR	5'-1"	21						
						S1	198	#4	2	2'-10"	375
						S2	54	#4	3	13'-3"	478
						*S3	70	#4	4	11'-11"	557
						*S4	54	#4	4	10'-6"	379
						S5	16	#4	3	15'-5"	165
						S6	28	#4	3	11'-9"	220
						U1	30	#4	1	14'-9"	296
						U2	12	#4	7	9'-2"	73
						REINFORCING STEEL		LBS.	36,504		
						*EPOXY COATED REINFORCING STEEL		LBS.	41,132		



— SUPERSTRUCTURE BILL OF MATERIAL —

	CLASS AA CONCRETE (CU. YDS.)	REINFORCING STEEL (LBS.)	EPOXY COATED REINFORCING STEEL (LBS.)
POUR #1	167.6		
POUR #2	228.8		
POUR #3	129.8	36,504	41,132
TOTALS**	526.2	36,504	41,132

** QUANTITIES FOR PARAPET AND CONCRETE BARRIER RAILS ARE NOT INCLUDED


GROOVING BRIDGE FLOORS

APPROACH SLABS	2,219 SQ.FT.
BRIDGE DECK	10,022 SQ.FT.
TOTAL	12,241 SQ.FT.

SUPERSTRUCTURE REINFORCING STEEL LENGTHS ARE BASED ON THE FOLLOWING MINIMUM SPLICE LENGTHS

BAR SIZE	SUPERSTRUCTURE EXCEPT APPROACH SLABS, PARAPET, AND BARRIER RAIL		APPROACH SLABS		PARAPET AND BARRIER RAIL
	EPOXY COATED	UNCOATED	EPOXY COATED	UNCOATED	
#4	2'-0"	1'-9"	2'-0"	1'-9"	2'-9"
#5	2'-6"	2'-2"	2'-6"	2'-2"	3'-5"
#6	3'-0"	2'-7"	3'-10"	2'-7"	4'-4"
#7	5'-3"	3'-6"			
#8	6'-10"	4'-7"			

PROJECT NO. B-5123
 CABARRUS COUNTY
 STATION: 21+44.10 -L-




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUPERSTRUCTURE
 BILL OF MATERIAL
 (RIGHT LANE)

DRAWN BY : N.D.AIUTO DATE: 11/9/15
 CHECKED BY : K.D.LAYNE DATE: 11/18/15
 DESIGN ENGINEER OF RECORD : H.A.LOCKLEAR DATE: 11/18/15

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS						SHEET NO. S-63
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 74
2			4			



PLAN


NOTES

SEE SUPERSTRUCTURE SHEETS FOR UPPER PART OF INTEGRAL END BENT DETAILS.

THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT THE UPPER PART OF WING IS TO BE POURED WITH SUPERSTRUCTURE.

THE TOP SURFACE OF THE END BENT CAP AND WINGS, EXCEPT THE BEARING AREA, SHALL BE RAKED TO A DEPTH OF 1/4".

FOR PILE SPLICE DETAILS, SEE SHEET 2 OF 2 OF INTEGRAL END BENT 2.




ELEVATION

PROJECT NO. B-5123

CABARRUS COUNTY

STATION: 21+44.10 -L-

SHEET 1 OF 2




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
SUBSTRUCTURE
INTEGRAL
END BENT 1
(RIGHT LANE)

REVISIONS

NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			S-64
2			4			TOTAL SHEETS 74

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

DRAWN BY: N.D. AIUTO DATE: 11/17/15
CHECKED BY: K.D. LAYNE DATE: 11/18/15
DESIGN ENGINEER OF RECORD: T.H. CARROLL DATE: 12/7/15




BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.


BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETERMINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.


TEMPORARY DRAINAGE AT END BENT




SECTION A-A




PARTIAL SECTION B-B




BILL OF MATERIAL					
END BENT 1					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	10	#9	1	37'-5"	1272
B2	5	#9	1	60'-0"	1020
B3	1	#9	1	17'-4"	59
B4	1	#9	1	17'-8"	60
B5	1	#9	1	18'-0"	61
B6	1	#9	1	18'-3"	62
B7	1	#9	1	18'-7"	63
B8	30	#4	STR	23'-8"	474
B9	19	#4	STR	3'-5"	43
B10	5	#4	STR	17'-2"	57
B11	5	#4	STR	8'-7"	29
H5	6	#5	STR	12'-7"	79
H6	6	#5	STR	12'-10"	80
H7	10	#5	STR	15'-2"	158
H8	10	#5	STR	15'-5"	161
S1	62	#4	3	11'-5"	473
S2	82	#4	2	4'-2"	228
S3	44	#4	4	6'-6"	191
S4	20	#4	3	12'-11"	173
U1	18	#4	5	6'-5"	77
V1	108	#5	STR	6'-11"	779
V2	22	#5	STR	10'-0"	229
V3	28	#5	STR	11'-1"	324
REINFORCING STEEL				LBS.	6,152
CLASS A CONCRETE					
CAP, LOWER WINGS & COLLARS				C.Y.	46.2
HP 12X53 STEEL PILES					
NO. 11				LIN. FT.	525




PLAN OF RIGHT WING



PLAN OF LEFT WING




ELEVATION OF RIGHT WING




SECTION X-X

SECTION Y-Y



ELEVATION OF LEFT WING

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-
 SHEET 2 OF 2



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUBSTRUCTURE
 INTEGRAL
 END BENT 1
 (RIGHT LANE)

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-65
1			3			TOTAL SHEETS
2			4			74

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

DRAWN BY: N.D. AIUTO DATE: 11/17/15
 CHECKED BY: K.D. LAYNE DATE: 11/18/15
 DESIGN ENGINEER OF RECORD: T.H. CARROLL DATE: 12/7/15

NOTES

STIRRUPS AND "U" BARS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR ANCHOR BOLTS.


HOOKS ON "V" BARS MAY BE TURNED AS NECESSARY FOR PLACING REINFORCING STEEL.

ALL STEEL IN THE DRILLED PIERS IS INCLUDED IN THE PAY ITEMS FOR "REINFORCING STEEL" AND "SPIRAL COLUMN REINFORCING STEEL".

THE LOCATION OF THE CONSTRUCTION JOINT IN THE DRILLED PIERS IS BASED ON AN APPROXIMATE GROUND LINE ELEVATION. IF THE CONSTRUCTION JOINT IS ABOVE THE ACTUAL GROUND LINE ELEVATION, THE CONTRACTOR SHALL PLACE THE CONSTRUCTION JOINT 1 FT. BELOW THE GROUND LINE.


FOR DRILLED PIERS, SEE GEOTECHNICAL SPECIAL PROVISIONS AND SECTION 411 OF THE STANDARD SPECIFICATIONS.

THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT THE LONGITUDINAL REINFORCEMENT FOR THE DRILLED PIERS IS DETAILED WITH 3 FEET OF EXTRA LENGTH.



DETAIL "A"

DIMENSIONS ARE TYPICAL FOR EACH BEARING



CONSTRUCTION JOINT DETAIL

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 1 OF 2



DocuSigned by:
 J.K. Bowles
 1C157DE150466AA...
 3/1/2016

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

SUBSTRUCTURE

BENT 1


(RIGHT LANE)

REVISIONS


NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			5-66
2			4			TOTAL SHEETS
						74

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

STR. #2




PLAN




ELEVATION


DRAWN BY: J.K. BOWLES DATE: 11/9/15
 CHECKED BY: N.D'AIUTO DATE: 11/10/15
 DESIGN ENGINEER OF RECORD: T.H. CARROLL DATE: 12/7/15



PLAN OF COLUMNS & DRILLED PIERS




LEFT END ELEVATION




SECTION A-A

*INVERT ALTERNATE STIRRUPS



ALL BAR DIMENSIONS ARE OUT TO OUT.



END VIEW

(TYP. EACH END)

BILL OF MATERIAL					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	8	#11	1	59'-8"	2536
B2	7	#11	STR	56'-8"	2107
B3	8	#5	STR	56'-8"	473
M1	12	#11	STR	45'-2"	2880
M2	12	#11	STR	41'-2"	2625
M3	12	#11	STR	37'-4"	2380
S1	54	#5	2	13'-0"	732
S2	28	#5	2	12'-0"	350
U1	63	#4	3	6'-10"	288
U2	8	#4	3	6'-8"	36
U3	8	#4	3	7'-1"	38
V1	36	#11	4	18'-0"	3443
REINFORCING STEEL					LBS. 17,888
SP-1	1	**	5	827'-7"	863
SP-2	1	**	5	732'-1"	764
SP-3	1	**	5	639'-1"	667
SP-4	1	*	6	589'-3"	394
SP-5	1	*	6	572'-1"	382
SP-6	1	*	6	557'-4"	372
SPIRAL COLUMN REINFORCING STEEL					LBS. 3,442
** THE SP-1, SP-2 & SP-3 SPIRAL REINFORCING STEEL SHALL BE W31 OR D-31 COLD DRAWN WIRE OR #5 PLAIN OR DEFORMED BAR.					
* THE SP-4, SP-5, & SP-6 SPIRAL REINFORCING STEEL SHALL BE W20 OR D-20 COLD DRAWN WIRE OR #4 PLAIN OR DEFORMED BAR.					
CLASS A CONCRETE					
POUR #3 (CAP)				C.Y.	40.4
POUR #2 (COLUMNS)				C.Y.	14.9
TOTAL CLASS A CONCRETE				C.Y.	55.3
DRILLED PIER QUANTITIES					
DRILLED PIER CONCRETE					
POUR #1 (DRILLED PIERS)				C.Y.	43.3
4'-0" Ø DRILLED PIERS IN SOIL				LIN. FT.	60.00
4'-0" Ø DRILLED PIERS NOT IN SOIL				LIN. FT.	33.00
PERMANENT STEEL CASING FOR 4'-0" Ø DRILLED PIER				LIN. FT.	63.00
SID INSPECTIONS				EA.	1
SPT TESTING				EA.	1
CSL TESTING				EA.	1
CSL TUBES				LIN. FT.	390

PROJECT NO. B-5123
 CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 2 OF 2

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

SUBSTRUCTURE


BENT 1

(RIGHT LANE)


REVISIONS

NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			5-67
2			4			TOTAL SHEETS 74




DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



DRAWN BY: J.K. BOWLES DATE: 11/9/15
 CHECKED BY: N.D. AIUTO DATE: 11/10/15
 DESIGN ENGINEER OF RECORD: T.H. CARROLL DATE: 12/7/15








PILE SPLICE DETAILS



ALL BAR DIMENSIONS ARE OUT TO OUT.


BILL OF MATERIAL

END BENT 2					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	10	#9	1	37'-5"	1272
B2	5	#9	1	60'-0"	1020
B3	1	#9	1	17'-4"	59
B4	1	#9	1	17'-8"	60
B5	1	#9	1	18'-0"	61
B6	1	#9	1	18'-3"	62
B7	1	#9	1	18'-7"	63
B8	30	#4	STR	23'-8"	474
B9	19	#4	STR	3'-5"	43
B10	5	#4	STR	17'-2"	57
B11	5	#4	STR	8'-7"	29
H1	6	#5	STR	13'-11"	87
H2	6	#5	STR	13'-8"	86
H3	10	#5	STR	14'-4"	149
H4	10	#5	STR	14'-1"	147
S1	62	#4	3	11'-5"	473
S2	82	#4	2	4'-2"	228
S3	44	#4	4	6'-6"	191
S4	20	#4	3	12'-11"	173
U1	18	#4	5	6'-5"	77
V1	108	#5	STR	6'-11"	779
V2	24	#5	STR	10'-0"	250
V3	26	#5	STR	11'-1"	301
REINFORCING STEEL				LBS.	6,141
CLASS A CONCRETE					
CAP, LOWER WINGS & COLLARS				C.Y.	46.0
HP 12X53 STEEL PILES					
NO. 11				LIN. FT.	360



PROJECT NO. B-5123
CABARRUS COUNTY
STATION: 21+44.10 -L-

SHEET 2 OF 2



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
SUBSTRUCTURE
INTEGRAL
END BENT 2
(RIGHT LANE)

REVISIONS

NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			5-69
2			4			TOTAL SHEETS 74


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

DRAWN BY: N.D. AIUTO DATE: 11/17/15
CHECKED BY: K.D. LAYNE DATE: 11/18/15
DESIGN ENGINEER OF RECORD: T.H. CARROLL DATE: 12/7/15

GENERAL NOTES

SLOPE PROTECTION SHALL BE PLACED UNDER THE END OF THE BRIDGE AS SHOWN IN THE DETAILS. STRAIGHT EDGING WILL NOT BE REQUIRED UNLESS, IN THE OPINION OF THE ENGINEER, VISUAL INSPECTION INDICATEDS NEED FOR IT. MEASUREMENT AND PAYMENT SHALL BE AS PRESCRIBED IN SECTION 462 OF THE STANDARD SPECIFICATIONS. FOR BERM WIDTH, SEE GENERAL DRAWING.


SLOPE PROTECTION SHALL CONSIST OF 4" POURED-IN PLACE CONCRETE PAVING AS SHOWN IN THE DETAILS ON THIS SHEET. CONCRETE SHALL BE CLASS "B". THE CONCRETE SURFACE SHALL BE FLOATED WITH A WOODEN FLOAT AND FINISHED. WELDED WIRE FABRIC REINFORCING SHALL BE 6 X 6 - W1.4 X W1.4, 60" WIDE. SLOPE PROTECTION SHALL BE POURED IN 5' STRIPS AS SHOWN IN THE "POURING DETAIL" WITH 2'-0" LONG #4 BARS PLACED ALONG THE SLOPE BETWEEN STRIPS AT 1'-6" MAXIMUM SPACING. SLOPE PROTECTION MAY BE POURED IN ALTERNATE 4' AND 5' STRIPS AS SHOWN IN THE "OPTIONAL POURING DETAIL" WITH ADJACENT RUNS OF WELDED WIRE FABRIC LAPPING AT LEAST 6". THE COST OF THE WELDED WIRE FABRIC AND #4 BARS, IF USED, SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE BID PER SQUARE YARD FOR SLOPE PROTECTION.




PLAN

BRIDGE @ STA. 21+44.10 -L-	4 INCH SLOPE PROTECTION	* WELDED WIRE FABRIC 60 INCHES WIDE
	SQUARE YARDS	APPROX. L.F.
END BENT 1	410	820


* QUANTITY SHOWN IS BASED ON 5' POURS.




SECTION A-A




POURING DETAIL



OPTIONAL POURING DETAIL




SECTION B-B



SECTION ALONG ROADWAY

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
**SLOPE PROTECTION
 DETAILS**
 (RIGHT LANE)


REVISIONS				SHEET NO.		
NO.	BY:	DATE:	NO.	BY:	DATE:	S-70
1			3			TOTAL SHEETS
2			4			74

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


ASSEMBLED BY : K. D. LAYNE	DATE : 11/9/15
CHECKED BY : H. LOCKLEAR	DATE : 11/18/15
DRAWN BY : ELR 5/92	REV. 5/1/06 TLA/GM
CHECKED BY : GRP 6/92	REV. 10/1/11 MAA/GM
	REV. 12/21/11 MAA/GM

ESTIMATED QUANTITIES


BRIDGE @ STA. 21+44.10 -L-	RIP RAP CLASS II (2'-0" THICK)	GEOTEXTILE FOR DRAINAGE
	TONS	SQUARE YARDS
BANK STABILIZATION NEAR END BENT 2	50	55
END BENT 2	475	530
TOTAL	525	585



PLAN OF RIP RAP




SECTION B-B



SECTION C-C

PROJECT NO. B-5123
IREDELL COUNTY
 STATION: 21+44.10 -L-



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

RIP RAP DETAILS

(RIGHT LANE)

REVISIONS

NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			S-71
2			4			TOTAL SHEETS 74

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

ASSEMBLED BY: N.D. AIUTO DATE: 11/12/15
 CHECKED BY: K.D. LAYNE DATE: 11/17/15
 DESIGN ENGINEER OF RECORD: T.H. CARROLL DATE: 12/7/15

NOTES

APPROACH SLAB SHALL NOT BE CONSTRUCTED PRIOR TO COMPLETION OF THE BRIDGE DECK.


FOR REINFORCED BRIDGE APPROACH FILL FABRIC WALL INCLUDING GEOTEXTILE, IMPERMEABLE GEOMEMBRANE, 4" Ø DRAINAGE PIPE, #78M STONE, WELDED WIRE FORM, AND SELECT MATERIAL, SEE ROADWAY PLANS.

AREA BETWEEN THE WINGWALL AND APPROACH SLAB SHALL BE GRADED TO DRAIN THE WATER AWAY FROM THE FILL FACE OF THE BRIDGE AND SHALL BE PAVED. SEE ROADWAY PLANS.


THE JOINT OPENING AT THE APPROACH SLAB/DECK INTERFACE SHALL BE SAWED NO MORE THAN 12 HOURS AFTER THE APPROACH SLAB IS CAST. THE JOINT SHALL BE CLEANED OF ALL DEBRIS BEFORE THE SEALANT IS APPLIED. THE JOINT SEALER MATERIAL SHALL CONFORM TO THE REQUIREMENTS OF SECTION 1028-3 OF THE STANDARD SPECIFICATIONS.

BILL OF MATERIAL					
FOR ONE APPROACH SLAB (2 REQ'D)					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
* A1	52	#4	STR	30'-0"	1042
A2	52	#4	STR	29'-11"	1039
* B1	110	#5	STR	24'-1"	2763
B2	110	#6	STR	24'-7"	4062
REINFORCING STEEL				LBS.	5,101
* EPOXY COATED REINFORCING STEEL				LBS.	3,805
CLASS AA CONCRETE				C.Y.	59.3

SPLICE LENGTHS		
BAR SIZE	EPOXY COATED	UNCOATED
#4	2'-0"	1'-9"
#5	2'-6"	2'-2"
#6	3'-10"	2'-7"




PLAN @ END BENT 1 PLAN @ END BENT 2
DIMENSIONS SHOWN ARE TYPICAL FOR BOTH APPROACH SLABS



PROJECT NO. B-5123
CABARRUS COUNTY
STATION: 21+44.10 -L-

SHEET 1 OF 3

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
BRIDGE APPROACH SLAB FOR INTEGRAL ABUTMENT					
(RIGHT LANE)					
REVISIONS					SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
TOTAL SHEETS					74




DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

DRAWN BY: K. D. LAYNE DATE: 8/25/15
CHECKED BY: N. D'AIUTO DATE: 11/9/15



01-MAR-2016 10:55
R:\Structures\Plans\Str02\B5123_SD_AS_02.dgn
ndaluto

STR. #2




NOTE: IMMEDIATELY AFTER THE CONSTRUCTION OF THE APPROACH SLAB, THE CONTRACTOR SHALL PROVIDE TEMPORARY BERM AND SLOPE DRAIN. CONTRACTOR SHALL GRADE TO PIPE INLET AND PROVIDE EROSION RESISTANT MATERIAL AS SHOWN. THE EROSION RESISTANT MATERIAL SHALL BE EITHER 1) ASPHALT PLANT MIX, TYPE 1 OR TYPE 2, MIN. 2" DEPTH, 2) EROSION CONTROL MAT, OR 3) CONCRETE, AS DIRECTED BY THE ENGINEER. THE SLOPE DRAIN SHALL CONSIST OF A NON-PERFORATED TEMPORARY DRAINAGE PIPE, 12 INCHES IN DIAMETER.

PLAN VIEW



SECTION S-S




NOTE: IF THE APPROACH SLAB IS NOT CONSTRUCTED IMMEDIATELY AFTER THE BACKFILLING OF THE END BENT EXCAVATION, GRADE TO DRAIN TO THE BOTTOM OF THE SLOPE AND PROVIDE EROSION RESISTANT MATERIAL, SUCH AS FIBERGLASS ROVING OR AS DIRECTED BY THE ENGINEER TO PREVENT SOIL EROSION AND TO PROTECT THE AREA ADJACENT TO THE STRUCTURE. THE CONTRACTOR WILL BE REQUIRED TO REMOVE THESE MATERIALS PRIOR TO CONSTRUCTION OF THE APPROACH SLAB.


TEMPORARY DRAINAGE DETAIL

TEMPORARY BERM AND SLOPE DRAIN DETAILS

(TO BE USED WHEN SHOULDER BERM GUTTER IS REQUIRED)




SECTION THROUGH SLAB



DETAIL "A"

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 2 OF 3



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

**BRIDGE APPROACH
 SLAB DETAILS**

(RIGHT LANE)

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-73
1			3			TOTAL SHEETS
2			4			74

ASSEMBLED BY : K. D. LAYNE DATE : 8/25/15
 CHECKED BY : N. D'AIUTO DATE : 11/9/15

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

NOTES


ALL REINFORCING STEEL IN BARRIER RAILS SHALL BE EPOXY COATED.

** THE #5 S4, S5, S6 & S7 BARS SHALL BE INSTALLED USING AN ADHESIVE ANCHORING SYSTEM. THE YIELD LOAD FOR THE #5 S4, S5, S6, & S7 BARS IS 18.6 KIPS. FIELD TESTING FOR THE ADHESIVE BOND SYSTEM IS NOT REQUIRED.

REINFORCING BARS IN THE RAIL MAY BE FIELD CUT TO AVOID DRAIN SLOTS.

GROOVED CONTRACTION JOINTS, 1/2" IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE BARRIER RAIL AND IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. THE CONTRACTION JOINT SHALL BE LOCATED AT EACH THIRD POINT BETWEEN BARRIER RAIL EXPANSION JOINTS. ONLY ONE CONTRACTION JOINT IS REQUIRED AT MIDPOINT OF BARRIER RAIL SEGMENTS LESS THAN 20 FEET IN LENGTH AND NO CONTRACTION JOINTS ARE REQUIRED FOR THOSE SEGMENTS LESS THAN 10 FEET IN LENGTH.

BAR TYPES



ALL BAR DIMENSIONS ARE OUT TO OUT.

BILL OF MATERIAL


FOR CONCRETE BARRIER RAIL

BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
* B3	22	#5	STR	24'-7"	564
* S4	44	#5	3	4'-3"	195
* S5	44	#5	STR	4'-1"	187
* S6	4	#5	3	3'-6"	15
* S7	4	#5	STR	3'-4"	14


* EPOXY COATED REINFORCING STEEL LBS. 975

CLASS AA CONCRETE BARRIER RAIL = C.Y. 7.0


CONCRETE BARRIER RAIL = LIN. FT. 50.0




PLAN AT END BENT 1




PLAN AT END BENT 2



SIDE VIEW



END VIEW




SECTION THROUGH RAIL

END OF RAIL DETAILS

PROJECT NO. B-5123
CABARRUS COUNTY
 STATION: 21+44.10 -L-

SHEET 3 OF 3



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

BRIDGE APPROACH SLAB DETAILS

(RIGHT LANE)

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-74
1			3			TOTAL SHEETS
2			4			74

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

ASSEMBLED BY : K. D. LAYNE DATE : 8/25/15
 CHECKED BY : N. D'AIUTO DATE : 11/9/15

01-MAR-2016 10:55
 R:\Structures\Plans\Str02\B5123_SD_AS_02.dgn
 ndaluto

STR. #2