



NOTE 1) UPON REMOVAL OF -NSD2- AND COMPLETION OF THE FINAL PERMANENT DITCH BETWEEN -NSN- AND -CSXN-, JUNCTION BOX 2 SHALL BE REMOVED AND A SEGMENT OF 36" BCCAMP SHALL BE USED TO CONNECT THE ENDS OF THE PROPOSED CULVERTS CONSTRUCTED PREVIOUSLY. ALL MATERIALS, LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE THIS WORK SHALL BE INCLUDED IN THE LUMP SUM PRICE FOR "JUNCTION BOX REMOVAL".

PROJ. REFERENCE NO.	SHEET NO.
U-3308	X-RR4

18+17.41
-NSS-NSN- (FINAL)

