

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

EARTHWORK SUMMARY

IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	EMBT +%	BORROW	WASTE
-L- STA 12+25 TO STA 28+50	1437.7	306	0	1131.7
-Y1- STA 10+91.67 TO STA 19+17	163.9	3131	2967.1	0
-Y1- STA 20+42.28 TO STA 25+14.78	2702	427	0	2275
-Y1- STA 25+84.34 TO STA 26+55	61	45	0	16
-Y2- STA 10+28.50 TO STA 11+73.50	117.3	696	578.7	0
-Y2- STA 13+12.50 TO STA 16+45.75	125	1004	879	0
-Y3- STA 17+40 TO STA 18+10	31.5	5	0	26.5
-Y3A- STA 18+00 TO STA 18+85	63	3	0	60
-Y4- STA 10+50.99 TO STA 15+90	894.6	3	0	891.6
-Y5- STA 10+44.50 TO STA 10+93	235.8	0	0	235.8
ROUNDABOUT	0	1752	1752	0
SUB-TOTAL	5831.8	7372	6176.8	4637
LOSS DUE TO CLEARING AND GRUBBING	-1674	0	1674	0
EARTH WASTE TO REPLACE BORROW	0	0	-4637	-4637
ESTIMATED SHOULDER MATERIAL	0	6	6	0
EST 5% FOR REPLACING TOPSOIL ON BORROW PITS			161	
TOTAL	4158		3381	0
SAY	4160		3390	
STABILIZER AGGREGATE = 3000 TONS				