


**TYPICAL SECTION NO. 2**  
 TO BE USED ON MAPS 1, 12, 15  
 MAP 1: STA. 16+71 TO STA. 43+66  
 STA. 64+86 TO STA. 125+02  
 MAP 6: STA. 85+08 TO STA. 174+09  
 MAP 12: STA. 158+98 TO STA. 219+94  
 MAP 15: STA. 10+00 TO STA. 85+00



**TYPICAL SECTION NO. 3**  
 TO BE USED ON MAPS 1, 6, 12  
 MAP 1: STA. 45+70 TO STA. 64+86  
 STA. 125+02 TO STA. 162+79  
 MAP 6: STA. 10+00 TO STA. 85+08  
 MAP 12: STA. 144+86 TO STA. 158+98

PAVEMENT SCHEDULE	
C1	PROP. APPROX. 1½" S9.5C AT AN AVG. RATE OF 168 LBS PER SQ. YD.
C2	PROP. APPROX. 2" S9.5D AT AN AVG. RATE OF 224 LBS PER SQ. YD.
C3	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVG. RATE OF 168 LBS PER SQ. YD. IN EACH OF TWO LAYERS
C4	PROP. APPROX. ¾" OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-2 MODIFIED, AT AN AVERAGE RATE OF 90 LBS PER SQ. YD.
D	PROP. APPROX. 4½" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 513 LBS. PER SQ. YD. IN ONE LIFT
F1	PROPOSED FOG SEAL TO BE APPLIED TO THE EXISTING ASPHALT SHOULDER
F2	AST MAT COAT, #67 STONE
R	EXISTING CONCRETE STRUCTURE
T	EXISTING EARTH MATERIAL
U1	EXISTING TRAVELWAY
U2	EXISTING PAVED SHOULDER.
V1	1½" MILLING
V2	MILLED RUMBLE STRIP
V3	2" MILLING
V4	4½" MILLING FOR PATCHING
Y	PROPOSED DIAMOND GRINDING

07-JAN-2016 13:48  
 S:\Contracts\Resurfacing Projects\Division 7\1-5734 and 1-5762 Guilford March 2016\5Jan2016\1-5734 & 1-5762 typseals.dgn  
 Author: ALCSD261658