PROJECT NO.	SHEET NO.	TOTAL NO.
I-5734, I-5762	11	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	AGGREGATE SHOULDER BORROW ALLOWED	LENGTH MI	WIDTH FT	REPAIR OF JOINTED CONCRETE PAVEMENT SLAB SY	#57 STONE TON	UNDERCUT CY	CLASS IV SUBGRADE STABILIZATION TON	GEOTEXTILE FOR SOIL STABILIZATION SY	INCIDENTAL STONE BASE TONS	MILLING ASPHALT PAVEMENT, 1½" DEPTH SY	MILLING ASPHALT PAVEMENT, 2"DEPTH SY	ASPHALT CONC SURFACE COURSE, TYPE S9.5C TON	SURFACE COURSE, S9.5D TON	ASPHALT BINDER FOR PLANT MIX TONS	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX TONS	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-2 MODIFIED TON	4-1/2" PATCHING OF EXISTING PAVEMENT TONS	PATCHING CONCRETE PAVEMENT SPALLS SF	ASPHALT SURFACE TREATMENT, MAT COAT, #67 STONE SY	EMULSION FOR ASPHALT SURFACE TREATMENT GAL	FOG SEAL SY	MILLED RUMBLE STRIPS (ASPHALT CONCRETE) (std. 665.01) LF	JOINT CONSTRUCTION, REPAIR AND SEALING LF	DIAMOND GRINDING PCC SY	MILL RUMBLE STRIPS IN CONCRETE SHOULDERS (std. 720.01) LF	PORTABLE LIGHTING LS	TRENCHING (UNPAVED) (1)(2") LF	JUNCTION BOX (STANDARD SIZE) EA	2" RISER W/ WEATHERHEAD EA	INDUCTIVE LOOP SAW CUT LF	LEAD-IN CABLE (14-2) LF
I-5734	Guilford	1	I-40 EB	FROM 1.3 MI. EAST OF SANDY RIDGE RD. TO 1.1 MI. EAST OF GALLIMORE DAIRY RD. (3.96 - 6.86)	1-3	4	MD	NO	NO	YES	2.894	48	74	22	25	67	148										166			33,447	3,922	132,956	104,532	4,614	*					
TOTAL FOR MAP NO. 1											**2.894**		**74**	**22**	**25**	**67**	**148**										**166**			**33,447**	**3,922**	**132,956**	**104,532**	**4,614**						
I-5734	Guilford	2	OFF RAMP TO NC 68	FROM I-40 EB TO NC 68	4	2		NO	NO	YES	0.091	48						65														2,008	850							
		"	"		5	2		NO	NO	YES	0.057	16							535		45		3							268									
		"	"		5	2		NO	NO	YES	0.02	20							235		20		1							94									
		"	"		6	2		NO	NO	YES	0.024	24							338		29		2							84									
		"	"		6	2		NO	NO	YES	0.044	36							929		78		5							155									
		"	"		6	2		NO	NO	YES	0.049	48							1,380		116		7							172									
		"	"		6	2		NO	NO	YES	0.01	67							393		33		2							35					25	1	1	800	400
TOTAL FOR MAP NO. 2											**0.295**							**65**	**3,810**		**321**		**20**							**808**		**2,008**	**850**			**25**	**1**	**1**	**800**	**400**
I-5734	Guilford	3	ON LOOP FROM NC 68	FROM NC 68 TO I-40 EB	6	2		NO	NO	YES	0.003	93						60	164		14		1																
		"	"		6	2		NO	NO	YES	0.013	59							450		38		2							61									
		"	"		5	2		NO	NO	YES	0.098	16							920		78		5							230									
		"	"		7	2		NO	NO	YES	0.04	18							422		36		2																
		"	"		8	2		NO	NO	YES	0.05	18																				845	528							
TOTAL FOR MAP NO. 3											**0.204**							**60**	**1,956**		**166**		**10**							**291**		**845**	**528**							
I-5734	Guilford	4	OFF RAMP TO GALLIMORE DAIRY RD	FROM I-40 EB TO GALLIMORE DAIRY RD	9	2		NO	NO	YES	0.22	16																		1,033		5,514	3,286							
		"	"		5	2		NO	NO	YES	0.013	16							122		10		1																
		"	"		5	2		NO	NO	YES	0.007	28							115		10		1							25									
TOTAL FOR MAP NO. 4											**0.24**								**237**		**20**		**2**							**1,058**		**5,514**	**3,286**							
I-5734	Guilford	5	ON RAMP FROM GALLIMORE DAIRY RD	FROM GALLIMORE DAIRY RD TO I-40 EB	7	2		NO	NO	YES	0.023	18						35	243		21		1							108									
		"	"		8	2		NO	NO	YES	0.184	18																				4,710	2,622							
TOTAL FOR MAP NO. 5											**0.207**							**35**	**243**		**21**		**1**							**108**		**4,710**	**2,622**							
I-5734	Guilford	6	I-40 WB	EAST OF GALLIMORE DAIRY RD. TO 1.3 MI EAST OF SANDY RIDGE RD (22.48 - 25.57)	2,3	2		NO	NO	YES	3.108	84	228	68	76	205	912										145			32,820	2,347	159,759	131,322	5,067						
TOTAL FOR MAP NO. 6											**3.108**		**228**	**68**	**76**	**205**	**912**										**145**			**32,820**	**2,347**	**159,759**	**131,322**	**5,067**						
I-5734	Guilford	7	OFF RAMP TO GALLIMORE DAIRY RD	FROM I-40 WB TO GALLIMORE DAIRY RD	9,10	2		NO	NO	YES	0.103	16																		725		3,519	2,147							
		"	"		9	2		NO	NO	YES	0.019	16							178		15		1							67									
		"	"		9	2		NO	NO	YES	0.005	27							79		7									35									
TOTAL FOR MAP NO. 7											**0.127**								**257**		**22**		**1**							**827**		**3,519**	**2,147**							
I-5734	Guilford	8	ON RAMP FROM GALLIMORE DAIRY RD	FROM GALLIMORE DAIRY RD TO I-40 WB	7	2		NO	NO	YES	0.014	20							164		14		1							49									
		"	"		9	2		NO	NO	YES	0.226	20																		1,061		5,777	3,064							
TOTAL FOR MAP NO. 8											**0.24**								**164**		**14**		**1**							**1,110**		**5,777**	**3,064**							
I-5734	Guilford	9	OFF RAMP TO NC 68	FROM I-40 WB TO NC 68	4	2		NO	NO	YES	0.006	24						23														145	88							
		"	"		15	2		NO	NO	YES	0.044	24								620	70		4							207									
		"	"			2		NO	NO	YES	0.053	24																											
		"	"		15	2		NO	NO	YES	0.015	24								211	24		1							70									
		"	"		15	2		NO	NO	YES	0.031	24								437	49		3							145									
		"	"		15	2		NO	NO	YES	0.027	36								570	64		4							127									
		"	"		15	2		NO	NO	YES	0.01	24								141	16		1							47									
		"	"		15	2		NO	NO	YES	0.057	35								1,170	91		5			60				268					75	1	1	225	200
TOTAL FOR MAP NO. 9											**0.243**							**23**		**3,149**	**314**		**18**			**60**				**864**		**145**	**88**			**75**	**1**	**1**	**225**	**200**
I-5734	Guilford	10	OFF LOOP FROM MAP # 9	FROM MAP # 9 TO REGIONAL RD	7	2		NO	NO	YES	0.019	19							212		19		1							45									
		"	"		7	2		NO	NO	YES	0.094	18							993		84		5							221									
		"	"		11	2		NO	NO	YES	0.009	18							95		8																		
		"	"		11	2		NO	NO	YES	0.005	19							56		5																		
		"	"		11	2		NO	NO	YES	0.009	45							238		20		1													1		535	300
TOTAL FOR MAP NO. 10											**0.136**								**1,594**		**136**		**7**							**266**						**1**		**535**	**300**
I-5734	Guilford	11	ON RAMP FROM NC 68	FROM NC 68 TO I-40 WB	5	2		NO	NO	YES	0.006	93						58	327		28		2							42									
		"	"		5	2		NO	NO	YES	0.019	55							613		52		3							134									
		"	"		5	2		NO	NO	YES	0.038	24							535		45		3							268									
		"	"		5	2		NO	NO	YES	0.066	18							697		59		3							465									
		"	"		4	2		NO	NO	YES	0.034	18																				837	336							
TOTAL FOR MAP NO. 11											**0.163**							**58**	**2,172**		**184**		**11**							**909**		**837**	**336**							
TOTAL FOR PROJ NO. I-5734, 52010.3.1											**7.857**		**302**	**90**	**101**	**272**	**1,060**	**241**	**10,433**	**3,149**	**1,198**		**71**			**60**	**311**			**72,508**	**6,269**	**316,070**	**248,775**	**9,681**	**1**	**100**	**3**	**2**	**1,560**	**900**