

PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.13.03.10571, 2017CPT.13.03.20571, 2017CPT.13.03.20572	13	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E	4457000000-N	4710000000-E	4721000000-E	4725000000-E				4810000000-E		4905000000-N				
										WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	TEMPORARY TRAFFIC CONTROL LS	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS) WHITE LF	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS) SCHOOL EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) LT ARROW EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) MERGE ARROW EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) STR ARROW EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) RT ARROW EA	PAINT PAVEMENT MARKING LINES (4") WHITE LF	PAINT PAVEMENT MARKING LINES (4") YELLOW LF	SNOWPLOWABLE PAVEMENT MARKERS EA				
2017CPT.13.03.10571	Madison	1	NC 63	FROM 1.5 MILES WEST OF SR 1100 TO SR 1162 (MP 4.12 - MP 8.22)	1	2	2WU	4.1	20	1,386	*							86,592	86,592	360				
		2	US 25/70 BUS	FROM NC 251 TO PVMT CHANGE AT MARSHALL (MP 1.47 - MP 3.55)	1	2	2WU	2.08	20										43,930	43,930	140			
		3	NC 251	FROM BRIDGE NO.'S 8 & 9 TO US 25/70 (MP 4.10 - MP 4.91)	1	2	2WU	0.81	44					3	5	5			20,000	20,000	60			
		4	US 25/70	FROM SR 1135 TO SR 1439 (MP 7.34 - MP 10.76)	1	2	2WU	3.42	30			48	12	11					72,230	72,230	230			
		5	NC 213	FROM SR 1611 TO SR 1426 (MP 7.92 - MP 9.92)	1,4,5,6	2	MU	2	42					4	10	4	2		47,520	42,240	264			
TOTAL FOR PROJ NO. 2017CPT.13.03.10571										1,386		48	12	18	15	9	2	270,272	264,992	1,054				
														44			535,264							
2017CPT.13.03.20571	Madison	6	SR 1318	FROM SR 1395 TO SR 1341 (MP 7.94 - MP 12.80)	2	2	2WU	4.86	18	2,414	*							102,643	102,643					
		7	SR 1318	FROM SR 1341 TO SR 1636 (MP 12.80 - MP 18.20)	2	2	2WU	5.4	20											114,048	114,048			
		8	SR 1370	FROM SR 1364 TO SR 1372 (MP 1.28 - MP 4.45)	2	2	2WU	3.17	18											66,950	66,950			
		9	SR 1364	FROM SR 1370 TO SR 1366 (MP 0.00 - MP 3.10)	2	2	2WU	3.1	18												65,472	65,472		
		10	SR 1346	FROM I-26 TO EOM (MP 0.00 - MP 1.30)	2	2	2WU	1.3	18												27,456	27,456		
		11	SR 1624	FROM SR 1604 TO EOM (MP 0.00 - MP 0.33)	2	2	2WU	0.33	20												6,970	6,970		
		12	SR 1604	FROM SR 1582 TO EOM (MP 0.00 - MP 0.45)	2	2	2WU	0.45	20												9,504	9,504		
		13	SR 1180	FROM SR 1181 TO SR 1181 (MP 0.00 - MP 3.23)	2	2	2WU	3.23	20												68,218	68,218		
		14	SR 1431	FROM SR 1346 TO EOP (MP 0.00 - MP 0.21)	3	2	2WU	0.21	19												4,435	4,435		
		TOTAL FOR PROJ NO. 2017CPT.13.03.20571										2,414								465,696	465,696			
																	931,392							
2017CPT.13.03.20572	Madison	15	SR 1374	FROM SR 1375 TO EOP (MP 0.00 - MP 0.60)	3	2	2WU	0.6	18	1,166	*								12,672	12,672				
		16	SR 1376	FROM SR 1375 TO EOP (MP 0.00 - MP 0.20)	3	2	2WU	0.2	18															
		17	SR 1382	FROM SR 1383 TO SR 1380 (MP 0.00 - MP 0.51)	3	2	2WU	0.51	18												10,771	10,771		
		18	SR 1107	FROM SR 1001 TO BUNCOMBE COUNTY LINE (MP 0.00 - MP 2.51)	3	2	2WU	2.51	18												53,011	53,011		
		19	SR 1453	FROM US 25/70 TO US 25/70 (MP 0.00 - MP 0.78)	3	2	2WU	0.78	20												16,474	16,474		
		20	SR 1622	FROM SR 1509 TO EOM (MP 0.00 - MP 0.20)	3	2	2WU	0.2	18															
		21	SR 1152	FROM SR 1153 TO EOP (MP 0.00 - MP 0.61)	3	2	2WU	0.61	18															
		22	SR 1153	FROM SR 1151 TO SR 1152 (MP 0.00 - MP 0.37)	3	2	2WU	0.37	18															
		23	SR 1375	FROM SR 1370 TO EOP (MP 0.00 - MP 1.85)	3	2	2WU	1.85	18													39,072	39,072	
		24	SR 1457	FROM US 23A TO SR 1503 (MP 0.00 - MP 0.40)	3	2	2WU	0.4	18													16,896	16,896	
25	SR 1136	SR 1135 TO SR 1203 (MP 1.10 - MP1.55)	3	2	2WU	0.45	19											9,504	9,504					
TOTAL FOR PROJ NO. 2017CPT.13.03.20572										1,166								158,400	158,400					
																	316,800							
GRAND TOTAL									42.94	4,966	1	48	12	18	15	9	2	894,368	889,088	1,054				
														44			1,783,456							