PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.13.06.10811, ETC.	15	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/ GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4695000000-E THERMO PAVEMENT MARKING LINES (8", 90 MILS) WHITE LF	4695000000-E THERMO PAVEMENT MARKING LINES (8", 90 MILS) YELLOW LF	4700000000-E THERMO PAVEMENT MARKING LINES (12", 90 MILS) YELLOW LF	4705000000-E THERMO PAVEMENT MARKING LINES (16", 120 MILS) WHITE LF	4710000000-E THERMO PAVEMENT MARKING LINES (24", 120 MILS) WHITE LF	4721000000-E THERMO PAVEMENT MARKING CHARACTER (120 MILS) RXR EA	4721000000-E THERMO PAVEMENT MARKING CHARACTER (120 MILS) SCHOOL EA	4725000000-E THERMO PAVEMENT MARKING SYMBOL (90 MILS) LT ARROW EA	4725000000-E THERMO PAVEMENT MARKING SYMBOL (90 MILS) RT ARROW EA	4725000000-E THERMO PAVEMENT MARKING SYMBOL (90 MILS) STR ARROW EA	4725000000-E THERMO PAVEMENT MARKING SYMBOL (90 MILS) STR & LT ARROW EA	4725000000-E THERMO PAVEMENT MARKING SYMBOL (90 MILS) STR & RT ARROW EA	4725000000-E THERMO PAVEMENT MARKING SYMBOL (90 MILS) MERGE ARROW EA	4810000000-E PAINT PAVEMENT MARKING LINES (4") WHITE LF	4810000000-E PAINT PAVEMENT MARKING LINES (4") YELLOW LF	4905000000-N SNOW-PLOWABLE PAVEMENT MARKERS EA
2017CPT.13.06.10811	Rutherford	1	US 74 A EBL	FROM US 221 ALT TO US 74 (MP 24.59 - MP 30.16)	1,5,6	2	MD	5.57	32	1,250	*	200	140	100		610			37	16	8	1	2		87,000	117,638	675
		2	US 74 A WBL	FROM US 74 TO US 221 ALT (MP 0.48 - MP 6.03)	1,5,6	2	MD	5.55	32			600	250	570		815			27	22	5		2	3	87,600	117,216	650
TOTAL FOR PROJ NO. 2017CPT.13.06.10811								**11.12**		**1,250**	**1**	**800**	**390**	**670**		**1,425**			**64**	**38**	**13**	**1**	**4**	**3**	**174,600**	**234,854**	**1,325**
												1,190							**123**						**409,454**		
2017CPT.13.06.20811	Rutherford	3	SR 1006	FROM SR 1745 TO SR 1744 (MP 8.38 - MP 10.33)	2	2	2WU	1.95	22																41,184	41,184	175
		4	SR 1111	FROM SC STATE LINE TO US 221 (MP 0.00 - MP 5.93)	2	2	2WU	5.93	19				500		45	30	2		2						125,542	125,242	
		5	SR 1749	FROM SR 1006 TO US 74 BUS (MP 0.00 - MP 14.58)	2	2	2WU	14.58	19							40		12							307,930	307,930	
		6	SR 1762	FROM SR 1788 TO US 74 BUS (MP 2.66 - MP 6.23)	2	2	2WU	3.57	20																75,398	75,398	
		7	SR 1351	FROM BRIDGE NO. 62 TO US 221 (MP 1.06 - MP 4.80)	2	2	2WU	3.74	19																78,989	78,989	
		8	SR 1565	FROM SR 1006 TO DEAD END (MP 1.78 - MP 2.27)	3	2	2WU	0.49	18																10,349	10,349	
		9	SR 1606	FROM SR 1595 TO SR 1609 (MP 0.00 - MP 0.40)	3	2	2WU	0.4	18																		
		10	SR 1609	FROM SR 1606 TO EOM (MP 0.00 - MP 0.18)	3	2	2WU	0.18	18																		
		11	SR 1613	FROM SR 1574 TO EOM (MP 0.00 - MP 0.19)	3	2	2WU	0.19	18																		
		12	SR 1621	FROM SR 1574 TO DEAD END (MP 0.00 - MP 0.29)	3	2	2WU	0.29	17																		
		13	SR 1622	FROM SR 1621 TO EOM (MP 0.00 - MP 0.23)	3	2	2WU	0.23	18																		
		14	SR 1790	FROM SR 1770 TO DEAD END (MP 0.00 - MP 0.59)	3	2	2WU	0.59	18																		
		15	SR 1803	FROM US 74 BUS TO SR 1784 (MP 0.00 - MP 0.28)	3	2	2WU	0.28	16																		
		16	SR 1804	FROM SR 1782 TO DEAD END (MP 0.00 - MP 0.36)	3	2	2WU	0.36	17																		
		17	SR 1805	FROM SR 1803 TO EOM (MP 0.00 - MP 0.18)	3	2	2WU	0.18	17																		
		18	SR 1813	FROM SR 1805 TO SR 1804 (MP 0.00 - MP 0.16)	3	2	2WU	0.16	18																		
		19	SR 1913	FROM US 74 BUS TO SR 1920 (MP 0.00 - MP 3.64)		2	2WU	3.64	18																		
		20	SR 1915	FROM SR 1917 TO SR 1916 (MP 0.00 - MP 0.43)		2	2WU	0.43	18																		
		21	SR 1916	FROM SR 1980 TO SR 1983 (MP 0.93 - MP 2.67)		2	2WU	1.74	18																		
		22	SR 1918	FROM SR 1917 TO PVMT CHANGE (MP 0.00 - 0.20)		2	2WU	0.2	18	3,724	*																
		23	SR 1924	FROM CLEVELAND COUNTY LINE TO NC 120 (MP 0.00 - MP 0.17)		2	2WU	0.17	18																		
		24	SR 1925	FROM CLEVELAND COUNTY LINE TO SR 1926 (MP 0.00 - MP 0.20)		2	2WU	0.2	19																		
		25	SR 1926	FROM NC 120 TO NC 120 (MP 0.00 - MP 1.53)		2	2WU	1.53	19.5																		
		26	SR 1927	FROM CLEVELAND COUNTY LINE TO SR 1926 (MP 0.00 - MP 0.23)		2	2WU	0.23	20																		
		27	SR 1928	FROM CLEVELAND COUNTY LINE TO SR 1990 (MP 0.00 - MP 0.21)		2	2WU	0.21	19																		
		28	SR 1929	FROM CLEVELAND COUNTY LINE TO SR 1990 (MP 0.00 - MP 0.37)		2	2WU	0.37	18																		
		29	SR 1943	FROM SR 1942 TO SR 1935 (MP 0.37 - MP 1.10)		2	2WU	0.73	18																		
		30	SR 1980	FROM SR 1916 TO SR 1917 (MP 0.00 - MP 0.20)		2	2WU	0.2	18																		
		31	SR 1982	FROM CLEVELAND COUNTY LINE TO SR 1921 (MP 0.00 - MP 1.77)		2	2WU	1.77	20																		
		32	SR 1983	FROM US 74 BUS TO SR 1913 (MP 0.00 - MP 1.31)		2	2WU	1.31	18																		
		33	SR 1990	FROM NC 120 TO NC 120 (MP 0.00 - MP 1.71)		2	2WU	1.71	19																		
		34	SR 2016	FROM SR 1913 TO EOM (MP 0.00 - MP 0.21)		2	2WU	0.21	18																		
		35	SR 2101	FROM US 221 ALT TO SR 2102 (MP 0.31 - MP 0.63)		2	2WU	0.32	20																		
		36	SR 2108	FROM SR 2102 TO DEAD END (MP 0.00 - MP 0.60)		2	2WU	0.6	18.5																		
		37	SR 2116	FROM SR 2210 TO SR 2117 (MP 0.00 - MP 1.60)		2	2WU	1.6	19																		
		38	SR 2128	FROM SR 2129 TO SR 2129 (MP 0.00 - MP 0.81)		2	2WU	0.81	17																		
		39	SR 2142	FROM SR 2129 TO SR 2143 (MP 0.00 - MP 1.31)		2	2WU	1.31	18.5																		
		40	SR 2147	FROM SR 2210 TO SR 2146 (MP 0.00 - MP 0.58)		2	2WU	0.58	18																		
		41	SR 2211	FROM US 221 TO SR 2116 (MP 0.00 - MP 1.31)		2	2WU	1.31	18																		
TOTAL FOR PROJ NO. 2017CPT.13.06.20811								**54.3**		**3,724**	**1**		**500**		**45**	**70**	**2**	**12**	**2**						**639,392**	**639,092**	**175**
												500					**14**		**2**						**1,278,484**		
2017CPT.13.06.20812	Rutherford	42	SR 1913	FROM US 74 BUS TO SR 1920 (MP 0.00 - MP 3.64)	4	2	2WU	3.64	18																76,877	76,877	
		43	SR 1915	FROM SR 1917 TO SR 1916 (MP 0.00 - MP 0.43)	4	2	2WU	0.43	18																9,082	9,082	
		44	SR 1916	FROM SR 1980 TO SR 1983 (MP 0.93 - MP 2.67)	4	2	2WU	1.74	18																36,749	36,749	
		45	SR 1918	FROM SR 1917 TO PVMT CHANGE (MP 0.00 - 0.20)	4	2	2WU	0.2	18																4,224	4,224	
		46	SR 1924	FROM CLEVELAND COUNTY LINE TO NC 120 (MP 0.00 - MP 0.17)	4	2	2WU	0.17	18																3,590	3,590	
		47	SR 1925	FROM CLEVELAND COUNTY LINE TO SR 1926 (MP 0.00 - MP 0.20)	4	2	2WU	0.2	19																4,224	4,224	
		48	SR 1926	FROM NC 120 TO NC 120 (MP 0.00 - MP 1.53)	4	2	2WU	1.53	19.5																32,314	32,314	
		49	SR 1927	FROM CLEVELAND COUNTY LINE TO SR 1926 (MP 0.00 - MP 0.23)	4	2	2WU	0.23	20																4,858	4,858	
		50	SR 1928	FROM CLEVELAND COUNTY LINE TO SR 1990 (MP 0.00 - MP 0.21)	4	2	2WU	0.21	19																4,435	4,435	
		51	SR 1929	FROM CLEVELAND COUNTY LINE TO SR 1990 (MP 0.00 - MP 0.37)	4	2	2WU	0.37	18																7,814	7,814	
		52	SR 1943	FROM SR 1942 TO SR 1935 (MP 0.37 - MP 1.10)	4	2	2WU	0.73	18																15,418	15,418	
		53	SR 1980	FROM SR 1916 TO SR 1917 (MP 0.00 - MP 0.20)	4	2	2WU	0.2	18	2,394	*														4,224	4,224	
		54	SR 1982	FROM CLEVELAND COUNTY LINE TO SR 1921 (MP 0.00 - MP 1.77)	4	2	2WU	1.77	20						45	20	2								37,382	37,382	
		55	SR 1983	FROM US 74 BUS TO SR 1913 (MP 0.00 - MP 1.31)	4	2	2WU	1.31	18																27,667	27,667	
		56	SR 1990	FROM NC 120 TO NC 120 (MP 0.00 - MP 1.71)	4	2	2WU	1.71	19																36,115	36,115	
		57	SR 2016	FROM SR 1913 TO EOM (MP 0.00 - MP 0.21)	4	2	2WU	0.21	18																4,435	4,435	
		58	SR 2101	FROM US 221 ALT TO SR 2102 (MP 0.31 - MP 0.63)	4	2	2WU	0.32	20																6,758	6,758	
		59	SR 2108	FROM SR 2102 TO DEAD END (MP 0.00 - MP 0.60)	4	2	2WU	0.6	18.5						90	60	4										
		60	SR 2116	FROM SR 2210 TO SR 2117 (MP 0.00 - MP 1.60)	4	2	2WU	1.6	19																33,792	33,792	
		61	SR 2128	FROM SR 2129 TO SR 2129 (MP 0.00 - MP 0.81)	4	2	2WU	0.81	17																17,107	17,107	
		62	SR 2142	FROM SR 2129 TO SR 2143 (MP 0.00 - MP 1.31)	4	2	2WU	1.31	18.5																27,667	27,667	
		63	SR 2147	FROM SR 2210 TO SR 2146 (MP 0.00 - MP 0.58)	4	2	2WU	0.58	18																12,250	12,250	
		64	SR 2211	FROM US 221 TO SR 2116 (MP 0.00 - MP 1.31)	4	2	2WU	1.31	18																27,667	27,667	
TOTAL FOR PROJ NO. 2017CPT.13.06.20812								**21.18**		**2,394**	**1**				**135**	**80**	**6**								**434,649**	**434,649**	
																	6								**869,298**		
GRAND TOTAL								**86.6**		**7,368**	**1**	**800**	**890**	**670**	**180**	**1,575**	**8**	**12**	**66**	**38**	**13**	**1**	**4**	**3**	**1,248,641**	**1,308,595**	**1,500**
												1,690					**20**		**125**						**2,557,236**		