

PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.14.01.10441.1 ETC	24	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	SHOULDER RECONSTRUCTION SMI	3" MILLING SY	1 1/2" MILLING SY	4 1/2" MILLING SY	INTERMEDIATE COURSE, I19.0B TONS	INTERMEDIATE COURSE, I19.0C TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	SURFACE COURSE, SF9.5A TONS	LEVELING COURSE, SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE) CENTER LANE LF	ADJ. OF METER OR VALVE BOX EA	PORTABLE LIGHTING LS	INDUCTIVE LOOP SAWCUT LF	LEAD-IN CABLE (14-2) LF		
2017CPT.14.01.10501.1	Jackson	1	US 441	FROM US 74 TO SWAIN COUNTY LINE	1	5	MU	YES	NO	4.29	60			36,200	133,000		29,042		13,955				2,220				2,600		1,592	842
TOTAL FOR MAP NO. 1										4.29				36,200	133,000		29,042		13,955				2,220				2,600		1,592	842
2017CPT.14.01.10501.1	Jackson	2	US 441 RAMP	FROM US 74 EAST BOUND TO US 441 NORTH BOUND	2	1		NO	NO	0.25	26	0.50	4,200				717		372				56							
TOTAL FOR MAP NO. 2										0.25		0.50	4,200				717		372				56							
2017CPT.14.01.10501.1	Jackson	3	US 441 RAMP	FROM US 441 TO US74 WEST BOUND	2	1		NO	NO	0.19	25	0.38	3,060				525		274				41							
TOTAL FOR MAP NO. 3										0.19		0.38	3,060				525		274				41							
2017CPT.14.01.10501.1	Jackson	4	US 441 RAMP	FROM US 74 WEST BOUND TO US 441 NORTH BOUND	2	1		NO	NO	0.17	25	0.34	2,750				469		248				37							
TOTAL FOR MAP NO. 4										0.17		0.34	2,750				469		248				37							
TOTAL FOR PROJ NO. 2017CPT.14.01.10501.1										4.9		1.22	10,010	36,200	133,000		30,753		14,849				2,354				2,600		1,592	842
2017CPT.14.01.10871.1	Swain	5	US 441	FROM JACKSON LINE TO US 19	1	5	MU	YES	NO	0.7	60			5,900	23,600		4,065		2,502				343						624	814
TOTAL FOR MAP NO. 5										0.7				5,900	23,600		4,065		2,502				343					624	814	
TOTAL FOR PROJ NO. 2017CPT.14.01.10871.1										0.7				5,900	23,600		4,065		2,502				343				624	814		
2017CPT.14.01.20501.1	Jackson	6	SR-1789	FROM SR-1449 TO END OF STATE MAINT.	7	2	2WU	NO	NO	0.07	12	0.14								39	31		4							
TOTAL FOR MAP NO. 6										0.07		0.14								39	31		4							
2017CPT.14.01.20501.1	Jackson	7	SR-1367	FROM SR-1324 TO SR-1551	9	2	2WU	NO	NO	1.55	19	3.10								1,314			88	150						
TOTAL FOR MAP NO. 7										1.55		3.10								1,314			88	150						
2017CPT.14.01.20501.1	Jackson	8	SR-1701	FROM SR-1700 DEAD END	7	2	2WU	NO	NO	0.93	18	1.86								747	280		67							
TOTAL FOR MAP NO. 8										0.93		1.86								747	280		67							
2017CPT.14.01.20501.1	Jackson	9	SR-1355	FROM .07 MILES SOUTH OF NC107 TO END OF PAVE.	9	2	2WU	NO	NO	0.23	18	0.46								185			12	100						
TOTAL FOR MAP NO. 9										0.23		0.46								185			12	100						
2017CPT.14.01.20501.1	Jackson	10	SR-1393	FROM SR-1392 TO END OF PAVE	7	2	2WU	NO	NO	2.15	18	4.30								1,727	658		155	200						
TOTAL FOR MAP NO. 10										2.15		4.30								1,727	658		155	200						
2017CPT.14.01.20501.1	Jackson	11	SR-1111	FROM SR-1112 TO SR-1110	7	2	2WU	NO	NO	0.22	20	0.44								196	71		17	25						
TOTAL FOR MAP NO. 11										0.22		0.44								196	71		17	25						
2017CPT.14.01.20501.1	Jackson	12	SR-1110	FROM SR-1111 TO END OF STATE MAINT.	7	2	2WU	NO	NO	0.38	20	0.76								339	121		30	75						
TOTAL FOR MAP NO. 12										0.38		0.76								339	121		30	75						
2017CPT.14.01.20501.1	Jackson	13	SR-1360	FROM NC 116 TO US 23/441	7	2	2WU	NO	NO	2.39	18	4.78								1,920	250		144	430						
TOTAL FOR MAP NO. 13										2.39		4.78								1,920	250		144	430						
2017CPT.14.01.20501.1	Jackson	14	SR-1142	FROM PVT CHG .01 MILES SOUTH OF NC 107 TO END OF PAVE.	7	2	2WU	NO	NO	1.25	20	2.50								1,115	398		99	250						
TOTAL FOR MAP NO. 14										1.25		2.50								1,115	398		99	250						
2017CPT.14.01.20501.1	Jackson	15	SR-1367	FROM NC 116 TO SR-1321	9	2	2WU	NO	NO	0.85	19	1.70								720			48	160						
TOTAL FOR MAP NO. 15										0.85		1.70								720			48	160						
2017CPT.14.01.20501.1	Jackson	16	SR-1118	FROM NC 107 TO END OF PAVEMENT	7	2	2WU	NO	NO	0.75	18	1.50								602	209		53	100						
TOTAL FOR MAP NO. 16										0.75		1.50								602	209		53	100						
2017CPT.14.01.20501.1	Jackson	21	SR-1336	FROM SR-1002 TO END OF MAINT.	7	2	2WU	NO	NO	1.13	18	2.26								944	731		107	460						
TOTAL FOR MAP NO. 21										1.13		2.26								944	731		107	460						
2017CPT.14.01.20501.1	Jackson	22	SR-1337	FROM SR-1336 TO END OF MAINT.	4	2	2WU	NO	NO	0.79	18	1.58	8,342			1,562				660			119							
TOTAL FOR MAP NO. 22										0.79		1.58	8,342			1,562				660			119							
TOTAL FOR PROJ NO. 2017CPT.14.01.20501.1										12.69		25.38	8,342			1,562				10,508	2,749		943	1,950						
2017CPT.14.01.10441.1	Haywood	17	NC 215	FROM SR-1636 TO 850' SOUTH UNDER I-40	3	3	MU	NO	NO	0.16	36	0.32	3,600				669		295				50				1			
TOTAL FOR MAP NO. 17										0.16		0.32	3,600				669		295				50				1			
TOTAL FOR PROJ NO. 2017CPT.14.01.10441.1										0.16		0.32	3,600				669		295				50				1			
2017CPT.14.01.20441.1	Haywood	18	SR-1812	FROM SR-1818 TO US276	8	2	2WU	NO	NO	1.41	24	2.82							1,877				113	175						
TOTAL FOR MAP NO. 18										1.41		2.82							1,877				113	175						
2017CPT.14.01.20441.1	Haywood	19	SR-1929	FROM US 23 BUS TO SR-1800	5	2	2WU	NO	NO	1.59	24	3.10	13,000	2,000		2,779				2,079			258			5		1,380	250	
TOTAL FOR MAP NO. 19										1.59		3.10	13,000	2,000		2,779				2,079			258			5		1,380	250	
2017CPT.14.01.20441.1	Haywood	20	SR-1818	FROM US 23 BUS TO CLYDE CITY LIMITS	6	2	2WU	NO	NO	4.75	20	9.50	25,266			4,315				5,276			524	250		1				
TOTAL FOR MAP NO. 20										4.75		9.50	25,266			4,315				5,276			524	250		1				
TOTAL FOR PROJ NO. 2017CPT.14.01.20441.1										7.75		15.42	38,266	2,000		7,094				9,232			895	425		6		1,380	250	
GRAND TOTAL										26.2		42.34	60,218	44,100	156,600		8,656		35,487	9,232	17,646	10,508	2,749	4,585	2,375	2,600	6	1		