

PROJECT NO.	SHEET NO.
2017CPT.03.01.10651, Etc.	15

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	AGGREGATE SHOULDER BORROW TON	SHOULDER RECONST. SMI	2 1/2" MILLING SY	1 1/2" MILLING SY	INC. MILLING SY	INT. COURSE, 119.0B TONS	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TON	ASPHALT PLANT MIX, PAVEMENT REPAIR TON	PATCHING EXISTING PAVEMENT (FULL DEPTH) TON	PATCHING EXISTING PAVEMENT (MILL) TON	FINE MILLING (0"-1.5") SY	2'-6" CONCRETE CURB & GUTTER LF
2017CPT.03.01.10651	NewHanover	1 - 10	US 117 / NC 132 (COLLEGE RD.)	(TRAFFIC CONTROL/LIGHTING)	N/A			NO	NO	N/A														
		TOTAL FOR MAP NO. 0								N/A														
2017CPT.03.01.10651	New Hanover	1	US 117 / NC 132 NB (COLLEGE RD.)	FROM .05 MILES PAST CEDAR AVE. TO US 17 (MARKET STREET BRIDGE)	1 - 3	3 - 4	2WD	NO	NO	1.763	36 - 48	20	1.02			500		4,445	267.00	10	25	70	13,338	
		TOTAL FOR MAP NO. 1								1.763		20	1.02			500		4,445	267.00	10	25	70	13,338	
2017CPT.03.01.10651	NewHanover	2	US 117 / NC 132 SB (COLLEGE RD.)	FROM US 17 (MARKET STREET BRIDGE) TO .05 MILES FROM CEDAR AVE.	1 - 3, 6	3 - 4	2WD	NO	NO	1.763	36 - 48	20	1.02	11,942	2,800	500	1,945	4,923	389.00	10	25	75	11,466	30
		TOTAL FOR MAP NO. 2								1.763		20	1.02	11,942	2,800	500	1,945	4,923	389.00	10	25	75	11,466	30
2017CPT.03.01.10651	NewHanover	3	US 117/ NC 132 NB EXIT RAMP	FROM 117NB TO MAP 4 (MP 0.000 - 0.175)	4	1	2WD	NO	NO	0.175	24	5	0.35			50		218	13.00			5		
		TOTAL FOR MAP NO. 3								0.175		5	0.35			50		218	13.00			5		
2017CPT.03.01.10651	New Hanover	4	US 117/ NC 132 NB ENTRANCE/EXIT RAMP	FROM MARKET ST. TO MAPS 3&5 (MP 0.000 - .133)	6	3	2WD	NO	NO	0.133	60							414	25.00			5		
		TOTAL FOR MAP NO. 4								0.133								414	25.00			5		
2017CPT.03.01.10651	New Hanover	5	US 117/ NC 132 NB ENTRANCE RAMP	FROM MAP 4 TO US 117 NB (MP 0.000 - 0.109)	5	1	2WD	NO	NO	0.109	22	5	0.11			1,407		125	7.00			5		
		TOTAL FOR MAP NO. 5								0.109		5	0.11			1,407		125	7.00			5		
2017CPT.03.01.10651	New Hanover	6	US 117/ NC 132 SB EXIT RAMP	FROM 117SB TO MAP 7 (MP 0.000 - 0.063)	4	1	2WD	NO	NO	0.063	22	5	0.13					72	4.00			5		
		TOTAL FOR MAP NO. 6								0.063		5	0.13					72	4.00			5		
2017CPT.03.01.10651	New Hanover	7	US 117/ NC 132 SB ENTRANCE/EXIT RAMP	FROM MAPS 6&8 TO MARKET ST. (MP 0.000 - 0.078)	6	3	2WD	NO	NO	0.078	60					2,746		243	15.00		5	5		
		TOTAL FOR MAP NO. 7								0.078						2,746		243	15.00		5	5		
2017CPT.03.01.10651	New Hanover	8	US 117/ NC 132 SB ENTRANCE RAMP	FROM MAP 7 TO US 117 SB (MP 0.000 - 0.161)	4	1	2WD	NO	NO	0.161	24	5	0.32			50		201	12.00			5		
		TOTAL FOR MAP NO. 8								0.161		5	0.32			50		201	12.00			5		
2017CPT.03.01.10651	New Hanover	9	W-5203AA (RESURF QYTS ONLY)	SB FROM MP 10.198 TO MP 10.598 & NB FROM MP 4.959 TO MP 5.359	SEE W-5203AA PLANS (PART I)	3	MD	NO	NO	0.4	36						1,264	2,040	183.00	10			10,500	
		TOTAL FOR MAP NO. 9								0.4							1,264	2,040	183.00	10			10,500	
2017CPT.03.01.10651	New Hanover	10	W-5601BB (RESURF QYTS ONLY)	NB FROM MP 6.209 TO 6.256 & SB FROM MP 9.301 TO MP 9.348	SEE W-601BB PLANS (PART II)	3	MD	NO	NO	0.047	36						99	390	28.00				2,190	
		TOTAL FOR MAP NO. 10								0.047							99	390	28.00				2,190	
		TOTAL FOR PROJ NO. 2017CPT.03.01.10651								4.692		60	2.95	21,050	11,635	1,100	3,308	13,071	943.00	30	55	175	37,494	30
36249.3622	NewHanover	11	INTERSECTION OF US 117/ NC 132 (COLLEGE RD.) & SR 2313 (WILSHIRE BLVD.)	NB FROM MP 4.792 TO MP 4.812 & SB FROM MP 10.748 TO MP 10.768	N/A	3	MD	NO	NO	0.02	36													
		TOTAL FOR MAP NO. 11								0.02														
		TOTAL FOR PROJ NO. 36249.3622								0.02														
		GRAND TOTAL								4.712		60	2.95	21,050	11,635	1,100	3,308	13,071	943.00	30	55	175	37,494	30