

COMPUTED BY: Jacob C. Wessell, PE DATE: 8/28/2015
 CHECKED BY: Steven V. Hudson, LG DATE: 8/28/2015

PROJECT NO. SHEET NO.
 40233.1.1 (B-4929) 3G-1

**STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS**

SUMMARY OF SUBSURFACE DRAINAGE

LINE	Station	Station	Location LT/RT/CL	Drain Type* UD/BD/SD	LF
			CONTINGENCY	SD	1000
				TOTAL LF:	1000

*UD = Underdrain
 *BD = Blind Drain
 *SD = Subsurface Drain

**SUMMARY OF
 BRIDGE WAITING PERIODS**

Bridge Description	End Bent/ Bent No.	MONTHS
Bridge 16	1	1
Bridge 16	2	1

SUMMARY OF AGGREGATE SUBGRADE/STABILIZATION

LINE	Station	Station	Aggregate Type ASU/AST	Aggregate Thickness INCHES	Shallow Undercut CY	Class IV Subgrade Stabilization TONS	Geotextile for Soil Stabilization SY	Stabilizer Aggregate TONS	Class IV Aggregate Stabilization TONS
			CONTINGENCY	ASU	1000	1900	3000		
					TOTAL CY/TONS/SY:	1000	1900	3000*	0

ASU = Aggregate Subgrade, AST = Aggregate Stabilization

*Total square yards of Geotextile for Soil Stabilization is only the estimated quantity for ASU/AST and may only represent a portion of the geotextile quantity shown in the Item Sheets of the Proposal.