SCALE: 1" = 10'

10'   10'

SCALE OF MAP MAY VARY
DUE TO METHODS OF REPRODUCTION.

BEFORE YOU DIG!
NC ONE CALL
(TOLL FREE)

811

(OR 1-800-632-4949)
IT'S THE LAW!

CRABBY MIKE'S

NOW OR FORMERLY
HENDY MICHAEL et al
D.B. 2784, PG 214

NAD 83 2007

S. NEW RIVER DR.

UTILITY CONSTRUCTION

MATCHLINE 2+60
SEE SHEET UC-18

24" ABANDON
8" UTILITY PIPE

ABANDON
UTILITY MANHOLE
RIM 4.25'
INV. IN -5.72'
INV. OUT -5.72'

EXISTING MANHOLE
RIM 4.56'
INV. IN -5.63'
INV. OUT -5.63'

MH-3
STA. 2+25
RIM 5.86
INV. IN -4.08' (EXISTING 10")
INV. IN -5.07' (PROPOSED 12")
INV. OUT -5.07'
4' DIA. UTILITY MANHOLE
4.93' UTILITY MANHOLE WALL 4' DIA.

PROPOSED 12" FORCE MAIN SEWER
SEE SHEET UC-21

PROPOSED 8" FORCE MAIN SEWER
SEE SHEET UC-24

PROPOSED 20 L.F. OF
12" GRAVITY SANITARY
SEWER @ 0.25%

PROPOSED 41 L.F. OF
12" GRAVITY SANITARY
SEWER @ 0.25%

KINSTON AVE.

5' MIN.
(TYP.)

MH-1
STA. 0+00
RIM 4.43
INV. IN -5.53'
INV. OUT -5.53'
4' DIA. UTILITY MANHOLE
3.96' UTILITY MANHOLE WALL 4' DIA.

PROPOSED 164 L.F. OF
12" GRAVITY SANITARY
SEWER @ 0.25%

MH-2
STA. 2+05
RIM 6.18
INV. IN -5.12'
INV. OUT -5.12'
4' DIA. UTILITY MANHOLE
5.30' UTILITY MANHOLE WALL 4' DIA.

S0+50 S0+60 S0+70 S0+80 S0+90 S1+00 S1+10 S1+20 S1+30 S1+40 S1+50 S1+60 S1+70 S1+80 S1+90 S2+00

12" FSS / 8" FSS

NOTE: TOPOGRAPHICAL INFORMATION PROVIDED BY NCDOT

ISLAND GRAVITY SEWER STA. 0+00 TO 2+60

HORIZONTAL: 1" = 10'
VERTICAL: 1" = 5'

EXISTING MANHOLE
RIM 4.56'
INV. IN -5.63'
INV. OUT -5.63'

MH-1
STA. 0+00
RIM 4.43
INV. IN -5.53'
INV. OUT -5.53'

MH-2
STA. 2+05
RIM 6.18
INV. IN -5.12'
INV. OUT -5.12'

MH-3
STA. 1+88
RIM 6.06
INV. IN -4.28' (EXISTING 10")
INV. IN -5.16' (PROPOSED 12")
INV. OUT -5.16'

PROPOSED
GRADE

EXISTING
GRADE

EXISTING
UNDERGROUND
CABLE

EXISTING FIBER
OPTIC LINE

EXISTING
TV FIBER
OPTIC LINE

EXISTING FIBER OPTIC LINE

EXISTING TV FIBER
OPTIC LINE

EXISTING TV FIBER
OPTIC LINE

3' MIN.
(TYP.)

MATCHLINE 2+60
SEE SHEET UC-18

EXISTING
TELEPHONE
FIBER
OPTIC LINE

EXISTING
TELEPHONE
FIBER OPTIC LINE

EXISTING
FIBER
OPTIC
LINES

EXISTING
TV FIBER
OPTIC LINE

EXISTING WATER
SERVICE LINES

EXISTING
TELEPHONE LINES

EXISTING
TELEPHONE
LINE

PROPOSED 41 L.F. OF
12" GRAVITY SANITARY
SEWER @ 0.25%

PROPOSED 12" FORCE MAIN SEWER
SEE SHEET UC-21

PROPOSED 8" FORCE MAIN SEWER
SEE SHEET UC-24

PROPOSED 164 L.F. OF
12" GRAVITY SANITARY
SEWER @ 0.25%

EXISTING
TELEPHONE
LINES

PROPOSED 20 L.F. OF
12" GRAVITY SANITARY
SEWER @ 0.25%

EXISTING 10" FORCE
MAIN SEWER

EXISTING TELEPHONE
FIBER OPTIC LINE

EXISTING FIBER
OPTIC LINE

0+00 0+20 0+40 0+60 0+80 1+00 1+20 1+40 1+60 1+80 2+00 2+20 2+40 2+60

15 / 10 / 5 / 0 / -5 / -10