



PLAN OF FLOOR SLAB - STAGE III & PARTIAL PLAN OF FLOOR SLAB - STAGE IV

THE 48" Ø AND 15" Ø R.C. PIPES THROUGH THE SIDEWALLS OF THE CULVERT SHALL BE LOCATED BY THE ENGINEER. THE REINFORCING STEEL SHALL BE FIELD BENT AS NECESSARY TO CLEAR PIPE. SEE DETAILS ON SHEET 15 OF 18.

PROJECT NO. B-4490
CUMBERLAND COUNTY
 STATION: 19+26.42 -L-

SHEET 10 OF 18



DocuSigned by:
 Kristy W. Alford
 3/29/2016

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
TRIPLE 14 FT. X 9 FT. CONCRETE BOX CULVERT					
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
SHEET NO. C-10					TOTAL SHEETS 18

DRAWN BY : I.L. AVERETTE DATE : 07-15
 CHECKED BY : J.P. ADAMS DATE : 08-15
 DESIGN ENGINEER OF RECORD: I.L. AVERETTE DATE : 09-15

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED